Boeing Technical Report D210-10506-1
October 1972

Aerial Artillery Design Study

Two Externally Mounted XM204 Howitzers
on a CH-47C Helicopter

## DOCUMENT CONTROL DATA - R & D

(Security classification of title, body of abstract and indexing annotation must be entered when the overall report is classified)

1. ORIGINATING ACTIVITY (Corporate author)	2a. REPORT SECURITY CLASSIFICATION
The Boeing Company, Vertol Division Philadelphia, Pennsylvania 19142	Unclassified
	2b. GROUP None

3. REPORT TITLE

Aerial Artillery Design Study Two Externally-Mounted XM 204 Howitzers on a CH-47C Helicopter

4. DESCRIPTIVE NOTES (Type of report and inclusive dates)

Twelve Part Final Report

5. AUTHOR(S) (First name, middle initial, last name) Alfred Bonnell-Design; Steve S.S. Dallas-Performance; Robert P. Giantonio-Vibration/Dynamics; Leo Gumienny-Integration; Edward H. Higgins-Stress Analysis; Norman I. Klavens-Muzzle Blast; Arthur MacArthur-Missions; Albert B. Meyer-Aeroelasticity; Henry J. Neeb-Flying Qualities; English Piper-Fire Control; Richard R. Pruyn-Summary; Richard D. Semple-Propulsion; Maurice E. Snook-Weights.

6. REPORT DATE	7a. TOTAL NO. OF PAGES	7b. NO. OF REFS
October 1972	xxvi + 224	25

8a. CONTRACT OR GRANT NO. DAAF03-72-C-0016	9a. ORIGINATOR'S REPORT NUMBER(S)
b. PROJECT NO.	D210-10506-1
c.	9b. OTHER REPORT NO(S) (Any other numbers that may be assigned this report)
d.	None

10. DISTRIBUTION STATEMENT

Distribution of this document is unlimited.

11. SUPPLEMENTARY NOTES	12. SPONSORING MILITARY ACTIVITY
None	United States Army Weapons Command Rock Island, Ill. 61201

13. ABSTRACT

Design arrangement and mounting approaches, weight estimates, balance calculations, stress analyses, and helicopter performance predictions of an aerial artillery system utilizing two externally-mounted 105mm XM204 soft recoil howitzers on a CH-47C Chinook helicopter are presented. This design provides for all the firing modes and operational capabilities required by the Weapons Command, including the ability to offload one howitzer when the helicopter is hovering. The study includes an analysis of the structural integration of the weapons and aircraft including muzzle blast effects and airframe dynamic responses. A minimum adequate fire control system for air-to-ground firing and typical ground artillery fire control equipment was included. Mission capabilities of this system include delivery of 60 rounds of rapid air-to-ground firing at the midpoint of a 100-nautical-mile radius with 15 minutes loiter to acquire the target. Delivery of a howitzer for detached firing and a mission using the aerial artillery for attached firing were also considered. Model testing that demonstrated the feasibility of modeling the 105mm howitzer for muzzle blast effects was also included.

DD FORM 1473 1 NOV 65

I-A

| KEY WORDS	LINK A		LINK B		LINK C	
	ROLE	WT	ROLE	WT	ROLE	WT
Aerial Artillery						
XM204 Howitzer						
CH-47C Chinook Helicopter						
Fire Control						
Muzzle Blast and Flash						
Soft Recoil						
Attack Helicopter						
Airborne 105mm Howitzer						
Model Blast Testing						

1-b

Contract DAAF03-72-C-0016
Boeing Technical Report D210-10506-1
October 1972

AERIAL ARTILLERY DESIGN STUDY
TWO EXTERNALLY MOUNTED XM204 HOWITZERS
ON A CH-47C HELICOPTER

FINAL REPORT

OCT ?? 1972

Prepared by
The Boeing Company, Vertol Division
Philadelphia, Pennsylvania 19142

For
Advanced Concepts Division
Aircraft Weapons Systems Directorate
Weapons Laboratory, WECOM
Rock Island, Illinois 61201

/-C

Figure 1. CH-47C Helicopter Aerial Artillery Weapon System

SUMMARY

A comprehensive preliminary design study has been conducted to
further define the physical and functional compatibility in
selected areas for the integration of the XM204 howitzer and
impulse generator system with the CH-47C helicopter for both
air-to-ground and ground-to-ground firing. Findings of this
study can be summarized as follows:

1. Performance: Missions of about a 100-nautical-mile-
    radius can be accomplished carrying 96 rounds and a 9-man
    gun crew. Running takeoffs will be required for atmos-
    pheric conditions more severe than sea level standard
    conditions.

2. Structural Integrity: Reinforcement of the helicopter for
    muzzle blast protection and to provide hardpoints for the
    howitzer installation will increase the empty weight of the
    CH-47C helicopter by 256 pounds. Rotor system stresses due
    to airborne and ground firing will not reduce the service
    life of these components. Stresses due to prolonged opera-
    tion at high gross weights may reduce the service life of
    forward rotor components.

3. Vibration: Response of the howitzers to the vibratory
    environment of the CH-47C can reduce the vibration of the
    helicopter at the penalty of +1,500-pound vibratory loads
    in the mounting structure. Detail design of the installa-
    tion needs to tune the structure or provide for vibration
    isolation.

4. Responses to Firing: Helicopter motions and elastic
    responses to recoil and muzzle blast of the soft-recoil
    XM204 howitzer firing at charge zones up to zone 8 are
    well within the capabilities of the control system, the
    structure, and the crew. There does not appear to be any
    need for the zero-recoil-producing impulse generator rocket
    system for the CH-47C installation.

5. Weight and Balance: The design presented has horizontal
    and lateral center of gravity travels that are well within
    the limitations of the CH-47C.

The final design configuration, illustrated in Figure 1,
includes two howitzers mounted externally on the helicopter.
These howitzers point forward in the traveling position and
also for air-to-ground firing. The left-side howitzer instal-
lation includes hoists for rapid removal for detached firing.
The right-side howitzer is mounted on a small firing platform
so that ground-to-ground attached firing can be provided as
soon as the helicopter lands without subsequent moving of the

weapon or other time-consuming tasks. A rotor brake is included in the design to provide more rapid response in the ground-to-ground attached mode. The design of the installation provides a hardpoints provisions kit that involves minimum modification and only a 256-pound increase in the empty weight of the helicopter. Subsequent installation or removal of the howitzer weapons kit onto the hardpoints-provisioned helicopter within one hour with a 10-man crew appears to be feasible. About 50 bolts are involved in the attachment of the weapons kit. Helicopter performance calculations show that the weapons installation penalizes the lifting and cruise capabilities, but missions of a 100-nautical-mile radius with 96 rounds and a full gun crew can be achieved with the CH-47C helicopter.

Provisions for the impulse generator system have been considered in the design, but the supporting technology efforts have shown that this system is not required. Analyses of helicopter motions and elastic deflections caused by the recoil due to inflight firing of the soft-recoil XM204 at zone 5 without the impulse generators show that these responses are negligibly small. Since the impulse generator system requires doubling the automatic loading complication and would increase the system weight by about 200 pounds, this system has not been included in the final design drawings.

The howitzer for ground-to-ground attached firing that is mounted on the right side of the helicopter consists of an XM204 modified to have the grouser wheels replaced by a gear pinion drive. The small external firing platform shown in Figure 2 is provided for crew operation of the weapon in the ground-to-ground attached firing mode. Muzzle blast reinforcements are not provided in the aft portion of the helicopter, so firing is limited to an azimuth sector of 150 degrees. Addition of a rotor brake to the helicopter and provision for quick removal of the air-to-ground ammunition feed system are provided to allow for firing of the first round of ground-to-ground attached fire within one minute after the helicopter lands. Of course, it would take a well-trained and well-motivated crew to execute all the tasks involved within this brief time. The most time-consuming task in firing this first round appears to be the setup of conventional artillery fire control aiming stake. A screwjack firing base is provided to prevent gun-jump in this attached-firing mode.

The howitzer on the left side of the helicopter is a complete XM204 field piece with attachment fittings added for mounting on the two retractable gun support beams. Two cables and winches are attached to the howitzer to lift the weapon clear of the remotely actuated attachment clamps on the gun support beams. When the howitzer has been lifted, the beams can be retracted to clear the way for lowering the howitzer to the ground. Present studies indicate that it is not necessary,

Figure 2. Aerial Artillery Concept: CH-47C
Helicopter Armed with Two XM204 Howitzors

Figure 2. Aerial Artillery Concept: CH-47C
Helicopter Armed with Two XM204 Howitzers

RIGHT WEAPON CREW PLATFORM

FOLD OF PLATFORM

RIGHT SIDE WEAPON

WEAPON CREW POSITIONS

INTERNAL FUEL TANK
GOUND CAPACITY

FWD HOIST BEAM

GROUND AMMO CONTAINERS

REBORESIGHT TARGET BOX

NOTE
BARREL EXTENSION USED
LENGTHEN ON LEFT SIDE
HOWITZER TO ACCOMODATE
GROUND TOWING

FWD HOIST

LATCH SPINDLE

FWD RETRACTABLE BEAM

AFT HOIST

LATCH DOG

LEFT SIDE WEAPON

AFT RETRACTABLE BEAM

FWD HOIST AND BEAM
OPERATORS STATION

AFT HOIST AND BEAM
OPERATORS STATION

FWD HOIST

AFT HOIST

REINFORCED ESCAPE
HATCH

STA 160

AMMO FEED SYSTEM

MUZZLE BLAST DOUBLER

AFT BOX BEAM

XM 204 HOW T2C4
COMPLETE FIELD PIECE

but it is possible to lower the howitzer to the ground from the center of gravity of the helicopter if an additional sling is provided. The cables would lower the howitzer down to the sling and then the sling would be used to position the weapon on the ground.

As shown in Figure 2, both XM204 soft-recoil howitzers are mounted for forward direct air-to-ground firing with automatic ammunition-loading mechanisms provided for rapid firing (30 rounds per minute each). The copilot is provided with a simple, fixed, depressible-reticle sight and laser rangefinder for aiming the helicopter/gun system for firing in this mode. Preflight adjustments of the howitzer elevation settings will allow for aiming the weapons with the helicopter at various airspeeds, rates of climb, and heights above the target.

The hardpoints kit required for installation of the weapons kit is illustrated in Figure 3. This hardpoints kit will add 256 pounds to the empty weight of the helicopter, but in no other way will it reduce the operational utility of the air- craft. Most of the added weight is due to the reinforcement of both sides of the front of the helicopter provided for muzzle blast protection in air-to-ground direct firing. This reinforcement was sized for unintentional firing of a zone 8 round and includes external skin doublers and increased- thickness transparent areas. The only other external members are the reinforced openings with appropriate closures for the winch top beams. Internal reinforcements for the weapon sup- port beam attachment include four frame-reinforcement bathtub fittings between the frames at stations 200, 240, 280, and 320. Also provided internally are frame web doublers at each of the above frames and for the frame at station 160. A new hydraulic pump and valve, as well as some added electrical connections, are required. This hardpoints provisions kit is envisioned as being installed into many designated helicopters in the combat zone during accomplishment of other field maintenance.

The design described herein has been studied in adequate detail to size the major components and fittings so that the installa- tion weight could be estimated to within 100 pounds. This analytical substantiation included calculation of stresses, vibration dynamics, helicopter dynamic motions and elastic response due to recoil loads, and muzzle blast structural loads. Rotor blade dynamic response, weight and balance, and helicopter performance were also calculated. Results of these analyses are reflected in the design and are presented in detail.

Component weights of the design installation on the CH-47C helicopter are summarized in Table I. As shown in this table, there is allowance for 96 rounds of ammunition with no crate or packing weight since the rounds are stored in the fixed

AFT HOIST ASSEMBLY
ATTACH POINTS 6 BOLTS

AFT BOX BEAM
ATTACH POINTS – 4 BOLTS

AMMO FEED SYSTEM
ATTACH POINTS – 12 BOLTS

LONGITUDINAL BEAMS
ATTACH POINTS – 16 BOLTS

REINFORCEMENTS
(6 FRAMES)

LASER RANGE FINDER
BRACKET

SIGHT & CONTROL
BOX BRACKET

FWD BOX BEAM ATTACH POINTS – 4 BOLTS

FWD HOIST ASSEMBLY ATTACH POINTS – 6 BOLTS

MUZZLE BLAST DOUBLER – BOTH SIDES OF FUSELAGE

160   200   240   280   320   360

Figure 3.   Hardpoints Provisions and Fastener Attach Points
for Weapons Kit Installation

viii

TABLE I. HELICOPTER AND KIT WEIGHT SUMMARY	
Item	Weight (lb)
Helicopter Empty Weight	20,743
Remove Troop Provisions	-93
Fuel Tank Changes	151
Combat Equipment (Armor, Suppressive Fire Weapons)	0
Hardpoints Provisions Kit	256
Weapons Kit (Including 6,951 lb of Howitzers)	10,690
Full Fuel	7,004
Ammunition (96 rounds)	3,820
Gun Crew (9 Men)	1,800
Fixed Useful Load (Aircrew, etc.)	689
Total	45,060
Alternate Design Gross Weight	46,000

racks and the readily removable containers. The 7,004 pounds of fuel provided will allow the CH-47C to exceed the 100-nautical-mile design radius missions. As shown in the table, no weight allowance is made for combat equipment which is 2,042 pounds (assuming that a gun crew member could fire one suppressive-fire weapon) for SEA operations of the CH-47C. If this combat equipment is required, the mission radius capability would be reduced to about 60 nautical miles. Further growth of the helicopter during the timeframe of the development of the weapon installation is likely to cause significant increases in this capability.

MODEL GUN TESTING

This study also included testing in which the feasibility of modeling the 105mm howitzer at the 1/11 scale appropriate for subsequent helicopter model testing was successfully demonstrated. Scaled muzzle blast fields were generated which were within 0.5 psi of the full-scale predictions. Response of scaled airframe panels was also explored. Testing of a model CH-47C helicopter with muzzle blast caused by a model howitzer is recommended to further substantiate the rotor blade loads and dynamic response analyses.

FOREWORD

This report describes the results of a preliminary design
study conducted to show how the XM204 howitzer could be inte-
grated with the CH-47C helicopter in such a way as to provide
for various firing modes required by the U. S. Army. This
study was conducted under Contract DAAF03-72-C-0016 during the
period from December 1971 to October 1972. Technical cogni-
zance for this project at Weapons Command, Rock Island Arsenal,
was initially provided by Lawrence L. Frauen; and in the final
stage of the study, this cognizance passed to Thomas J. Redling.
Both these men were of the Aircraft Weapons Systems Director-
ate, Advance Concepts Group, under the supervision of John A.
Reynolds. William G. Smith, Chief of the Future Weapons
Division of the Research, Development and Engineering Director-
ate, also provided impetus and guidance to this effort. The
authors also wish to acknowledge the help of Mark J. Salsbury,
Artillery Weapons Systems Directorate, Rock Island Arsenal,
William P. Burgess and Dr. Glen Moore of the Naval Weapons
Laboratories, Dahlgren, Virginia, and Robert G. S. Sewell of
the Naval Weapons Center, China Lake, California, for their
significant contributions to the muzzle blast work performed.
The authors of this report and the areas of the principle con-
tribution are:

Alfred Bonnell	- Design
Steve S. Dallas	- Performance
Robert P. Giantonio	- Vibration/Dynamics
Leo Gumienny	- Integration
Edward H. Higgins	- Stress Analysis
Norman I. Klavens	- Muzzle Blast
Arthur MacArthur	- Missions
Alfred B. Meyer	- Aeroelasticity
Henry J. Neeb	- Flying Qualities
English Piper	- Fire Control
Richard R. Pruyn	- Summary
Richard D. Semple	- Propulsion
Maurice E. Snook	- Weights

TABLE OF CONTENTS

Preceding page blank

LIST OF ILLUSTRATIONS

LIST OF TABLES

LIST OF SYMBOLS

MUZZLE BLAST

b	width of skin panel, inches
¢	bore diameter (caliber), inches
C	velocity of sound in aluminum, ft./sec.
R	modulus of elasticity, psi
E_A	total energy available in propellant, ft.lb.
E_p	kinetic energy of projectile, ft.lb.
E_T	thermal energy, ft.lb.
f_o	natural frequency, Hz
F_{tu}	ultimate yield strength of a material, psi
F_{ty}	static yield strength of a material, psi
H_c	heat of explosion of propellant, calories/gram
I_c	critical impulse, psi-sec.
K	dimensionless constant
L	barrel length, in.
M_p	mass of projectile, slugs
T	period of oscillation (reciprocal of natural frequency), sec.
t_c	critical time, sec.
V_o	muzzle velocity, ft./sec.
W_c	weight of propellant, lb.
X/C	distance in calibers, measured perpendicular to the barrel axis
Z/C	distance in calibers, measured from the muzzle along the barrel axis
λ	geometric length ratio

MUZZLE BLAST (Continued)

Δ_p — overpressure (absolute pressure minus atmospheric pressure)

σ_y — dynamic yield strength of a material, psi

δ — thickness of skin panel, inches

ε — strain

PERFORMANCE

A — total rotor disc area $(2 \pi R^2)$, ft^2

A_F — projected frontal area in cruise flight, ft^2

A_V — exposed vertical drag area, sq. ft.

C_D — drag coefficient of aircraft components based on frontal area

C_{D_V} — vertical drag coefficient of fuselage section

DL — download caused in hover by downwash of the rotors impinging on the fuselage and weapon installation, lb.

f_e — equivalent parasite drag area of the airframe and weapon installation or components thereof, ft^2

OGE — out-of-ground effect

R — rotor radius, ft.

T — thrust of the rotors in hover to balance the weight and download of the helicopter, lb.

ρ — mass density of air, $slug/ft^3$

ν — actual downwash velocity, ft/sec.

ν_{IND} — induced velocity from momentun theory $(\sqrt{T/2A\rho})$, ft/sec.

κ — factor that accounts for the radial variation of the downwash

PERFORMANCE (Continued)

$\Delta \ell$ length of an increment of the fuselage expressed as a percent of the rotor radius

$\bar{\omega}$ width of an increment of the fuselage expressed as a percent of the rotor radius

STRESS ANALYSIS

E modulus of elasticity in tension, psi

f calculated stress, psi

F_{bu} ultimate bearing stress, psi

F_{by} yield bearing stress, psi

F_{cu} ultimate compressive stress, psi

F_{su} ultimate stress in pure shear, psi

F_{tu} ultimate tensile allowable stress, psi

F_{ty} tensile yield allowable stress, psi

G modulus of rigidity

GW gross weight, lb.

H_D density altitude, ft.

H_z weight load components, lb.

I moment of inertia of section, in^4

M applied moments along axis and at point noted in subscript, in.lb.

MS margin of safety

$\mu - 3\sigma$ mean value less 3 standard deviations of the scatter in the data

Ω rotor speed, rpm

P applied loads in direction and at point noted in subscript, lb.

STRESS ANALYSIS (Continued)

Q static moment of crosssection, in.lb.

R stress ratio

t thickness, in.

V_H maximum airspeed attainable within the limits of V_{ne} and military rated power, knots

V_{ne} structural limit airspeed of the helicopter, knots

z section modulus, in^3

σ_{cu} critical ultimate stress, psi

σ stress, psi

ΔM moment at the rotor blade to spar attachment per inch of blade span due to muzzle blast

ΔP_{BLAST} muzzle blast overpressure at the rotor blade, psi

σ_{BLAST} stress in the blade due to muzzle blast, psi

ρ radius of gyration, in.

η maneuver load factor

INTRODUCTION

The helicopter has provided combat units of the Army with
increased tactical mobility. This in turn has developed a
continuing desire to provide field artillery with matching com-
bat support mobility. This desire has led to the development
of aerial rocket artillery that has been deployed with some
success. Due to the greater range and accuracy, the reduced
cost of rounds, and the greater variety of rounds provided by
the field artillery howitzers, there has been a continuing
desire to provide more mobility for the howitzers. In fact,
development of the CH-47C Chinook helicopter received increased
impetus from the need to carry the 155mm howitzer. Sling-load
techniques have been developed to rapidly emplace these 13,500-
pound weapons. A major problem of sling-loading has been that
it degrades the stability of the helicopter, and this has
resulted in limited adverse weather capability. While in-
creased stability sling-load systems are being developed, there
is a need for a better system. Also, the ability to fire from
the air without emplacing the weapon is desired so that the
security of the ground situation does not limit firing opera-
tions and firing is more responsive and not interrupted when
the weapons are being displaced. For these reasons, the Army
has continued a low level of effort to develop aerial artillery
using howitzers despite serious concerns about the effects of
muzzle blast and recoil on the helicopter. This effort is now
ready to pay off since the technology of weapons and helicopters
has now developed adequately. As shown in this report, the
Army's XM204 soft recoil howitzer has reduced the recoil prob-
lem to negligible proportions, and the CH-47C helicopter is
more rugged and has adequate payload to carry the weapons,
ammunition, and additional reinforcements required to take the
muzzle blast and other loadings. Previous Army testing of
large weapons on the earlier H-21 helicopter showed that this
helicopter needed significant reinforcements. Muzzle blast
and recoil damage occurred in the large recoilless rifle tests
at Aberdeen, results analyzed in Reference 1 , and tests of
the 75mm Pack howitzer and the 105mm howitzer at Rock Island,
References 2 and 3 , respectively. This testing experience
has been incorporated into the present design and this new
design is now ready to be built and tested.

For additional background on the subject of aerial artillery,
the years of work on this subject have produced six documents
on design study efforts. These reports have been analyzed for
content and the matrix of Table II was generated to display
areas of significant effort. As shown in the table, various
weapons, various helicopter configurations, and tactical
effectiveness have been studied. Some supporting technology
efforts have been made, but none of these efforts has been to
the depth presented in the present report.

1

The objective of this study was to perform an analysis and study of aerial artillery work items selected from Section G of the U. S. Army Weapons Command document, dated November 1970, entitled, "Aerial Artillery Weapon (Externally-Mounted Concept)(U)." This study has further defined the physical and functional compatibility in selected areas for the integration of the XM204 howitzer and impulse generator system with the CH-47C for selected firing modes.

TABLE 11. AERIAL ARTILLERY DOCUMENTS

Title	Supporting Technologies										Mission Effectiveness		
	Weapon Installation							Fire Control Systems & Surveys	Target Acquisition	Survivability	Cost Effectiveness	Tactical Effectiveness	Operational Perf contr
	Weapon Systems	Mounting Configuration	Stress and Dynamics	Flight Control	Blast	Navigation & Communication	Aerodynamics and Performance						
Aerial Artillery Study Subtask 1.8 Analysis of Ammunition and Fuel Requirements, Contract DAAH01-69-C-1916, July 1968	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters					Brief Downwash Effects & Helicopter Performance Review						Evaluation Performance of the Effects of Ammo Expenditure and Distance Upon Fuel Requirements and Aircraft Productivity
Airmobile VTOL Artillery Weapons Systems, May 1963, Boeing Report R-447	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters	Brief Study of Recoil Loads	Review of Flight Control Degradation Related to the Various Helicopters									
Feasibility & Design Study of Airmobile Artillery, Contract DA44-177-AMC-108(T), April 1964	Howitzers, Rockets, Missiles	Comprehensive Group of Helicopters' General Arrangement	Brief Study of Recoil Loads	Brief In-flight Stick Motion Analysis Study	Brief Blast Overpressure Analysis	Night Firing Capability Navigation and Communication System Reviews	Helicopter Performance Chart Completed; Brief Dynamics Study	Fire Directions System & Artillery Survey Review	Review of Applicable Target Acquisition & Sighting Systems	Review of Countermeasures and Armor Study of Survivability	Cost Effectiveness Comparison of Candidate Weapon Systems	Tactical Effectiveness of Candidate Sys tem Reviewed	
Aerial Artillery System Concept Study - VTOL Aircraft Parametric Study, September 1969, Boeing Document D210-10040-1	Missiles	Study Considered Various VTOL Aircraft but not Weapon Mountings					VTOL Aircraft Reviewed in Depth for Performance Data Shown on 13 Charts						
Cost and Schedule Addendum for Air to Ground Study of the 105/155mm Howitzer/HC-1B, Contract DA-11-070-AMC-103(W), April 19..	105mm and 155mm Howitzer	Howitzer Firing from Cutout in Side of CH-47 Fuselage	Detailed Definition of Dynamics Analysis, Stress Integration, In-flight Gun Firing										
Cost Effectiveness Comparison of Artillery Systems for Support of Airmobile Operations by Research Analysis Corporation, AD381800, May 1967	Rockets, Missiles, Mortars, Howitzers, Recoilless Rifles	Analysis of Weapon Integration Probl..			Review of Blast Problems for the Various Weapons		Brief Downwash Review			Overview of Survivability Analysis - Brief Analysis of Ground Vulnerability of Helicopters	Cost Effective Comparison of various Artillery Systems for Airmobile Operations	Tactical situations	Operational performance Analysis for 3 Aerial Artillery Firing Modes

TABLE II. AERIAL ARTILLERY DOCUM

| Title | Weapon Installation | | Supporting Techno | | | | Aer |
	Weapon Systems	Mounting Configuration	Stress and Dynamics	Flight Control	Blast	Navigation & Communication	Perf
al Artillery Study Subtask 1.8 ysis of Ammunition and Fuel irements, Contract DAAH01-69- 16, July 1968	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters					Brie was & Ba Perf Retd
obile VTOL Artillery Weapons ems, May 1963, Boeing rt R-447	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters	Brief Study of Recoil Loads	Review of Flight Control Degradation Related to the Various Heli-copters			
ibility & Design Study of mobile Artillery, Contract -177-AMC-108(T), April 1964	Howitzers, Rockets, Missiles	Comprehensive Group of Helicopters' General Arrangement	Brief Study of Recoil Loads	Brief In-flight Stick Motion Analysis Study	Brief Blast Overpressure Analysis	Night Flying Capability Navigation and Communication System Reviews	Heli Perf Char plet Brie namd
al Artillery System Concept ly - VTOL Aircraft Parametric ly, September 1969, Boeing ment D210-10040-1	Missiles	Study Considered Various VTOL Aircraft but not Weapon Mountings					VTOL craf vie Dept Perf Data on l
and Schedule Addendum for Air round Study of the 105/155mm ltzer/HC-1B, Contract DA-11- -AMC-103(W), April 1966	105mm and 155mm Howitzer	Howitzer Firing from Cutout in Side of CH-47 Fuselage	Detailed Definition of Dynamics Analysis, Stress Integration, Inflight Gun Firing				
Effectiveness Comparison of llery Systems for Support of mobile Operations by Research ysis Corporation, AD381800, 1967	Rockets, Missiles, Mortars, Howitzers, Recoilless Rifles	Analysis of Weapon Integration Problems			Review of Blast Problems for the Various Weapons		Brie was

TABLE II. AERIAL

Title	Weapon Installation		Stress and Dynamics	Flight Control	Blast	N Co
	Weapon Systems	Mounting Configuration				
Aerial Artillery Study Subtask 1.8 Analysis of Ammunition and Fuel Requirements, Contract DAAH01-69-C-1916, July 1968	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters				
Airmobile VTOL Artillery Weapons Systems, May 1963, Boeing Report R-447	Howitzers, Rockets, Missiles	Attached & Detached Firing Modes Studied for Various Helicopters	Brief Study of Recoil Loads	Review of Flight Control Degradation Related to the Various Heli - copters		
Feasibility & Design Study of Airmobile Artillery, Contract DA44-177-AMC-108(T), April 1964	Howitzers, Rockets, Missiles	Comprehensive Group of Helicopters' General Arrangement	Brief Study of Recoil Loads	Brief In-flight Stick Motion Analysis Study	Brief Blast Overpressure Analysis	Ni Ce Ne ar ce te
Aerial Artillery System Concept Study - VTOL Aircraft Parametric Study, September 1969, Boeing Document D210-10040-1	Missiles	Study Considered Various VTOL Aircraft but not Weapon Mountings				
Cost and Schedule Addendum for Air to Ground Study of the 105/155mm Howitzer/HC-1B, Contract DA-11-07C-AMC-103(W), April 1966	105mm and 155mm Howitzer	Howitzer Firing from Cutout in Side of CH-47 Fuselage	Detailed Definition of Dynamics Analysis, Stress Integration, In-flight Gun Firing			
Cost Effectiveness Comparison of Artillery Systems for Support of Airmobile Operations by Research Analysis Corporation, AD381800, May 1967	Rockets, Missiles, Mortars, Howitzers, Recoilless Rifles	Analysis of Weapon Integration Problems			Review of Blast Problems for the Various Weapons	

ARTILLERY DOCUMENTS

| Supporting Technologies | | | | | Mission Effectiveness Evaluation | | |
Navigation & Communication	Aerodynamics and Performance	Fire Control Systems & Surveys	Target Acquisition	Survivability	Cost Effectiveness	Tactical Effectiveness	Operational Performance
	Brief Down-wash Effects & Helicopter Performance Reviews						Evaluation Performed of the Effects of Ammo Expenditure and Distance Upon ? Fuel Requirements and Aircraft Productivity
ght Flying pability vigation d Communication Systm Reviews	Helicopter Performance Chart Completed; Brief Dynamics Study	Fire Directions System & Artillery Survey Reviews	Review of Applicable Target Acquisition & Sighting Systems	Review of Countermeasures and Armor Study of Survivability	Cost Effectiveness Comparison of Candidate Weapon Systems	Tactical Effectiveness of Candidate Systems Reviewed	
	VTOL Aircraft Reviewed in Depth for Performance Data Shown on 13 Charts						
	Brief Down-wash Review			Overview of Survivability Analysis - Brief Analysis of Ground Vulnerability of Helicopters	Cost Effective Comparison of Artillery Systems for Airmobile Operations	Tactical Situations Analysis of Aerial Artillery	Brief Analysis of Operational Performance & Systems Analysis for 3 Firing Modes

DEFINITION OF THE DESIGN MISSIONS

The general requirements of the approved QMDO, as expanded and explained in Reference 4, have been further expanded and detailed to provide specific design missions. These design missions are based mostly on judgment and trade-studies, and mission analyses are required to validate these mission details. The four missions shown should be considered as illustrations of the potential and the limitations of aerial artillery. The design does not vary greatly with the mission if all the firing modes are retained; however, the number of rounds carried can be traded against variations in mission radius, temperature, or altitude of takeoff, gun crew size, or more equipment, etc.

It may be noted that in the following three ground-to-ground design missions, only 36 rounds are fired, while 60 rounds are maintained for air-to-ground. This selection was based on the fact that the rounds for the air-to-ground firing had to be prezoned (to zone 5) and crimped before the flight. Therefore, these rounds could not as readily be replaced during the flight. Standard rounds could be delivered to the forward firing site by the logistics transport helicopters while these helicopters are delivering ammunition to other artillery sites. Also, since automatic loaders are provided for air-to-ground firing, there is a potential for firing more rounds in this mode. Further study of how the aerial artillery would be used is required to more firmly select the mix of rounds.

GROUND-TO-GROUND ATTACHED FIRING MISSION

The aerial artillery helicopter is to take off with a 9-man gun crew and the complete howitzer installation and equipment. Ammunition load will be 96 rounds with 36 of these rounds in readily removable containers and the remainder of the rounds in racks. Rounds in the racks will be loaded with zone 5 propellant and crimped for firing with the automatic loading system. All rounds will be fused on loading. This mission is summarized in Figure 4.

A running takeoff (rather than an OGE vertical takeoff) will be made so that the helicopter can be loaded to the alternate design gross weight at takeoff conditions of 2,000 feet pressure altitude and 95°F. At sea level standard conditions, a vertical takeoff (OGE) is required.

The helicopter will be able to fly to at least a 100-nautical-mile radius at an average cruise speed of 120 knots. During the flight, the weapon will be ready to fire air-to-ground at targets of opportunity and ready to be diverted to other higher priority missions. At the design mission radius, the helicopter will make a vertical landing at takeoff atmospheric conditions.

Figure 4. Mission 2, Aerial Artillery Ground-to-Ground Firing Mode (Howitzer Attached)

The rotors will be braked to a rapid stop, and the crew will quickly set up the attached fire howitzer. The engines will be stopped. Thirty rounds will be fired, retaining the remainder of the rounds to be ready for other targets obtained during the return flight. All empty cartridge cases will be recovered.

After the attached firing is complete, the howitzer will be returned to the travel psoition and the automatic loader reinstalled. The ammunition containers and empty cartridge cases will be returned to the helicopter, the engines restarted, warmed up, and the flight back to the base will be made with ten percent fuel reserve remaining at landing.

GROUND-TO-GROUND DETACHED FIRING MISSION (LAND TO DETACH)

As in the attached fire mission, the aerial artillery helicopter will take off with a full crew and equipment so that alternate targets can be attacked. At takeoff, the missions are almost the same. Less fuel is required on the return leg since the detachable howitzer, 36 rounds of ammunition, and a five-man gun crew are offloaded at the mission midpoint; but this is offset by the 15 minutes of hovering capability that are provided to find the landing zone and detach the weapon. This mission is summarized in Figure 5. Again, at least a 100-nautical-mile radius is required with a running takeoff and a vertical landing to unload the howitzer. The mission is flown at 2,000 feet, 95°F. The rotors are not stopped when the howitzer is being detached. Four gunners and 60 rounds are retained in the helicopter during the return flight so that other targets can be attacked. Ten-percent reserve fuel is required on landing at base.

GROUND-TO-GROUND DETACHED FIRING MISSION (HOVERING DETACHMENT)

This mission is identical to the detached firing mission with landing for detachment of the howitzer except in the details of how it is performed. The performance of the helicopter is identical. In executing the mission, the helicopter does not land at the midpoint. The left howitzer is detached and lowered to the ground from the hovering helicopter. The 36 rounds and the gun crew are lowered using the helicopter rescue hoist.

AIR-TO-GROUND FIRING MISSION

Again, as in the previously discussed missions, takeoff is with full equipment and men to provide for mission flexibility. The helicopter may perform a running takeoff and must fly a 95-nautical-mile radius mission. To acquire and attack the target, fuel for 15 minutes of hovering is provided at the mission midpoint. (This fuel allowance would provide about 30 minutes of low-speed loitering or several high-speed gun runs.) All 60

CH 47C WITH
T55-L-11 ENGINES

HELICOPTER HOVERS FOR 15 MINUTES
TO FIND LANDING ZONE AND TO
EMPLACE THE WEAPON

LAND WITH 10%
RESERVE FUEL

BASE

RUNNING TAKEOFF AT
2,000 FT, 95°F
ZERO WIND

100 NAUTICAL MILES

HELICOPTER MAKES
VERTICAL LANDING AND
UNLOADS DETACHABLE
HOWITZER, 5 MEN AND
36 ROUNDS

TARGET

Figure 5.   Mission 3, Aerial Artillery Ground-to-Ground Firing
Mode (Howitzer Detached Hover Unloading)

rounds that were crimped with zone 5 charge for automatic loading will be fired during this attach mission. The 36 rounds which are in the removable containers for ground-to-ground firing could be rezoned to zone 5, crimped, and loaded into the automatic loader for firing during the return flight. This mission is summarized in Figure 6.

Figure 6. Mission 1, Aerial Artillery Air-to-Ground Firing Mode

DESIGN PHILOSOPHY

Philosophies used to establish the design presented in this report were an amalgam of the philosophies presented in Reference 4 and philosophies for mounting large items on helicopters that have been developed by Boeing. All these philosophical requirements that are achievable have been met. The concluding design will result in as simple, rugged and low-cost an installation as possible with the various required firing and operating modes.

WECOM CONCEPTUAL REQUIREMENTS

As noted in the following, the study contract configuration satisfies or exceeds the conceptual requirements extracted from Reference 4:

1. <u>The system must be capable of delivering large volumes of fire in support of ground units</u>. The contract configuration is capable of delivering 36 adjustable-zone rounds and 60 rounds of zone 5 in the ground-to-ground mode at normal firing rates for manual operation. The loaders for air-to-ground firing are sized for firing at 30 rounds per minute each.

2. <u>The system must be capable of firing air-to-ground mode, using XM204 howitzer with impulse generator</u>. The contract configuration includes provisions for firing air to ground with or without impulse generators. Both weapons are loaded by automatic feeders and fired by remote control. Impulse generators can be added to the system but they are not required.

3. <u>The system is to have independent fire control with battalion augmentation</u>. The contract configuration includes a fire control system consisting of standard ground artillery sights, etc. for ground-to-ground firing and a gunsight and laser rangefinder for air-to-ground firing. Battalion communication can be maintained by means of the radios in the helicopter.

4. <u>Barrel-type ammo container should be used</u>. Eighteen-round barrel-type containers are used to offload ammo for ground-to-ground detached firing of the left weapon. The containers may be lowered through the rescue hatch in hover mode or offloaded from the cargo ramp when the aircraft is on the ground.

5. <u>One weapon must be detachable for ground emplacement, and the system must include the capability to offload this weapon from hover mode</u>. The left-side XM204 may be off-loaded on the ground or in hover mode. This weapon is a

complete field piece and may be manhandled or transported by prime mover into position after detachment.

6. <u>The system is to have effective communications</u>. The radios in the helicopter will provide effective communications.

7. <u>Weight of the system shall not significantly degrade the performance of the aircraft</u>. With the howitzer installation, the helicopter is capable of flying to the structural limits of the aircraft for the gross weights involved. Airspeeds in excess of the best range speed (approximately 110 knots) are readily achieved.

8. <u>The aircraft must operate in the same environmental elements as ground vehicles</u>. The CH-47C is an all-weather aircraft, capable of operation in all environments including a temperature range of -65°F to +125°F.

9. <u>On-board and detachable fire control should be provided</u>. The on-board fire control system consists of a simple gunsight and a laser rangefinder. Ground-to-ground attached and detached firing are accomplished using the sighting and fire control equipment provided for field usage of the XM204.

10. <u>The single system must be capable of replacing close support cannon artillery</u>. The system is capable of standoff aerial bombardment for close support of ground operation. In addition, a single XM204 may be offloaded from hover for strategic deployment on the ground. The crew, plus 36 rounds of ammo, may be rapidly offloaded with this weapon. Sixty additional rounds can be offloaded individually from the ammo racks.

11. <u>The single system must be capable of firing antipersonnel, antimaterial, marking and screening smoke, illuminating, and chemical rounds</u>. The system is capable of carrying all types of ammo and selectively firing it in the air-to-ground or ground-to-ground modes.

12. <u>Speed range and endurance of the system must be greater than airmobile maneuver force transport vehicles</u>. The aerial artillery kit reduces the speed, range, and endurance capability of the CH-47C helicopter, but the modified helicopter appears to give adequate performance. A cruise speed of 120 knots and a 100-nautical-mile radius mission are achievable. This speed and range are compatible with airmobile maneuver force vehicles since this force is limited to the capability of the transport helicopter with external (sling) load.

13. <u>Growth potential for indirect fire from the air should be provided</u>. Mounting of the weapons permits indirect firing

12

from the air; however, muzzle blast effects and ammo loading problems as well as rotor synchronization must be resolved.

14. **Weapons easily transportable in case air movement not possible.** The left-side weapon is a complete field piece and is easily detachable without the aid of ground equipment.

15. **The system should be capable of firing special rounds, i.e., antiradiation, etc. when available.** Firing the weapons is not limited by the helicopter in the ground-to-ground modes. Air-to-ground firing is nominally limited to zone 5 firing, but there is considerable margin provided in the design for firing the larger zones.

16. **The system is to be rugged, reliable, simple, facilitate training, etc.** The installation as configured represents the ultimate in ruggedness and simplicity.

17. **Provisions for automatic ammo and impulse generator loading of the weapons in flight should be included.** An automatic ammo loader is included. If it were necessary, a similar loader could be provided to load impulse generators.

ADDITIONAL BOEING CONCEPTUAL REQUIREMENTS

As a result of experience with mounting various items on helicopters and from discussion on the subject with likely users of the aerial artillery installation, the following additional design philosophies and goals were established:

1. The aerial artillery system shall be incorporated into the aircraft as a kit, easily attachable and removable. Installation and removal shall not require a crane or other special equipment. A design goal will be to install or remove the weapons kit within one hour.

2. The hardpoints provisions to accept the weapons kit shall not compromise the use of the aircraft in its primary mission as a cargo/troop transport.

3. The system and its attachments shall be simple and rugged in construction. The design shall incorporate proven technology.

4. The system shall require a minimum of airframe rework. Holes in the fuselage, which would adversely affect the structural integrity of the airframe, shall be avoided.

5. The study configuration shall be exposed to a human factors evaluation to ensure that all aspects of the system are operable.

13

6. The total aerial artillery kit installation shall not cause serious detrimental effects on performance and will not reduce stability or controllability of the aircraft.

7. To minimize cost, all fire control equipment will be the most simple equipment which will produce adequate accuracy. Existing conventional artillery fire control will be used for ground firing. Airborne firing will be designed for an accuracy of 15 mils, one sigma, error.

8. To provide for the continuous high gross weight and unusual flight profile operations inherent in armed helicopter operations, it will be assumed that the critical dynamic components of all helicopters which have had the weapons kit installed will be replaced after a reduced service life. Preliminary estimates indicate that reduced service life of some forward rotor blade components is involved.

9. In the preliminary design of the attachments for the aerial artillery kit, it was assumed that all components of the helicopter are already loaded to a significant portion of their strengths. Reinforcements have been provided to spread the load until the loads going into the basic structure are small. Detail design should show that the need for reinforcement can be reduced from that shown in this report.

10. Design of all components will be such that no single failure or single malfunction can result in serious injury to the aircrew, artillery group, or friendly ground personnel.

DESCRIPTION OF THE CONFIGURATION
AND FUNCTION OF COMPONENTS

The aerial artillery configuration selected for detailed study
is composed of a CH-47C Chinook helicopter mounting two XM204
howitzers as shown in Figure 2 . The weapon arrangement con-
sidered is essentially the same as that envisioned in the
WECOM Aerial Artillery Concept document, Reference 4 . The two
howitzers are carried externally. The installation includes
provisions for ground-to-ground attached firing of one howitzer
and ground-to-ground detached firing of the other, as well as
air-to-ground firing of both howitzers.

In Reference 4, the two ground-to-ground firing modes were
accomplished using the left-side weapon. With the concurrence
of RIA, the concept was changed in this respect; and the ground
functions were divided between the two weapons. In the study
configuration, the left-side weapon may be offloaded for
detached ground-to-ground mode firing. The right-side weapon
is fixed to the airframe and used for ground-to-ground attached
firing.

For air-to-ground firing, the design provides for aerial direct
firing forward of either weapon at a preset fixed elevation.
The weapons are aimed by the copilot/gunner using a simplified
fire control system consisting of a gunsight and laser range-
finder. The copilot/gunner will aim the weapons in azimuth by
using the directional controls of the helicopter. Elevation
aiming will be accomplished by establishing the preselected air-
speed and slightly changing the rate of climb so that the target
is within the reticle of the gunsight when the helicopter is at
the preselected range. Preselected airspeed can also include hover.

The howitzer installation is accomplished by incorporation of
a hardpoints provisions kit on the helicopter which provides all
the fittings, brackets, hydraulic and electrical fittings for
the subsequent addition of the weapons kit. The hardpoints kit
is installed with a minimum of modification to the helicopter
and a minimum increase in empty weight. Weights of the various
components of the hardpoints kit are:

Item	Weight (lb)
Internal Attachment Forgings (8 pieces)	25
Frame Reinforcements (6 frames)	60
Muzzle Blast Doublers and Reinforced Hatches	110

Item	Weight (lb)
Rotor Brake (to stop rotors for attached firing)	51
Brackets, etc.	10
Weight of Hardpoints Kit	256

The weapons kit attaches to the hardpoints kit with about 50 bolted connections. Attachments are designed to allow the installation or removal of the weapons kit within one hour so that dedicated helicopters are not required. The weapons kit includes the weapons and the supporting structures. Component weights for this kit are:

Item	Weight (lb)
Left-Side XM204 Howitzer	3,751
Right-Side Howitzer Modified for Firing Platform Operation	3,200
Box Beams (2) and Longitudinal Support Beams (4)	390
Retractable Beams (2), Latches, Drive Motors, etc.	1,577
Bearing and Attachments	80
Hoist Assemblies (2)	192
Right-Side Firing Platform	155
Internal Fuel Tank, Fittings, etc.	600
Ammo Feed System (Both Howitzers)	400
Ammo Racks	280
Air-to-Ground Sight, Laser Rangefinder and Reboresight Equipment	50
Artillery Group Fire Control and Other Carry-On Equipment	15
Weight of Weapons Kit	10,690

The left-side howitzer is a complete field piece with only minor modifications, and its installation on the aircraft also includes provisions for offloading from hover. The support structure for this gun is retractable, and a double hoist system, equipped with 100 feet of cable, is incorporated to lower the weapon to ground level.

The crew for ground operation of this howitzer may disembark with the weapon or may be already on the emplacement site. Once on the ground, the gun suspension system may be pumped down to the travel position and the weapon manhandled, or towed, to the desired location. Ammo is offloaded through the rescue hatch in hover or down the rear ramp with the ship on the ground. Army standard 18-round ammo drums may be used to transport the offloaded rounds. The system mission weight includes two 18-round ammo drums for ground-to-ground detached firing.

The offload procedure is reversed to pick up the left weapon for reemplacement or aerial firing. The howitzer would be prepared for hover pickup by putting the wheels, etc. in the travel position, with the cannon out of battery, and with the barrel set to a preselected angle. The forward and aft hoist harnesses, forward carriage spindle, aerial mount adapter channel, and magnetic breech actuation plate may be attached by the four-man gun crew within an estimated five minutes with the weapon in this position. (The magnetic breech actuation plate may be permanently installed if it does not interfere with manual operation of the breech.) After hookup to the twin-hoist system, the weapon is raised to a position slightly higher than its retracted support structure (see Figures 7 and 8). The structure is then extended and the weapon lowered into engagement with the aircraft. Securing of the weapon is accomplished by means of a mechanically-actuated lock at the spindle socket in the forward support beam and by two dogs which grip the aerial mount adapter channel by again retracting the aft beam.

Locking of the forward carriage spindle completes the electrical circuit to the permanently-installed linear motor on the howitzer mount which is used to fire the weapon remotely from inside the aircraft. Boresight realignment of the howitzer with the aircraft fire control system is accomplished by a retractable auxiliary optic tube which extends from the side of the fuselage into engagement with the M114 elbow telescope on the mount. The weapon is then aligned in azimuth by retraction or extension of the forward support beam while sighting through the optic tube at a fixed boresight target attached to the side of the aircraft. A vertical scale can also be provided on the target for determining an elevation boresighting correction in the reattachment sequence. The off and onloading sequence for the howitzer is identical whether the aircraft is in hover or on the ground.

STEP 1 PREPARATION FOR ON-LOADING

WEAPON IN TRAVEL POSITION.
INSTALL AERIAL ATTACH FITTINGS.
INSTALL HOIST HARNESS 2 PLACES.
HOVER AIRCRAFT OVER WEAPON
AND ATTACH HOIST CABLES.

FWD HOIST
CABLE HARNESS

AFT HOIST CABLE HARNESS

MAGNETIC CLUTCH PLATE (ON BREECH PIVOT)

PLATFORM STABILIZER

AERIAL MOUNT ADAPTER CHANNEL

GROUND

AERIAL MOUNT FWD
CARRIAGE SPINDLE

XM204 IN TRAVELING
POSITION

STEP 2 HOISTING WEAPON

HOIST OPERATORS AT WINDOWS 2
AND 3. RAISE WEAPON ABOVE
RETRACTED SUPPORT BEAMS.
RAISE MUZZLE END TO ALIGN
MOUNT ADAPTER CHANNEL WITH
AFT BEAM.

FWD HOIST   AFT HOIST

FWD RETRACTABLE
SUPPORT BEAM

AFT RETRACTABLE
SUPPORT BEAM

STEP 3 LOCATING WEAPON

EXTEND RETRACTABLE SUPPORT
BEAMS. LOWER BREECH END OF
WEAPON TO ENGAGEMENT WITH
AFT RETRACTABLE BEAM.

STEP 4 SECURING AND ALIGNMENT OF WEAPON

LOWER MUZZLE END AND ENGAGE
CARRIAGE SPINDLE IN SOCKET IN
FWD BEAM. BORESIGHT WEAPON.
ACTUATE HOLD-DOWN DOGS AND
LATCHES. PIVOT AMMO FEED SYSTEM
INTO ENGAGEMENT WITH BREECH.

NOTE HOIST CABLES REMAIN
ATTACHED DURING FLIGHT

LATCH ENGAGED

Figure 7.   Left Weapon On-Loading During Hover Sequence

18

Figure 8. Aerial Artillery System Power and Control Schematic

19

The twin-hoist/retractable beam concept for providing loading and unloading from hover capability of the left-side weapon was selected after consideration of many alternates as the most simple, direct approach to answer this design requirement. In addition to the structure and mechanical complexities involved, the problem was also investigated from a human factors point of view. The step-by-step sequence of offloading and onloading the left weapon was examined by layout to ensure that this operation was not beyond the capabilities of the aircraft crew. The results of this layout study are summarized in Figure 7. The time required to offload the weapon and emplace for firing the first round depends on the situation on the ground. If the ammunition and gun crew are already on the ground, the terrain is suitable, and the howitzer can be lowered directly to the firing site, then the time required is mainly to set up the fire control sights and aiming stakes. Compared to setting up an XM204 field piece, the only additional times are about 30 seconds to lower the weapon to the ground and about one minute to remove the hoist cables and the three quick-attachment bolts that hold the adapter fittings to the howitzer.

The twin-hoist arrangement was selected to minimize weapon rotation, sway and pitch during hoisting operation in the hover mode. The retractable beam concept provides ease of removal and replacement of understructure, ample bearing surface for transmitting weapon static, vibratory and recoil loads to the airframe, and a convenient means of azimuth boresighting after onloading.

Weapon hoisting operations are controlled by two crewmen stationed at window numbers 2 and 3 on the left side of the aircraft. Each operator controls one hoist and one retractable beam. The hoists are standard lightweight, hydraulically-powered units with 2,000 pounds of operating load capacity at 100 ft/min lifting rate. Each hoist is attached to the end of a truss structure which is weapon kit-provided and when installed inserts into a hole in the upper fuselage and attaches to the airframe overhead structure. Vertical and longitudinal diagonal braces are provided outside to stabilize the hoist beam end. Hoist controls and hydraulic pressure and return lines are routed inside each hoist beam and are supplied with these kit-furnished items.

In addition to a winch control, each operator's station includes in/out control buttons for extension or retraction of the weapon support beams. These two support beams are of similar construction with an I-beam within a box beam. The inner I-beams are free to slide within the outer box beams which are fixed to the airframe. Each inner beam is extended, retracted, and secured by means of an airframe-mounted reversible electric motor driven pinion, meshing with a gear

20

rack on the bottom surface. The motors are wired through quick disconnects to switches at each operator's control station. The forward inner beam assembly incorporates an electrically-operated spindle latch for securing the weapon carriage. The aft beam assembly incorporates dogs which engage the aerial mount adapter channel upon retraction.

The right-side howitzer installation includes a fixed platform for crew operation on the ground. The suspension system is removed from this weapon and the traversing beam assembly replaced with a bracket and driven pinion which meshes with a gear rack on the underside of the platform edge. The traversing drive system is modified so that the azimuth handcranks drive the pinion, thereby training the gun in azimuth. A hand-actuated hydraulic jack to stabilize the platform against the ground is provided. The 4-man crew for ground operation of this weapon is carried aboard the aircraft. The gun may be trained 2,700 mils (150 degrees) from full forward in azimuth and -89 to +1,333 mils in elevation (by stopping the rotors with the rotor brake and moving the blades manually to an optimum position). For indirect firing on the ground with rotors stopped, the rotor blades must be rotated to provide maximum clearance for passage of the projectile and muzzle blast.

WEAPONS KIT AND HARDPOINTS PROVISIONS

The total aerial artillery system is attached to the CH-47C helicopter as a kit. Hardpoint provisions for attaching the kit are built into the selected airframe and do not compromise its use as a cargo or troop transport aircraft when the weapon kit is not installed.

The weapon kit (Figure 2) consists of the following:

1. Left-side XM204 Howitzer. Complete field piece with aerial artillery adapter fittings consisting of:

    a. Forward carriage spindle

    b. Aerial mount adapter channel

    c. Magnetic clutch plate

    d. Platform stabilizer

    e. Hoist harnesses

    f. Lanyard pull linear motor and electrical leads to carriage spindle

2. Right-side XM204 Howitzer. Modified to remove:

21

a. Suspension system

b. Traversing beam assembly

c. Forward cradle and lunette

d. Outboard portion of firing base

Add:

a. Bracket and pinion gear azimuth drive and linkage to handcranks

b. Weapon platform attach hardware

3. Forward and aft box beams, longitudinal support beams, and attach bolts.

4. Forward and aft retractable beams including latch dogs, spindle latch retraction motor pinions and gear racks, wiring controls and hardware.

5. Forward and aft weapon hoist assemblies including hoist beams, struts, hydraulic plumbing and controls.

6. Right-side weapon platform including secondary structure azimuth ring gear and attach hardware.

7. Fuel cell fairings (4).

8. Ammo feed systems, attach hardware, hydraulic and pneumatic plumbing and electric wiring and controls.

9. Internal fuel tank and tie-down hardware, fuel system plumbing and transfer system to auxiliary tanks.

10. Crew seats for nine men.

11. Fixed ammo racks (2) for 60 rounds XM204 ammo plus cargo deck tie-downs.

12. Ammo containers, drum type (2) with cargo deck tie-downs.

13. Laser rangefinder, control, mechanical innerconnect and HUD sight.

14. Retractable boresight tube and target.

15. Miscellaneous carry-on-board equipment including:

a. Fire control quadrant

 b. Aiming posts

 c. Plotting board

 d. Small arms

Hardpoints provisions (Figure 3) include:

1. Muzzle blast skin and glass doublers.

2. Bracketry and electrical leads for laser rangefinder, HUD, weight and control.

3. Pylon window for laser rangefinder.

4. Reinforcements for fuselage frames 160 through 360.

5. Forward and aft beam attach forgings.

6. Rotor brake installation.

7. Engine bleed air system modification to provide pneumatic power for ammo feed system.

8. Hydraulic system modification to provide increased capacity for weapon hoists and ammo feed system.

9. Fuel system modifications to accommodate elimination of main external tanks and incorporation of internal tank.

Hydraulic power to drive the hoists and ammo loader controls of the weapons kit is obtained from the ship's utility hydraulic system. The hardpoints kit will provide all the modifications to the hydraulic system which would be difficult to remove. These modifications would be similar to those which have been designed and fabricated for conversion of the CH-47C to the Model 347. The existing pump, mounted on the accessory drive gearbox, aft transmission, needs to be replaced with an increased capacity unit. No change is required to the mounting pad and attachments. Large diameter, low loss, pressure and return lines bypass the existing utility system valve and are routed forward along the right-side shoulder of the fuselage to system shutoff valves near station 312. These lines, pump and shutoff valves are part of the removable aerial artillery weapons kit and do not contribute to the empty weight of the aircraft when the kit is not installed. Some increase to the capacity of the present utility hydraulic system reservoir may be required to handle the added volume imposed by the weapons kit. Detail design and analysis of the kit hydraulic system will dictate the extent of this change.

As part of the airframe rework to incorporate the hardpoints

provisions, quick-disconnect connections for three additional
DC circuits will be installed in the aircraft. The weapon kit
will provide electrical power supply cables routed aft from the
DC junction box in the forward cabin to plug-in receptacles for
the aerial artillery kit near station 312. These cables will
be tied to the fuselage frames as necessary as the kit is
installed. Separate electrical receptacles will be provided in
the power supply calbes for the beam retraction, series-wound
high-torque motors and for the control and actuation systems
of each ammo feed system. Initial evaluation indicates that
no addition to the present ship's power generation system will
be required. Empty weight increase due to the added DC cir-
cuits is estimated to be negligible.

Pneumatic pressure for the ammo feed systems is supplied by
the CH-47C engine bleed air system. Only a small percent of
the 74 psia available from the customer bleed ports is needed
to transfer rounds from the ammo racks outboard and forward to
the standby tubes behind the weapons. The existing anti-ice
bleed port valves on each engine are replaced with valves
incorporating bypasses and a connecting manifold from which
the combined bleed flow may be ducted downward and forward to
a heat exchanger installed in one of aftermost cargo compart-
ment windows. Temperature of the air at this point should be
less than the 560°F at the bleed ports. Downstream from the
0.8 ft^2 heat exchanger, air temperature will be less than 160°F.
The bleed air manifold, ducting, and heat exchanger are included
in the ammo feed system weight and are part of the weapons kit.
Anti-ice bleed valves incorporating bypass ports for the ammo
feed system manifold will be part of the kit provisions. The
weight of these modified valves is estimated to be negligible.

INSTALLATION PROCEDURE FOR WEAPONS KIT

Installation of the aerial artillery kit to the hardpoints-
equipped CH-47C helicopter starts with the addition of the
hoist beam, strut, and hoist assemblies which weigh 96 pounds
each and are inserted and secured at the fuselage shoulders at
stations 160 and 320. Hydraulic power is connected to the
hoists, utilizing the modifications to the ship's system pro-
vided as part of the hardpoints kit to provide increased
capacity and the required connections. The main fuel cells
are removed from both sides of the aircraft are stored for
future reinstallation. The two box beams are positioned under
the helicopter. The aft box beam, which weighs 265 pounds,
may be lifted into place using the aft weapon hoist on the
left side and the screw-jack firing base on the right side,
and manpower to stabilize the load. The forward box beam
weighs only 77 pounds and may be manhandled into contact with
its hardpoint attachments on the underside of the aircraft.
The aft retractable beam may be inserted into its supporting
aft box beam using the aft winch plus manpower. The forward

retractable beam, weighing 469 pounds, can be inserted using manpower. After installation of the stiffening structure and the crew platform, right-side weapon may be ground-hoisted into position. Additional fittings could readily be provided so that the Chinook maintenance crane could be used to lift this howitzer into place if an additional crane is found to be required. The right-side weapon installation is complete when the azimuth drive pinion and platform gear rack are intermeshed. The ammo feed system assemblies are installed through the number 4 windows on both sides of the aircraft and adjusted to the breech location of the weapons. The internal crew accommodation, ammunition racks and drums, and auxiliary fuel system pick up existing cargo deck tie-down fittings. Left weapon boresighting equipment and fire control sight and ranger attach to previously installed hardpoints kit bracketry. Electrical, hydraulic, and pneumatic power supply for the kit are connected to hardpoints kit-provided quick disconnects. Routing of the required power supply lines is schematically shown in Figure 8. Kit installation procedure is complete after the attach fittings have been installed on the left-side howitzer and the weapon hoisted into place and secured on the support structure.

AUTOMATIC AMMUNITION FEED SYSTEM

For the air-to-ground firing mode, ammo loading is accomplished remotely from inside the aircraft using a mechanical feed system (see Figure 9). The rounds are hand-loaded into a pneumatic tube inside and transported by engine bleed air pressure to a rotating cylinder in line with the howitzer breech. Bleed air pressure is again utilized to move each round into the standby tube immediately behind the breech. From this point, an electric ram loads the round into the gun. The breech is opened and closed in sequence with the loading and firing by means of a hydraulic cylinder and magnetic clutch engaging an extension of the breech pivot. The total loader assembly is rotated upward hydraulically before firing. After firing, the casing is ejected upon opening the breech; and the casing is deflected downward into a net by a curved plate on the underside of the loader.

The ammunition feed system uses on-board pneumatic, electric and hydraulic power. It is quickly removable and is mounted in a window so it does not require a special opening in the fuselage structure. For ammunition supply to the right-side howitzer for ground-to-ground crew operation, the outboard element of the loader may be removed and the remaining tube utilized for transfer of rounds from inside for manual loading on the gun platform. A firing rate of 120 rounds per minute is possible in the aerial artillery air-to-ground mode using both weapons and the ammunition feed system.

25

COVER OVER NO. 4 WINDOW

HYDRAULIC CYLINDER ROTATES
LOADER UP FOR EJECTION
OF SHELL CASING

RUBBER BOOT

HYDRAULIC CYLINDER
ROTATES ROUND 90°
FOR LOADING

PNEUMATIC PRESSURE
FORCES ROUND INTO STAND-
BY TUBE AFTER ROTATION

TUBE GATE OPENS
AUTOMATICALLY WHEN
ROTATED IN LINE
WITH BORE

LOADING SPADE AND ACTUATOR
RAMS ROUND, CLOSES BREECH

SHELL CASE DEFLECTOR

MAGNETIC CLUTCH ENGAGES
BREECH PIVOT-HYDRAULIC CYLINDER
ROTATES PIVOT TO OPEN/CLOSE BREECH

LOAD AMMO INTO PNEUMATIC TUBE

PNEUMATIC PRESSURE IN

NOTE: ATTACH NET AFT & BELOW
BREECH TO CATCH EJECTED CASINGS

26

Figure 9.   Pneumatic Ammo Feed System Installation
in Number 4 Window

STRUCTURAL COMPONENT SIZING CONSIDERATIONS

The structural components of the weapons kit and hardpoints provisions, shown in Figure 10, are sized to provide load paths to carry loads generated by the weapon installation into the helicopter structure. Design of these load paths is complicated by the need for the ability to install the hardpoints provisions in the field during other maintenance. Also, these load paths must provide for rapid field installation of the weapons kit. In general, these load paths are sized by the 8g crash loads vertically and recoil malfunction loads laterally and longitudinally. The vertical and lateral crash load paths are along the box beams up through the fuselage bottom skin into the beam attach forgings and into the frames. Longitudinal loads are distributed to the structure by the longitudinal support beams and the lower longeron of the fuselage. Details of the calculations involved in sizing these components are presented in Appendix IV. In this section, the sizing of components for malfunction and crash loads is discussed based on limit load considerations, followed by a discussion of the sizing for normal flight and firing loads based on fatigue considerations. Vibration tuning of the mounting structure has also been considered to ensure that the large mass of the howitzer installation will not significantly increase helicopter vibration.

MALFUNCTION AND CRASH LOAD PATHS

Malfunction during firing of the weapons produce loads that design the supporting structure. These malfunctions may occur in flight or on the ground and may result in longitudinal ultimate design loads up to 36,500 x 1.5 = 54,750 pounds from either weapon in flight or the same load in a lateral direction from the right-side weapon on the ground. As with normal firing, malfunction loads originate at the barrel centerline and are transmitted to the firing base via the cradle, trunnions, and mount. Longitudinal loads from the left-side howitzer enter the two retractable beams through the adapter channel and spindle and are transferred to the box beams by means of internal bearing surfaces. The retractable beams are steel, American standard "I" cross-section with the webs oriented horizontally. The forward beam measures 5 x 12 inches; the aft one, 9 x 20 inches. The box beams are steel with .06-inch wall thickness and with internal dimensions to provide bearing surfaces for the retractable beams. From the box beams, the loads are taken in shear through bolted connections, four places, on the bottom corners of the fuselage. From these points, loads are taken in compression by the 2 x 2.5 x 1.88-inch wall, aluminum alloy channel section of the longitudinal

support beams which are added as kit items on the outside
bottom corners of the fuselage. It should be noted that the
elastic stability of these channels is ensured by their attach-
ment to the fuselage skin and frames. The loads are trans-
ferred from these beams through shear attachments over a 180-
inch length of the side and bottom fuselage skins to provide
adequate shear distribution to the stringers and longerons.

Loads from the right-side howitzer are taken from the firing
base through one 10 x 20 x .06-inch wall steel box beam with a
center web and weapon platform secondary structure for similar
shear distribution through the skins to the stringers and
longerons.

Right-side weapon malfunction recoil loads, during ground-to-
ground firing, are transmitted via the single main box beam mem-
ber and enter the fuselage corners as a lateral load which may
also have a downward component, depending upon the elevation at
which the weapon is fired. The lateral component of this load
is transmitted by means of the hardpoints provisions forgings
installed between frames 280 and 320 for shear distribution to
the bottom of the fuselage. The vertical component due to
weapon elevation comes out as tension and compression across
the bottom corners of the fuselage. With increases in eleva-
tion, an increasing compression load is transmitted to the
ground through the platform screwjack under the firing base.

Misfire loads are up to 29,250 pounds and in the opposite
direction from normal or malfunction recoil loads. With the
weapons pointing forward, misfire loads are reacted in an
opposite sense and come out as tension in the longitudinal
support beams at the corners of the fuselage. Load distribu-
tion in the airframe, however, is accomplished through shear
at the stringers and longerons over the same 180-inch length
of side and bottom skins as for the aft malfunction load.
Misfire at the right-side weapon creates tension in the main
box beam and is transmitted to the fuselage corners and comes
out as shear across the bottom skins. Misfires with the
weapon elevated produce the opposite effect from recoil mal-
functions. The load enters the airframe as compression and
tension at the fuselage bottom corners and is absorbed as
torsion in the fuselage cross-section.

LOAD PATHS FOR NORMAL OPERATIONS

In this study, it was found that only the hoist beam assem-
blies are designed by normal operating loads. This is mostly
due to the large magnitudes of the crash and malfunction loads,
but it is expected that subsequent detail design efforts will
show that normal flight vibratory loads design some portions
of the fittings and other structures. This will be particularly
true if the large vibration of the howitzers can not be reduced
by tuning of the structure. High-cycle fatigue damage of all

28

Figure 10. Aerial Artillery System Weapon Support Structure

the normally flight-loaded support structures needs to be studied in detail.

Normal operating loads design the hoist beam assemblies. The two identical weapon hoist structures are fabricated from 6 x 6 x .06-inch wall aluminum alloy box beams. The 16,800-pound load transmitted by the hoist structures is based on a 3g vertical load factor times 1.5 ultimate design load. Each hoist assembly is attached to the airframe at three points: two internally at the upper shoulder of the fuselage; and one at the outside lower corner. All points are bolted shear attachments. Hoist loads are reacted as torsion in the fuselage cross-section. Figure 11 shows the hoist beam assemblies.

Normal operating loads would also be expected to design some portion of the ammunition loaders. These lightweight loaders will experience many cycles of fairly high loads as the rounds are transported into the howitzers. The loaders also experience helicopter vibration, and the supporting structure will have to be tuned to provide vibration isolation. Resolution of these problems needs to be accomplished during detail design.

WEAPON AND HELICOPTER VIBRATION PREDICTION

Results of the dynamic analysis of the CH-47C helicopter with the weapons kit installed show a generally satisfactory preliminary design and are summarized in Figure 12. These results show that the longitudinal and lateral accelerations of the howitzers are large (about 0.5g) with reduced helicopter vibration. This indicates that the howitzers are acting as vibration absorbers in the lateral and longitudinal directions. Vertical accelerations of the howitzers are small with significantly increased helicopter vibration. The vertical stiffness of the mounting structure is such that the vertical motions of the howitzers are isolated from the helicopter. This design is acceptable for helicopter vibrations if additional vertical vibration absorbers are provided.

The predicted howitzer vibration causes 3 mils maximum angular excursion of the barrels, which is a small part of the total aiming error. This vibration magnitude needs to be considered further since it could introduce fatigue loading problems in the hardpoints attachments. In subsequent detail design efforts, continued detail dynamic considerations of the howitzer attachments are necessary. Somewhat increased vertical stiffness and reduced lateral and longitudinal stiffness should be explored to reduce vibration changes to the treatments for vibration reduction such as the existing vibration absorbers and cargo floor isolation.

The methodology used in this study calculates the response of the analytical model of the airframe as a result of the

30

LONGITUDINAL +
STABILIZER STRUT

AFT HOIST BEAM +

CH-47C FUSELAGE

FWD HOIST BEAM +

VERTICAL SUPPORT +
BEAM

LONGITUDINAL +
STABILIZER STRUT

FWD

VERTICAL SUPPORT +
BEAM

+ INDICATES REMOVABLE
KIT FURNISHED ITEMS

Figure 11.   Aerial Artillery Left Weapon Hoist Structure

31

Figure 12. CH-47C and CH-47C AAWS 3/Rev Vibration Comparison

32

predicted rotor loads from the D-88 rotor aeroelastic analysis.
In previous studies, this analytical vibration prediction
method has shown excellent agreement with measured flight data.
The validity of the airframe analytical model has also been
substantiated by extensive ground shake testing. The CH-47C
airframe analytical model provided the baseline structural
model on which the aerial artillery weapons and support struc-
ture were superimposed. The nodal grid system of the CH-47C
airframe and that of the weapon supports is shown as Figure 13.
The basic structural representation of the CH-47C airframe
contains 2,142 structural elements and 1,745 nodal degrees of
freedom. This array has been reduced as a result of previous
studies to 133 degrees of freedom. For this study, the air-
craft was divided into four substructures: forward pylon, gun
support structure, mid-cabin, and aft pylon. The substructures
used in the analytical solution are also shown in Figure 13.
Modifications were made to the baseline configuration in sub-
structure number 2 which extends from fuselage stations 160
to 320 for support of the weapon platform. Idealization of
the structure in this region required 80 additional structural
elements. The remaining substructures were identical to that
of the baseline aircraft. Three linear motions and three
rotations were considered to be an adequate definition of the
weapon system dynamic response at the CG position of each gun.

The vibration solution flowchart for the AAWS study is given in
Figure 14. Each substructural stiffness matrix was generated
separately and merged into a total system stiffness matrix which
is reduced to 138 degrees of freedom for the dynamic response
solution. Considering the discrete mass of each retained
degree of freedom, the dynamic matrix is formed and solved
for the eigenvalues and eigenvectors. Using a modal represen-
tation of the structural dynamic properties, i.e., natural
frequencies and modes, the airframe vibration resulting from
the predicted flight loads (D-88 aeroelastic rotor analysis)
is determined by a damped forced response solution. The solu-
tion requires approximately 2-1/2 hours of IBM 360/65 computer
usage with 1/2 hour to generate a weapon platform substructure
and approximately two hours to merge the subsystem and perform
the dynamic solution.

In the design of the aerial artillery weapon kit supports and
attachment structures, the dynamic requirements considered were:

- Acceptable (3/rev) fuselage vibration

- Vibration of the weapon platform must be sufficiently
  low to allow adequate sighting accuracy of the guns
  in the firing mode.

The baseline configuration considered was a CH-47C aircraft
with no vibration treatment and having a gross weight of

33

SUBSTRUCTURE	LOCATION	PROMINENT ITEM
1	STA 0. – 160.0	FWD PYLON
2	STA 160. – 320.	GUN SUPPORT
3	STA 320. – 482.	MID CABIN
4	STA 482. – 594.	AFT PYLON

Figure 13. Structural Model System Used for Dynamic Analysis

Figure 14. Flow Diagram for Airframe Forced Vibration Calculations

20,000 pounds. The weapon and supports for transporting and
firing a right and left-side 105mm howitzer were assumed to
add approximately 3,200 and 3,750 pounds, respectively. The
assumed gross weight was significantly less than that which
resulted from the final design.

Natural frequencies of the helicopter with the howitzer instal-
lation and the baseline aircraft are tabulated in Table III.
As shown, the weapons kit causes two new frequencies to appear
which are the first and second vibration modes of the gun on
the support beams. Preliminary sizing of the support structure
provided for isolation of the vertical gun motion from airframe
excitation by tuning the uncoupled vertical symmetrical bending
mode of the weapon platform below the 3/rev forcing frequency.
As illustrated in Figure 15, the gun modes resemble the first
bending and first chordwise modes of a high aspect ratio wing.
Further, it is noted that the only frequencies significantly
altered with the attachment of the weapon system are those
frequencies for modes which contain significant lateral motion.
This can be attributed to the high lateral stiffness of the
gun installation which approximates a rigidly-mounted lumped
mass attached to the helicopter in the lateral direction. In
the vertical direction, the right and left gun masses are
virtually isolated from the fuselage as a result of the soft
vertical stiffness of the support beams. The most significant
frequency change occurs in the fuselage racking mode, the fre-
quency of which is reduced from 11.09 to 7.71 cps. This change
is attributed to the relatively large mass of the gun support
system rigidly attached laterally to the airframe and acting in
a mode with significant lateral motion. The vibration modes
which contribute most of the vibration are illustrated in
Figure 16.

A summary of predicted vibration levels is presented in
Figure 12 and discussed in detail in the following:

LONGITUDINAL VIBRATION

Fuselage

Longitudinal vibration forward of fuselage station 300 with
the howitzer-equipped aircraft is comparable to the acceptable
levels of the baseline aircraft. In the aft pylon region, the
vibration with the howitzer installation is approximately twice
that of the basic aircraft. Since this region is unoccupied,
this increase in vibration is probably acceptable, but component
stresses would have to be checked.

Gun CG

Longitudinal vibration of the howitzer at 0.45 g's is approxi-
mately nine times that of the fuselage at the attachment. The

TABLE III
MODEL CH-47C AAWS AND CH-47C FREQUENCY COMPARISON

MODE NO.	AAWS FREQ – CPS	CH-47C FREQ – CPS	DESCRIPTION
1	5.93	6.17	AFT PYLON LATERAL
2	6.33*	--	FIRST GUN MODE (VERT. BEND)
3	7.71	11.09	LAT. MODE (FRAME RACKING)
4	8.33	8.31	AFT PYLON LONGITUDINAL
5	9.21	9.83	LATERAL MODE
6	12.22	12.20	...D PYLON LONGITUDINAL
7	13.96**	--	SECOND GUN MODE (TORSION)
8	14.41	14.41	VERTICAL MODE
9	14.85	14.55	LATERAL MODE
10	15.02	15.70	LATERAL MODE

* FIRST GUN SUPPORT MODE

** SECOND GUN SUPPORT MODE

37

FIRST GUN MODE
f = 6.33 CPS

SECOND GUN MODE
f = 13.96 CPS

Figure 15. CH–47C AAWS Gun Support Modes

38

CH-47C AAWS
f = 7.71 CPS

CH-47C AAWS
FWD HUB LONG.
f = 12.22 CPS

CH-47C
f = 11.09 CPS

CH-47C
FWD HUB LONG.
f = 12.20 CPS

Figure 16. Critical Mode Comparison, CH-47C and CH-47C AAWS

39

high longitudinal vibration of the gun CG is attributed to force excitation of the second gun mode at 13.96 cps. Howitzer yaw angle displacement resulting from this vibration is approximately 3 mils.

LATERAL VIBRATION

Fuselage

A significant reduction in lateral vibration is apparent for the weapon configuration. In the CH-47C aircraft, the lateral vibration results primarily from excitation of the 11.09-cps mode as shown in Figure 16. For the howitzer-equipped aircraft, the above frequency was reduced to 7.71 cps, resulting in a decrease in response from the 3/rev excitation.

Gun CG

Lateral vibration at the howitzer is predicted to be of the same magnitude as the longitudinal vibration. Similarly, the large lateral vibration can be attributed to excitation of the second gun mode at 13.96 cps.

VERTICAL VIBRATION

Fuselage

Vertical vibration increases in the cabin for the with-howitzer configuration. In the baseline aircraft, vertical response results from excitation in both the 11.09-cps and 12.22-cps modes as shown in Figure 16, but the response phasing is such that cancellation results. However, for the howitzer support aircraft, the 11.09-cps mode is lowered to 7.71 cps, eliminating the response cancellation which results in higher vertical vibration. Cockpit vibration is of similar magnitude, and aft pylon vibration shows a decrease of approximately 25 percent. It is noted that the cockpit vibration levels shown are well above the Military Specification requirements, but these levels are for the aircraft without vibration absorbers. As in the CH-47C aircraft, the installation of the production aircraft absorber configuration would reduce the vertical vibration to the specification levels.

Gun CG

Vertical vibration of the gun is less than 0.1g as a result of the vertical isolation of the first gun mode.

COMPONENT VIBRATION TESTING

All nonstructural components shall be vibration tested in accordance with the Boeing-Vertol component vibration

40

qualification document for the CH-47C helicopter (114-DY-019-1). This testing is designed to detect weaknesses in design or construction which may cause component failure or malfunction when subjected to the vibration environment of the CH-47C.

HANGING SHAKE TEST

It is recommended that the howitzer/CH-47C helicopter configuration be subjected to a hanging shake test. The purpose of such testing is threefold:

1. To ascertain the location of predicted CH-47C modes with aerial artillery installed.

2. To determine the existence of any structural and artillery mounting resonances and their proximity to CH-47C rotor order excitation.

3. To allow probing of the installation for points of highest stress concentration for optimum location of instrumentation during the flight-test evaluation.

MUZZLE BLAST AND FLASH EFFECTS

Firing of the 105mm howitzer in close proximity to the CH-47C helicopter requires the addition of protective doublers and reinforced hatches in the forward portion of the fuselage shown in Figure 17. Rationale for the design of these reinforcements is described in this section. Detailed calculations involved are presented in the Stress Analysis, Appendix IV. The muzzle blast reinforcements are added to the helicopter as part of the hardpoints provisions kit.

Secondary ignition (flash) of exiting muzzle gases, a phenomenon which can increase blast pressure fourfold, has not influenced the design since it rarely occurs with the 105mm round. With the protection provided, if flash would occur, some damage to the reinforced skin areas would be likely; and some sheet-metal repairs would be required. Development of new rounds, such as the zone 8, could make flash more likely; and some protection from flash may be found to be desirable. A muzzle flash suppressor, such as described in Reference 5, appears to be the best approach to provide flash protection if flash can not be prevented in the development of the round. This device alters the aerothermodynamics of the escape of the gun gases from the muzzle so that flash is prevented. This device would also prevent the occurrence of the visible light produced by the flash phenomenon and would therefore also protect the pilot's vision in night flying.

REINFORCEMENT OF FUSELAGE SKIN

This study has determined that protection against the loads induced by muzzle blast overpressures is required for skin areas adjacent to and forward of the gun muzzles. Figure 17 shows the section of the fuselage for which a skin doubler is required. Design of the doubler is based on calculations of the free-space overpressures for the 30-inch extended-barrel version of the XM204. The Salsbury report (Reference 6) provides the necessary formulae and general blast field solution curves needed for these calculations. In general, the longer barrel allows more complete burning of propellant, providing greater muzzle velocity and a consequent reduction in blast pressure of approximately 20 percent. The free-space overpressure isobars for zone 5 are shown projected on the fuselage of the aircraft in Figure 18. It should be noted that these curves represent only the free-space blast pressures produced by the weapon. Impingement of this pressure wave on the fuselage skin creates a reflected wave with attendant increases in pressure. This phenomenon is well treated by Kinney (Reference 7). From Figure 5 of Reference 8, it was determined that for the range of free-space overpressures and angles of incidence involved, the reflected overpressures range from two to three times that of the incident wave.

42

REINFORCED PILOTS
ESCAPE HATCH WITH
0.40 THICK PLEXIGLAS
TRANSPARENT AREA

REINFORCED
ESCAPE HATCH
WITH 0.40 THICK
PLEXIGLAS

MUZZLE

DOUBLER
0.065 ALUMINUM

Figure 17.   Aluminum Doublers and Reinforced Hatches are Required
on Both Sides o. Nose of Fuselage

43

DURATION OF THE OVERPRESSURE
IS ESTIMATED TO BE .003 SECONDS.

XM 204 WITH 30" EXTENSION
MUZZLE AT 8" OUT OF BATTERY

PLAN VIEW

₵ AIRCRAFT

1.0
1.3
2.0
2.7
4.0

1.4 PSI
2.0 PSI
2.7 PSI
3.2 PSI
3.6 PSI
4.0 PSI
WL-7   ₵ BARREL
1.0 PSI

4.5 PSI AT INITIAL CONTACT
WITH FUSELAGE SKIN

₵ BARREL

₵ BARREL
CH-47C
PROFILE

₵ AIRCRAFT
102"

| 0 | 21.50 | 51.75 | 70.5 | 95.0 | 120.0 | 140.0 | 160.0 | 180.0 | 200.0 |

SIDE VIEW

FRONT VIEW

Figure 18.   Fuselage Projection of the Free-Space Overpressures Due
to Zone 5 Firing of the Extended-Barrel XM204 Howitzer

44

As skin panels must be protected against an inadvertent firing of a zone 8 round when the weapon is in a forward-firing air-to-ground mode, it was necessary to calculate the free-space and resulting reflected pressures involved. As a new zone 8 round is still under development and the propellant type and weight not yet specified, it was necessary to extrapolate a plot of muzzle velocity to the desired 2,200 ft/sec to determine the associated weight of standard M-1 propellant. Using this approach, an estimated value of 4.5 pounds was determined; and this was used to calculate the peak reflected overpressures for the panels in question.

To determine the thickness of skin necessary to withstand these overpressures, use was made of the blast damage criteria established by Sewell and Kinney (Reference 9). The natural frequency of a critically located panel (shown in Figure 19) was calculated, and a critical time equal to 1/4 of its period was found. From this critical time and the peak overpressures expected (multiplied by a 1.5 factor of safety), a critical impulse was calculated which is the minimum load which, if applied to the panel, would result in damage. As the critical impulse is a function of the panel thickness, speed of sound, and dynamic yield strength, the formula for critical impulse was solved for thickness.

The Appendix IV detail calculations show that for the most critical panel, a reinforcement thickness of .065 inch is required. As a conservative first estimate of the size and weight of the doubler, the .065-inch thickness required for the peak pressure was kept constant over the entire area. In addition, an elastomeric shock absorption material (such as rubber or neoprene) should be sandwiched between the panel and doubler to reduce the vibration and acoustic effects of the blast. Detailed specification of this isolator needs to be addressed in the subsequent program.

STRUCTURAL REINFORCEMENT

Blast loads are taken by the doubler through the fuselage skin and into the fuselage frames. The preliminary design philosophy that all added loads will be taken by reinforcements would require that the fuselage frames be treated. The weight of such reinforcements is of small magnitude and the detail design may show that these reinforcements are not required. Therefore, these structural members have not been treated in this study.

PLEXIGLAS REINFORCEMENT

The Plexiglas areas shown in the Figure 17 sketch must be reinforced to withstand the reflected overpressures produced by the accidental firing of a zone 8 round during air-to-ground

Figure 19.   Location of the Most Critical Panel
of Fuselage for Muzzle Blast Damage

mode. A detailed dynamic stress analysis of the circular
window of the fuselage escape hatch and the pilot escape door
is presented in Appendix IV.

The analysis employed used predicted zone 8 incident over-
pressures to calculate the reflected pressure loads on the
Plexiglas. A dynamic yield coefficient of 2.0 was assumed (as
contrasted with a coefficient of 3.7 for aluminum); and using
the allowables for Plexiglas, the thickness of Plexiglas
required was found by a dynamic stress analysis to be 0.4 inch.
A similar analysis determined the more distant, but larger,
pilot escape door to require the same thickness of Plexiglas.
Should a reduction in Plexiglas thickness be desired, rein-
forcing strips can be employed down the middle of the Plexiglas
to help take the added load.

ROTOR BLADE LOADS, STRESSES, AND RESPONSES

Rotor blade stress analyses and aeroelastic calculations of
rotor blade loads and responses have been made to determine if
rotor system modifications are required to allow repeated firing
of the howitzers at zone 5 in the air-to-ground mode. These
calculations are not necessary for ground-to-ground attached
firing. For air-to-ground firing, the calculated loads are found
to be small as compared to the strength of the parts and no
modifications are required. Firing zone 5 in this mode will
cause no reduction in the fatigue lives of the rotor system
components, and considerable margin exists for firing higher
charge zones. These analytical results are in good general
agreement with the experimental data on the effects of blast
on rotor blades reported in Reference 1.

Stresses in the rotor blades have been calculated in a conser-
vative manner by adding the maximum flight maneuver stresses
to the stress increment caused by muzzle blast. As shown in
Figure 20, the ultimate blade spar stresses are increased
less than 10 percent by the blast loads and are well within
the ultimate allowables. A similar result is shown in Figure
21 for fatigue stresses. Aeroelastic calculations of rotor
control pitch link loads show that the blast load is attenuated
by a factor of about 5. The resulting pitch link load will not
cause fatigue damage in the control system when superimposed
on the flight loads. Details of the blade stress calculations
and the margins of safety are given in the Stress Analysis,
Appendix IV.

Aeroelastic calculations of rotor loads due to muzzle blast
utilized five flapwise bending modes and two torsional response
modes with the spanwise distribution of blast pressure shown
in Figure 22. This pressure representation is a conservative
simplification of the worst case of the interaction of the
pressures shown in Figure 23 with the blade. Flap bending

47

Figure 20. CH-47C Spar Ultimate Maneuver Stresses as Affected by
Muzzle Blast Pressure

Figure 21. CH-47C Spar Fatigue Stresses as Affected by Blast Pressure

NOTE: PRESSURES SHOWN ARE FOR ZONE 5 CHARGE FROM
A STANDARD-BARREL XM204. USE OF A 30-INCH
BARREL EXTENSION WOULD REDUCE OVERPRESSURES
BY APPROXIMATELY 20 PERCENT.

2.1 PSI PATTERN AT PLANE OF ROTOR

SIDE OF HELICOPTER

XM 204 MUZZLE

MAX POSSIBLE AREA OF
ROTOR SYSTEM TO BE
EXPOSED 1.7 PSI & ABOVE = 15.3 FT^2

1.7 PSI PATTERN
AT PLANE OF ROTOR

PLAN VIEW

2.1 PSI
(ESTIMATED)

PLANE OF FWD
ROTOR

1.7 PSI

1.7 PSI

1.2 PSI

2^0

2.1 PSI

2.5 PSI

2.5 PSI

3.5 PSI

3.5 PSI

102"

WL-7

AIRCRAFT

XM 204
MUZZLE

XM 204 MUZZLE

FRONT VIEW

WEAPON

SIDE VIEW

Figure 22. Projection of Overpressure Isobar Pattern on Forward Rotor

50

Figure 23. Muzzle Blast Pressure Pulse Representation
Used in Aeroelastic Rotor Loads Calculations

51

moments, torsional moments, pitch link loads, and flap and torsional deflections are determined for two different pressure pulse durations. The results for t = .0015 second correspond to the loads expected on the rotor blade due to the expected pressure blast from the XM204 weapon. The time history of the actual pressure blast starts out at a value of 1.0 at t = 0 and goes to zero at t = .003 second that is a triangular shaped impulse. To simplify the calculations, the actual triangular shape was replaced by a rectangular pulse of half the duration. This simplification does not change the results since the ratio of the impulse duration to the natural periods of the flap and torsion natural frequencies is small so that the shape of the pulse is inconsequential and the blade response depends only on the impulse area. Results shown for t = .003 second are included to show how the blade response would increase if the pressure load impulse were doubled.

The load calculations were made using generalized coordinate theory to obtain the linearized equations of motion and generalized forces. The generalized flap and torsion loads being

$$Q_{Fn} = f(t) \int c\, p(x)\, Z_n(x)\, dx$$

$$Q_{Tn} = f(t) \int c^2\, p(x)\, (1/2 - PA)\, \theta_n(x)\, dx$$

where

$f(t)$ = the time function applied to the rotor blade

$p(x)$ = spanwise distribution of blade loading due to pressure blast

c = blade chord

$Z_n(x)$ = flap bending deflection mode shape

$\theta_n(x)$ = torsional deflection mode shape

Values were calculated for the mass, spring, and damping matrices as well as for the generalized forces. Utilizing Boeing Computer Program L-33, the flap response and torsional response of the blade were determined. Blade flapwise and chordwise bending and torsional moment distributions were calculated from these responses.

Response of the blade to blast results in the flapwise moment distribution shown in Figure 24. The peak moment of about 8,800 in.-lb at about 15 percent radius is approximately 1/8 of the normal vibratory bending moment caused by flight at 130 knots. This change is a negligible increase in load. As shown in Figure 25, the predominant response of the blades to the blast results from the rigid body rotation of the blades about

52

Figure 24. Flapwise Bending of Blades Due to Zone 5
Muzzle Blast

53

NOTES:

1. CH-47C ROTOR BLADE

2. ROTOR SPEED - 230 RPM

3. ZONE 5, DOUBLE LOAD

Figure 25. Flapwise Excursion of the Blades is Predominantly Rigid-Body Motion

54

the flapping hinges. Elastic bending of the blades causes only about 1/3 of the flapwise excursion.

The torsional response of the blade due to the blast, shown in Figure 26, results in the loads in the control system shown in Figure 27. This load was initially of concern since the static load, as shown on the figure, is 5,400 pounds; however, the dynamic calculations show that due to the short duration of the impulse, this load is attenuated by a factor of about 5. The 1,200-pound control load predicted is small as compared to the fatigue strength of the control system. Dynamic response of the blade tip twisting to the expected muzzle blast load is shown in Figure 28 to have a double amplitude of about 1.7 degrees. This response is of a high frequency, about 9/rev, and contributes to the blade flap bending response, but it has no other significance.

Figure 26.   Torsional Moment Distribution Due to Blast

Figure 27. Rotor Control Pitch Link Loads Due to
Muzzle Blast

Figure 28. Blade Tip Twisting Deflection Due to Muzzle Blast

DYNAMIC RESPONSES OF AIRCRAFT TO WEAPON FIRING

Dynamic calculations have been made to determine the need for additional reinforcements and protection of the aircraft from recoil and muzzle blast effects when the time history of the loading is considered. Blast and recoil loads are both impulses. Blast has an almost instantaneous pressure rise time and the pressure decays in a nearly-triangular manner back to ambient in about .002 seconds. Recoil of the XM204 soft howitzer is a rectangular pulse with a duration of about .4 second. All the dynamic systems of the helicopter will be perturbed by the firing blast and recoil impulses, but the significant responses will occur only in those systems with sufficiently large natural frequencies that the load is not attenuated. This is illustrated in Figure 29 which shows that for the blast and recoil pulses, those dynamic systems with natural frequencies greater than 250 and 0.5 Hz, respectively, must be considered. The 250 Hz limit for blast loads is so high that most of the helicopters' dynamic systems will attenuate blast loads. Structural panel natural frequencies are greater than 250 Hz; and therefore, the hydraulic response of these panels has been included in the stress analyses involved. Systems with lower natural frequencies (for example, the rotor blade response to blast which was presented in the previous section) show little dynamic response to blast as a result of the attenuation. This is in contrast to recoil loads which will excite almost all of the dynamic responses of the helicopter. Responses above the 0.5 Hz limit for recoil loads include almost all the elastic responses and most of the rigid body responses including the flying qualities modes. Fortunately, all these responses appear to be of such low magnitude with the soft recoil howitzer in the design configuration, no load protection or structural reinforcements are required. Results of the various response analyses performed are discussed in further detail in this section.

DYNAMIC RESPONSES TO MUZZLE BLAST

The only significant responses of the helicopter to muzzle blast will be:

- Rotor blade dynamic motions and elastic deflections

- Fuselage nose panel elastic deflection

- Fuselage frame elastic deflections

The dynamic responses of the blades and panels are discussed in the previous section and in Appendixes III and VII. Fuselage frame dynamic responses were studied in Reference 1, and this methodology should be applied when the detail design

Figure 29. Single-Degree-of-Freedom Analysis Illus-
trates Significant Modes of Response

60

of the aerial artillery installation is executed. Some frame reinforcement may be necessary, depending on how well the skin doubler spreads the load into the frames. The weight involved in such reinforcements is small so the preliminary design of these items was not attempted in this study.

AIRCRAFT RESPONSE TO RECOIL LOADS

The motions of the helicopter due to the recoil force from firing one of the howitzers in the air-to-ground mode have been calculated. These motions are generally shown to be less than two-degree excursions if the pilot made no control corrections. Control motions required to completely negate the recoil effects involve displacements of less than one inch which are held for about 1/4 second. These control inputs could easily be accomplished by the pilot; or for more rapid corrections, the inputs could be made automatically through the stability augmentation system. This analysis shows that from helicopter motion considerations, the added complication of adding impulse generators on the weapons is not warranted.

Attitude time histories were obtained by the digital solution of the helicopter equations of motion to estimate the transient response characteristics to arbitrary time variations in specified forcing functions. The primary forcing function in this instance was the howitzer recoil which had the impulse and duration as a function of firing zone shown below.

Zone	Impulse (lb-sec)	Duration at 5,000 Pounds (sec)
1	721	.144
2	782	.156
3	870	.174
4	973	.195
5	1,133	.226
6	1,370	.274
7	1,751	.350
8	2,266	.454

Yaw and roll responses were of primary interest and were examined as a function of parametric variations in aircraft gross weight, center of gravity, airspeed, firing zone, and restoring pedal displacements.

In general, the data indicate that the yaw and roll attitude displacements from trim following assymetric firing of one of the howitzers are relatively small. The time histories shown in Figures 30 through 33 indicate that above airspeeds of 60 knots, the motion is adequately damped and maximum yaw excursions of 1.0 to 1.3 degrees from trim and experienced. Roll attitude deviations from trim are less than 1.0 degree.

Aircraft configuration (i.e., gross weight and CG variation) has little influence on resulting attitude motion. Differences of less than 0.3 degree are shown in Figures 32 and 33 for the entire weight and CG envelope tested.

Figure 30 shows that low damping and stability at hover and low speeds (below 60 knots) allows yaw attitude deviations from trim of 4.0 degrees within three seconds. The associated yaw rates experienced were on the order of 1.0 to 2.0 deg/sec, which is extremely low.

The effects of varying the firing zone (impulse time) were investigated, and the data relative to the minimum and maximum zones is presented in Figure 31. A maximum difference of 1.5 degrees exists between yaw responses to zone 1 and zone 8 firings. The maximum displacement from trim was 2.1 degrees for the zone 8 firing.

One method of reducing the aircraft displacement from trim due to gun recoil is to introduce simultaneously with the firing impulse an equal and opposite control impulse. This method was investigated and the results are presented in Figure 34. The .75-inch equivalent pedal input reduced the yaw motion to approximately 0.1 degree.

ELASTIC RESPONSE OF FUSELAGE TO RECOIL LOADS

A generalized coordinate analysis was made to determine the response of the fuselage to the recoil impulse from the XM204. The impulse size used was 2,000 lb-sec with a duration of approximately .4 second. The analysis considers nine elastic fuselage mode shapes coupled with the howitzer in its mounted position. The summation of all nine modal contributions to the fuselage elastic deflection response in the longitudinal, lateral, and vertical directions is determined at several points on the fuselage. Shown in Figure 35 is the response at the cockpit in three directions. A maximum acceleration of .14 g's in the vertical direction at the cockpit was determined from this displacement response.

SUSTAINED FIRE EFFECTS

Sustained firing of the weapon at firing rates up to 30 rounds per minute will not give loads of greater magnitude than a

single firing. A single firing of the weapon can cause a maximum dynamic amplification factor of two since the modal frequencies are relatively short. However, for the case of sustained firing, the impulse loads occur periodically which give rise to many harmonics of forcing. Three items become important: (1) do any of the firing harmonics come close or coincide with an aircraft modal frequency; (2) do the modes which have modal frequencies close to the firing harmonics have large modal deflections at the location of the weapon positions in the aircraft; and (3) how long does the sustained firing last. If a combination of items (1) and (2) does exist, that is, a harmonic of the sustained firing load vs. time waveform is close to the natural frequency of an aircraft mode and that mode does have large modal deflections at the weapon location, a large dynamic amplification of the aircraft response will occur. With typical structural damping of aircraft structures, the maximum dynamic amplification will be approximately 17. However, the dynamic amplification factor is offset by the fact that the magnitude of the harmonic component near the resonant frequency will be much smaller than the magnitude of the impulse load. For example, a rectangular impulse load of magnitude 5,000 pounds lasting 0.4 second fired every two seconds contains a 6-cps frequency force magnitude of 290 pounds which is a factor of 1/18 the impulse magnitude. Also, even if this is the case, the maximum dynamic amplification will not be attained immediately; some length of time will be required to reach this. Item (3), the time of sustained firing, is therefore an important consideration.

NOTE: ASSUMES RIGHT HOWITZER FIRES ONE ROUND AND
PILOT MAKES NO CONTROL CORRECTiONS

Figure 30. Responses to Recoil Are Reduced With Increased Airspeed

64

GROSS WT	—	45,000 LB
AIRCRAFT C.G.	—	STA 325
AIRSPEED	—	100 KTS
FIRE ZONE	—	NOTED

Figure 31. Responses to Recoil Increase With Increased Firing Zone

NOTE: ASSUMES RIGHT HOWITZER FIRES ONE ROUND AND PILOT MAKES NO CONTROL CORRECTIONS

Figure 32. Helicopter Responses to Recoil Do Not Vary Much With Gross Weight

66

Figure 33.   CG Variations Have Small Effect on Responses to Recoil

NOTE: ASSUMES RIGHT HOWITZER FIRES ONE ROUND

GROSS WT	—	45,000 LB
AIRCRAFT C.G.	—	STA 325
AIRSPEED	—	100 KNOTS
FIRE ZONE	—	5

Figure 34. Small Control Inputs Can Correct the Effects of Recoil

Figure 35. Deflection Response of the Cockpit Due to the Recoil Load from a Single Firing of One Weapon

EFFECTS OF GUN GAS INGESTION AND
MUZZLE BLAST ON ENGINES

The impact on the helicopter engines of ingesting the hot gun gases and the overpressures emanating from the aerial artillery muzzle blast has been evaluated. In addition, for air-to-ground firing, the possible effect of impulse generator exhaust on the engine inlet flow was also assessed. The latter would appear to be potentially a more severe problem due to the proximity of the impulse generator and the engine inlet, but neither the hot gases from firing nor the impulse generator exhaust was found to pose a serious ingestion problem for the engines.

AIR-TO-GROUND FIRING

The rate of discharge of expended propellant and the magnitude of the rotor downwash were determined to assess the severity of the hot gas ingestion problem when firing from the hovering helicopter. At design gross weight, the disc loading of the 60-foot-diameter CH-47C rotor is 5.82 psf, and the corresponding rotor downwash is 15,100 lb/sec. For the 105mm howitzer, the following assumptions were made:

- Zone 7 propellant charge, 2.82 lb (conservative calculation)

- Conversion factor, propellant to hot gas - 95 percent

- Firing rate - 100 rounds/minute

The hot gas resulting from muzzle blast is:

$$2.82 \times 0.95 \times \frac{100}{60} = 4.46 \text{ lb/sec}$$

The hot gas is such a minute fraction of the rotor downwash, no ingestion problem is judged to exist; and the downwash would direct the hot gas away from the engine inlet in addition to diluting it.

Experimental determinations of the blast fields resulting from firing the 105mm howitzer indicate that peak overpressures of approximately 0.5 psi can be anticipated at the engine inlet located 28 feet from the muzzle. Engine manufacturers have evaluated the effect of such incident overpressures and have determined that they will have no significant effect on engine operation. The opinion of the engine manufacturer is that the pressure sensor of the fuel control will not even note the occurrence of the transient overpressure due to the high velocity of the blast wave. Neither will the overpressure precipitate compressor stall since stall is triggered by

pressure distortion at the engine inlet rather than uniform overpressure. Engine problems encountered to date which were associated with weapons fired from aircraft have been the general result of very rapid changes in inlet temperature, a factor which is not of concern according to the above discussion.

The impulse generator rocket motor would have exhaust gases at approximately 4,000°F moving at a velocity of 8,000 ft/sec. In the low velocity field of the downwash from the helicopter rotor, the boundaries of this exhaust plume would remain clearly defined. In the plane of the engine inlet, 13 feet aft of the howitzer breech, plume diameter would be four feet; and the plume would completely bypass the engine inlet -- downwash would only serve to deflect the rocket motor exhaust downward, away from the inlet.

GROUND FIRING

The mission scenarios established for aerial artillery include firing the 105mm howitzer on the ground; however, in this application, the impulse generator would not be employed so only the effects of muzzle blast were considered. The howitzer can be fired broadside to the aircraft on the ground, and this mode of firing results in the muzzle being 22 feet from the engine inlet.

For the ground-firing scenario, helicopter rotor blades would be stopped and the engines running at the ground idle setting. The condition is not amenable to analysis, but some simplifying assumptions were made to calculate approximate results. Assuming that 10 rounds were fired in a one-minute period and that the hot gas from firing was dissipated uniformly throughout the surrounding air, a temperature increase of approximately 30°F was calculated for the engine inlet airflow. This result would indicate that the hot gas ingestion problem is not too severe. However, it must remain for actual firing in varying wind conditions to indicate the actual severity of the problem.

WEIGHT, BALANCE, AND CONTROL

The aerial artillery weapons kit consists of heavy fixed and removable components as well as large fuel and ammunition loads so weights and balance have been considered in detail. Substantiation of component weights is presented in Appendix V with detail weight summaries for the design missions presented in this section. The unusual center-of-gravity positions that can be produced as a result of the aerial artillery installations are shown by analysis to introduce no significant problems of stability and control. The change in the balance of the helicopter as the left (removable) howitzers is lowered to the ground from hover is shown to involve only small changes in control.

DESIGN MISSION LOADINGS

The design missions all start with the same equipment on board at takeoff. Table IV shows the effect of the fuel system changes, the addition of the hardpoints provisions, and the weapons kit less howitzers on the weight and balance. The weight empty of the CH-47C from Spec 114-PJ-7103 was used as the basic aircraft. The crash-resistant fuel system was added along with the modifications. The left and right main cells were removed with the pods to make space for installation of the howitzers and necessary support structure. Twenty-four troop seats were removed, leaving nine for the required number of gunners. A 60-gallon ferry fuel tank was installed in the center of the fuselage just forward of the escape hatch, allowing movement of personnel around the fuel tank and also leaving the rescue hatch accessible for unloading supplies. The howitzer support structure, hydraulic hoist support structure, muzzle blast doubler, and frame beef-up weights were calculated from layouts. Actual weights were used for weapons, ammo, and purchased parts.

Balance calculations were prepared to show the extreme horizontal and lateral CG travels. Tables V and VI show the calculations for the forward and aft loadings, and Figure 36 shows the resulting horizontal CG envelope compared to CG limits. The envelope is well within these horizontal limits. Tables VII and VIII show the lateral loading calculations which are summarized in the Figure 37 plot of lateral CG versus horizontal CG. This plot shows that the lateral CG remains within the lateral limits, providing the ammunition is stowed on the left-hand side first and consumed last if the left-hand howitzer is not on the aircraft. When both howitzers are on the aircraft, the lateral CG is within limit regardless of the sequence of ammunition loading or usage.

72

TABLE IV. WEIGHT AND BALANCE OF AIRCRAFT LESS WEAPONS, FUEL, AMMUNITION, AND USEFUL LOAD

Item	Weight (lb)	Horizontal		Vertical		Lateral	
		Arm (in.)	Moment (in.-lb)	Arm (in.)	Moment (in.-lb)	Arm (in.)	Moment (in.-lb)
Weight Empty CH-47C (Ref. 114-PJ-7103)	20,743	(345)	7,156,190	(146)	3,030,552	0	2,074
Add Crash Resistant Fuel System	586	327	191,798	80	46,880	0	0
Remove Main Fuel Cells, Pods, Backing Board, etc.	-435	314	-136,590	77	-33,531	0	0
Remove Troop Seats and Belts (24)	-93	300	-27,900	85	-7,871	0	0
Hardpoint Provisions -	(256)						
Add Forward and Aft Beam Attaching Forgings	25	276	6,900	80	1,988	0	0
Add Frame Reinforcements	60	240	14,400	118	7,080	0	0
Add Muzzle Blast Doublers	110	107	11,770	100	11,000	0	0
Add Rotor Brake	51	112	5,712	155	7,905	0	0
Add Brackets, etc.	10	362	3,620	148	1,478	-115	-1,152
Weapon Kit Items - Less Weapons	(3,739)						
Add Forward Hoist, Support Beams and Controls	96	164	15,744	122	11,712	64	6,134
Add Gun Platform	155	320	49,600	57	8,835	-115	-17,856
Add Fwd Lateral Gun Support	586	221	129,228	51	29,886	37	21,506
Add Aft Lateral Gun Support	1,328	314	416,992	51	67,728	45	59,096
Add Longitudinal Beam	48	320	15,360	51	2,448	0	0
Add Tie-Down Dogs & Clamps	25	320	8,000	60	1,500	-115	-2,880
Add Elec.Mtr. & Controls (2)	60	320	19,200	50	3,000	51	3,060
Add Gun Fire Control	50	97	4,850	111	5,560	24	1,200
Add Ammo Loader	200	371	74,200	100	20,000	70	14,000
Add Ammo Loader	200	371	74,200	100	20,000	-70	-14,000
Add Ammo Racks	140	372	52,080	90	12,600	38	5,320
Add Ammo Racks	140	372	52,080	90	12,600	-38	-5,320
Add Ferry Fuel Tank	600	290	174,000	87	52,200	0	0
Add Miscellaneous	15	362	5,430	148	2,217	-115	-1,728
Total Weight Empty	24,796	(337)	8,347,680	(134)	3,327,479	(3)	75,588

73

ITEM	WEIGHT LBS.	HORIZONTAL		VERTICAL		LATERAL	
		ARM	MOMENT	ARM	MOMENT	ARM	MOMENT
Weight Empty	24796.0	(336.7)	8347680	(134.2)	3327479	(3.0)	75588
Pilot & Co-Pilot	400.0	74.5	29800	98.0	39200	0	0
Flight Engineer	200.0	104.9	20980	108.0	21600	0	0
Trapped Fuel	20.0	385.0	7700	100.0	2000	0	0
Unusable Fuel	16.0	314.8	5037	59.0	944	0	0
Unusable Oil	25.0	480.7	12081	164.5	4113	0	0
Usable Oil	28.0	480.7	13460	164.5	4606	0	0
Gunners (3)	600.0	431.0	258600	93.5	56100	-38.0	- 22800
Gunners ((3)	600.0	431.0	258600	93.5	56100	38.0	22800
Gunners (2)	400.0	241.0	96400	93.5	37400	-38.0	- 15200
Gunner (1)	200.0	251.0	50200	93.5	18700	38.0	7600
Howitzer	3751.0	265.0	994015	84.0	315084	102.0	382602
Howitzer(Less Tra-versing Beam & Wheels)	3200.0	271.0	867200	84.0	268800	-102.0	-326400
Fuel(10% Ferry 3900 lbs)	390.0	290.0	113100	100.0	39000	0	0
Minimum Flying Weight	34626.0	(319.8)	11074790	(121.0)	4191126	(3.6)	124190
Loading-Fwd To Aft							
Fuel(Full Ferry 3900-390)	3510.0	290.0	1017900	100.0	351000	0	0
	38136.0	(317.1)	12092690	(119.1)	4542126	(3.3)	124190
Fuel-Aux Tanks	3104.0	314.0	974656	76.1	236214	0	0
	41240.0	(316.9)	13067346	(115.9)	4778340	(3.0)	124190
Ammo 30 Rds	1110.0	371.0	411810	90.0	99900	-38.0	-42180
Ammo 30 Rds	1110.0	371.0	411810	90.0	99900	38.0	42180
	43460.0	(319.6)	13890966	(114.5)	4978140	(2.9)	124190
Ammo 2 Cans	1600.0	471.0	753600	90.0	14400	0	0
Total Gross Weight	45060.0	(325.0)	14644566	(113.7)	5122140	(2.8)	124190

TABLE VI. WEIGHT AND BALANCE FOR AFT LOADINGS

| ITEM	WEIGHT LBS.	HORIZONTAL		VERTICAL		LATERAL	
		ARM	MOMENT	ARM	MOMENT	ARM	MOMENT
Minimum Flying Wt.	34626.0	(319.8)	11074790	(121.0)	4191126	(3.6)	124190
Loading-Aft To Fwd							
Ammo 2 Cans	1600.0	471.0	753600	90.0	144000	0	0
	36226.0	(326.5)	11828390	(119.7)	4335126	(3.4)	124190
Ammo 30 Rds	1110.0	371.0	411810	90.0	99900	-38.0	-42180
Ammo 30 Rds	1110.0	371.0	411810	90.0	99900	38.0	42180
	38446.0	(329.1)	12652010	(118.0)	4534926	(3.2)	124190
Fuel-Aux Tanks	3104.0	314.0	974656	76.1	236214	0	0
	41550.0	(328.0)	13626666	(114.8)	4771140	(3.0)	124190
Fuel(Full Ferry 3900-390)	3510.0	290.0	1017900	100.0	351000	0	0
Total Gross Weight	45060.0	(325.0)	14644566	(113.7)	5122140	(2.8)	124190

Figure 36. Weight and Longitudinal Balance Are Within Limits for the Design Weapon, Fuel and Ammunition Loading

TABLE VII. BALANCE CALCULATIONS FOR LATERAL LOADINGS

Item	Weight (lb)	Horizontal Arm (in.)	Horizontal Moment (in.-lb)	Vertical Arm (in.)	Vertical Moment (in.-lb)	Lateral Arm (in.)	Lateral Moment (in.-lb)
Weight Empty	24,796	(337)	8,347,680	(134)	3,327,479	(3)	75,588
Useful Load							
Trapped Fuel	20	385	7,700	100	2,000	0	0
Unusable Fuel	16	315	5,037	59	944	0	0
Unusable Oil	25	481	12,018	165	4,112	0	0
Usable Oil	28	481	13,460	165	4,606	0	0
Pilot and Copilot	400	75	29,800	98	39,200	0	0
Flight Engineer	200	105	20,980	108	21,600	0	0
Total Basic Weight	25,485	(331)	8,436,675	(133)	3,399,941	(3)	75,588
Right-Hand Loading							
Howitzer	3,200	271	867,200	84	268,800	-102	-326,400
	28,685	(324)	9,303,785	(128)	3,668,741	(-9)	-250,812
Gunners (5)	1,000	355	355,000	94	93,500	-38	-38,000
	29,685	(325)	9,658,875	(127)	3,762,241	(-10)	-288,812
Gunners (4)	800	386	308,800	94	74,800	38	30,400
	30,485	329	9,967,675	(124)	3,837,041	(-9)	-319,212
Ammo in Rack	1,110	371	411,810	90	99,900	38	42,180
Ammo in Can	800	471	376,800	90	72,000	38	30,400
Total Right-Hand Loading	32,395	(332)	10,756,285	(124)	4,008,941	(-6)	-185,832

TABLE VII. BALANCE CALCULATIONS FOR LATERAL LOADINGS (CONT'D)

Item	Weight (lb)	Horizontal		Vertical		Lateral	
		Arm (in.)	Moment (in.-lb)	Arm (in.)	Moment (in.-lb)	Arm (in.)	Moment (in.-lb)
Total Basic Weight (includes right-hand howitzer)	28,685	(324)	9,303,785	(128)	3,668,741	(-8)	-250,812
Left-Hand Loading Howitzer	3,751	265	994,015	84	315,084	102	382,602
	32,436	(318)	10,297,980	(123)	3,983,825	(4)	131,790
Gunners (4), L/H	800	386	308,800	94	74,800	38	30,400
	33,236	(319)	10,606,690	(122)	4,058,625	(5)	162,190
Ammo in Rack	1,110	371	411,810	90	99,900	38	42,180
Ammo in Can	800	471	376,800	90	72,000	38	30,400
Most Lateral	35,146	(324)	11,395,300	(120)	4,230,525	(7)	234,770
Gunners (5), R/H	1,000	355	355,000	94	93,500	-38	-38,000
	36,146	(325)	11,750,300	(120)	4,324,025	(5)	196,770
Ammo in Rack	1,110	371	411,810	90	99,900	-38	-42,180
Ammo in Can	800	471	376,800	90	72,000	-38	-30,400
	38,056	(329)	12,538,910	(118)	4,495,925	(3)	124,190
Fuel - Full Ferry	3,900	290	1,131,000	100	390,000	0	0
- Aux. Tanks	3,104	314	974,656	76	236,214	0	0
Total Loading	45,060	(325)	14,644,566	(114)	5,122,139	(3)	124,190

TABLE VIII. SUMMARY, LATERAL TRIM CHANGES WITH WEAPON OFFLOADING

Configuration	Gross Weight (lb)	Lateral Trim (Hover)				
		CG Offset (in.)	Fuselage List Angle (deg)	Lateral Stick Motion (Available 4.2 in.)		
				Inches Used	Percent Available Used	
Aerial Artillery Aircraft With 96 Rounds of Ammunition	34,236 Zero Fuel & Ammo GW	3.6 Left	.90 Left	.46 Right	11.0 Right	
	41,240 Max. Fuel Gross Wt.	3.0 Left	.15 Left	.39 Right	9.2 Right	
	45,060 Max. GW	2.8 Left	.70 Left	.36 Right	8.6 Right	
With Detachable Howitzer Offloaded, 36 Rounds of Ammunition	30,485 Zero Fuel Gross Wt.	-8.5 Right	2.12 Right	1.09 Left	26.0 Left	
	37,489 Max. Fuel Gross Wt.	-6.9 Right	1.73 Right	.89 Left	21.6 Left	
	39,089 Max. GW	-6.6 Right	1.66 Right	.86 Left	20.7 Left	

1		WEIGHT EMPTY	24,796 LBS
1 – 2		BASIC WEIGHT – INCLUDES TRAPPED AND USABLE LIQUIDS, PILOT, CO-PILOT, AND FLIGHT ENGINEER	25,496 LBS
2 – 3		HOWITZER – RIGHT SIDE	28,696 LBS
3 – 4		GUNNERS (5) – RIGHT SIDE	29,686 LBS
4 – 5		GUNNERS (4) – LEFT SIDE	30,496 LBS
5 – 6		AMMO – LEFT SIDE (48 RDS)	32,396 LBS
3 – 7		HOWITZER – LEFT SIDE	32,436 LBS
7 – 8		GUNNERS (4) – LEFT SIDE	33,236 LBS
8 – 9		AMMO – LEFT SIDE (48 RDS)	35,146 LBS
9 – 10		GUNNERS (5) – RIGHT SIDE	36,146 LBS
10 – 11		AMMO – RIGHT SIDE (48 RDS)	38,056 LBS
11 – 12		FUEL – FERRY & AUX (7,004 LBS)	45,060 LBS

NOTE: LEFT SIDE AMMO MUST BE STOWED FIRST AND USED LAST WHEN LEFT SIDE HOWITZER IS NOT ON AIRCRAFT.

Figure 37. Lateral-Longitudinal Center of Gravity Diagram CH-47C Aerial Artillery

80

LATERAL CONTROL, HOVER OFFLOADING OF LEFT WEAPON

When the left weapon is offloaded, an unusually large lateral
CG offset results. Lateral trim calculations have been made
to ensure that this lateral CG offset does not require exces-
sive amounts of lateral control. The lateral CG extremes are
shown in Table VII and Figure 37. The results, summarized in
Table VIII, indicate that the static trim attitude and control
position changes are within the control and operational limits
of the CH-47C. The most critical configuration requires 26.0
percent of available lateral control, thus providing a sub-
stantial margin on the 10-percent control remaining limit
which is an absolute limit for very restricted flight. Ade-
quate control is available for 35-knot sideward flight. The
accompanying fuselage list angle of 2.12 degrees is well
within the 3-degree pilot comfort limit.

A summary of the lateral trim attitude limits is shown in
Figure 38. The design configuration satisfies all limitations.
It is satisfactory that the pilot can fly with sideslip to have
level roll attitude at speeds above 130 knots.

Figure 38. Roll Attitude Limits Versus Airspeed

FLIGHT PERFORMANCE

CONFIGURATION

The primary features of the CH-47C, configured for the artillery role, which affect performance are shown in Table IX. Also noted is the comparable features of a standard CH-47C as described in the Reference 10 detail specification.

TABLE IX. COMPARISON OF AERIAL ARTILLERY CONFIGURATION TO STANDARD CONFIGURATION		
Item	Standard CH-47C	Aerial Artillery Configuration
Rotor System		
Diameter, ft	30	30
Chord, in.	25.25	25.25
Power Plant		
Ratings SL/Std, SHP		
Maximum (10 min)	3,750	3,750
Military (30 min)	3,400	3,400
Normal Power	3,000	3,000
Drive System Rating, SHP	6,000 at 243 rpm	6,000 at 243 rpm
Weights, lb		
Maximum	46,000	46,000
Design	33,000	33,000
Weight Empty	20,743	24,796
Fuel Capacity, gal	1,129	1,078
Hover Download Increase[1] (DL/T), percent	--	5.25
Equivalent Drag Increase[1], ft^2	--	76.2
(1) Relative to CH-47C		

HOVER PERFORMANCE

Figure 39 illustrates the hover capability out-of-ground effect (OGE) of the aerial artillery version of the CH-47C configuration. Also shown on this plot is the hover performance of the CH-47C. Performance is shown at standard temperature and 95°F. As noted, at sea level standard, the aerial artillery aircraft possesses the capability to hover OGE at a gross weight of 43,260 pounds. At 2,000 feet/95°F, this capability lapses to 41,750 pounds or approximately 2,600 pounds less than the standard CH-47C. This reduction in capability is attributable to the increased download of the aerial artillery aircraft which is 5.25 percent (DL/T) higher than the standard CH-47C.

TAKEOFF PERFORMANCE

For the aerial artillery helicopters with mounted weapons and internal cargo, it is not necessary to make a hovering out-of-ground-effect (OGE) takeoff as is required for external payload (sling load) missions. Therefore, in this design, it was assumed that takeoff would be at the maximum alternate weight less warmup fuel (45,060 pounds since two minutes at NRP requires 940 pounds of fuel), with the kind of takeoff depending on the atmospheric conditions. As noted previously, the CH-47C can not hover OGE at sea level standard conditions with the weapons installed due to the increased download. Takeoff would therefore be in ground effect at sea level standard; a running takeoff with lift-off at about 60 knots would be required at 2,000 feet, 95°F. It would be possible to reduce the fuel load by 1,800 or 2,300 pounds to have a hover OGE capability at sea level standard and 2,000 feet, 95°F respectively. These reductions in fuel would reduce the range by about 35 to 40 miles radius.

Figures 40 through 45 illustrate the mission capability of the aerial artillery CH-47C in the following three roles:

- Detachable Howitzer

- Air-to-Ground Firing Mission

- Ground-to-Ground Attached Firing Mission

Mission performance is shown at two ambient conditions: sea level standard day and 2,000 feet/95°F. The ability of the CH-47C in the aerial artillery configuration to accomplish these missions is summarized in Table X.

As shown at a weight commensurate with its ability to hover OGE at sea level standard (43,260 pounds), the aerial artillery version of the CH-47C possesses the ability to transport

84

(OUT OF GROUND EFFECT)

MAXIMUM POWER   TWO T55 - L - 11 ENGINES

Figure 39.   CH-47C Helicopter Hover Ceiling Versus Gross
   Gross Weight

WARM-UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
HOVER (OGE) 15 MIN AT STATION
UNLOAD REMOVABLE GUN (3,751 LB), TWO CANS OF AMMO (1,600 LB),
  AND FIVE GUNNERS (1,000 LB) – TOTAL OF 6,351 LB
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
24,796 LB EMPTY WEIGHT
   689 LB FIXED USEFUL LOAD
7,004 LB FUEL TANK CAPACITY

* 3,751 LB – REMOVABLE HOWITZER
  1,600 LB – (2) CANS OF AMMO
  1,000 LB – (5) GUNNERS
  3,200 LB – PERMANENT HOWITZER
  2,220 LB – 60 ROUNDS OF AMMO
    800 LB – (4) GUNNERS
 12,571 LB – DESIGN PAYLOAD

TAKE-OFF GROSS WEIGHT
46,000 LB (MAXIMUM)
45,060 LB (DES PAYLOAD/FULL FUEL)
(43,260 LB) (VTO AT SL/STD)
VERTICAL LANDING CAPABILITY
(43,260 LB) AT MISSION MID-POINT

FUEL TANK CAPACITY
(1,078 GALLONS)

DESIGN PAYLOAD*

RADIUS – NAUT MILES

OUTBOUND PAYLOAD – 1,000 LB

Figure 40. Capability of Aerial Artillery CH-47C on
Detachable Howitzer Mission at Sea Level
Standard Conditions

86

WARM-UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
HOVER (OGE) 15 MIN AT STATION
FIRE 60 ROUNDS OF AMMO (2,220 LB) AND SAVE
AMMO CASINGS (157 LB) – NET 2,063 LB
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
24,796 LB EMPTY WEIGHT
   689 LB FIXED USEFUL LOAD
7,004 LB FUEL TANK CAPACITY

* 3,751 LB – REMOVABLE HOWITZER
  1,600 LB – (2) CANS OF AMMO
  1,000 LB – (5) GUNNERS
  3,200 LB – PERMANENT HOWITZER
  2,220 LB – 60 ROUNDS OF AMMO
    800 LB – (4) GUNNERS
 12,571 LB – DESIGN PAYLOAD

Figure 41. Capability of Aerial Artillery CH-47C on
Air-to-Ground Firing Mission at Sea Level
Standard Conditions

87

WARM UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
LAND AT STATION AND STOP ENGINES
FIRE (2) CANS OF AMMO (36 ROUNDS) FROM PERMANENT
MOUNTED GUN – 1,600 LB TOTAL
WARM UP 2 MIN AT NRP
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
24,796 LB EMPTY WEIGHT
689 LB FIXED USEFUL LOAD
7,004 LB FUEL TANK CAPACITY

TAKE-OFF GROSS WEIGHT
46,000 LB (MAXIMUM)
45,060 LB (DES PAYLOAD/FULL FUEL)
(43,260 LB) (VTO AT SL/STD)
VERTICAL LANDING CAPABILITY
(43,260 LB) AT MISSION MID-POINT
FUEL TANK CAPACITY
(1,078 GALLONS)
DESIGN PAYLOAD*

OUTBOUND PAYLOAD – 1,000 LB
RADIUS – NAUT MILES

- 3,751 LB – REMOVABLE HOWITZER
  1,600 LB – (2) CANS OF AMMO
  1,000 LB – (5) GUNNERS
  3,200 LB – PERMANENT HOWITZER
  2,220 LB – 60 ROUNDS OF AMMO
  800 LB – (4) GUNNERS
  12,571 LB – DESIGN PAYLOAD

Figure 42. Capability of Aerial Artillery CH-47C on
Ground-to-Ground Attached-Firing Mission
at Sea Level Standard Conditions

WARM-UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
HOVER (OGE) 15 MIN AT STATION
UNLOAD REMOVABLE GUN (3,751 LB), TWO CANS OF AMMO (1,600 LB),
    AND FIVE GUNNERS (1,000 LB) — TOTAL OF 6,351 LB
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
        24,796 LB EMPTY WEIGHT
            689 LB FIXED USEFUL LOAD
   7,004 LB FUEL TANK CAPACITY

TAKE-OFF GROSS WEIGHT
46,000 LB (MAXIMUM)
45,060 LB (DES PAYLOAD/FULL FUEL)
41,750 LB (VTO AT 2,000 FT, 95°F)

VERTICAL LANDING CAPABILITY
(41,750 LB) AT MISSION MID-POINT

* 3,751 LB — REMOVABLE HOWITZER
  1,600 LB — (2) CANS OF AMMO
  1,000 LB — (5) GUNNERS
  3,200 LB — PERMANENT HOWITZER
  2,200 LB — 60 ROUNDS OF AMMO
    800 LB — (4) GUNNERS
 12,571 LB — DESIGN PAYLOAD

DESIGN PAYLOAD*

FUEL TANK CAPACITY (1,078 GALLONS)

OUTBOUND PAYLOAD – 1,000 LB

RADIUS – NAUT MILES

Figure 43.   Capability of Aerial Artillery CH-47C on
             Detachable Howitzer Mission at 2,000 Feet,
             95°F

89

WARM-UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
HOVER (OGE) 15 MIN AT STATION
FIRE 60 ROUNDS OF AMMO (2,220 LB) AND SAVE AMMO
CASINGS (157 LB) — NET 2,063 LB
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
    24,796 LB EMPTY WEIGHT
   689 LB FIXED USEFUL LOAD
    7,004 LB FUEL TANK CAPACITY

TAKE-OFF GROSS WEIGHT
46,000 LB (MAXIMUM)
45,060 LB (DES PAYLOAD/FULL FUEL)
(41,750 LB) (VTO AT 2,000 FT, 95°F)

VERTICAL LANDING CAPABILITY
(41,750 LB) AT MISSION MID-POINT

* 3,751 LB — REMOVABLE HOWITZER
1,600 LB — (2) CANS OF AMMO
1,000 LB — (5) GUNNERS
3,200 LB — PERMANENT HOWITZER
2,200 LB — 60 ROUNDS OF AMMO
   800 LB — (4) GUNNERS
12,571 LB — DESIGN PAYLOAD

(Chart: OUTBOUND PAYLOAD — 1,000 LB (y-axis, 0 to 24) vs RADIUS — NAUT MILES (x-axis, 0 to 140). Labels: DESIGN PAYLOAD*, FUEL TANK CAPACITY (1,078 GALLONS))

Figure 44. Capability of Aerial Artillery CH-47C on
Air-to-Ground Firing Mission at 2,000 Feet,
95°F

WARM UP 2 MIN AT NRP
CRUISE OUT AT 99% BRS
LAND AT STATION AND STOP ENGINES
FIRE (2) CANS OF AMMO (36 ROUNDS)
FROM PERMANENT MOUNTED GUN — 1,600 LB TOTAL
WARM UP 2 MIN AT NRP
CRUISE BACK AT 99% BRS
LAND WITH 10% FUEL RESERVE
   24,796 LB EMPTY WEIGHT
     689 LB FIXED USEFUL LOAD
   7,004 LB FUEL TANK CAPACITY

TAKE-OFF GROSS WEIGHT
46,000 LB (MAXIMUM)
45,060 LB (DES PAYLOAD/FULL FUEL)
41,750 LB (VTO AT 2,000 FT, 95°F)

VERTICAL LANDING CAPABILITY
(41,750 LB) AT MISSION MID-POINT

* 3,751 LB — REMOVABLE HOWITZER
   1,600 LB — (2) CANS OF AMMO
   1,000 LB — (5) GUNNERS
   3,200 LB — PERMANENT HOWITZER
   2,200 LB — 60 ROUNDS OF AMMO
    800 LB — (4) GUNNERS
12,571 LB — DESIGN PAYLOAD

Figure 45.   Capability of Aerial Artillery CH-47C on
Ground-to-Ground Attached-Firing Mission
at 2,000 Feet, 95°F

91

TABLE X. MISSION PERFORMANCE SUMMARY

Mission	Takeoff Weight	Payload (100 NM Radius)	
		SL/Std	2,000 Ft, 95°F
Detachable Howitzer			
● Warm up 2 min at NRP	46,000 lb (1)	13,511 lb (5)	13,600 lb
● Cruise out at 99% BRS	45,060 lb (2)	12,571 lb	12,750 lb
● HOGE for 15 min on sta	43,260 lb (3)	10,850 lb	--
● Unload 6,351 lb	41,750 lb (4)	--	9,950 lb
● Cruise back at 99% BRS			
● Land w/10% fuel reserve			
Air-to-Ground Firing			
● Warm up 2 min at NRP	46,000 lb (1)	13,511 lb (6)	13,511 lb (9)
● Cruise out at 99% BRS	45,060 lb (2)	12,571 lb (7)	12,571 lb
● HOGE for 15 min on sta	43,260 lb (3)	10,971 lb (8)	--
● Fire 60 rds (2,063 lb)	41,750 lb (4)	--	9,700 lb
● Cruise back at 99% BRS			
● Land w/10% fuel reserve			
Ground-to-Ground Firing			
● Warm up 2 min at NRP	46,000 lb (1)	13,900 lb	14,300 lb
● Cruise out at 99% BRS	45,060 lb (2)	13,000 lb	13,400 lb
● Land at sta/stop engines	43,260 lb (3)	11,350 lb	--
● Fire 36 rds (1,600 lb)	41,750 lb (4)	--	10,450 lb
● Warm up 2 min at NRP			
● Cruise back at 99% BRS			
● Land w/10% fuel reserve			

Notes:
(1) Maximum Alternate Weight
(2) Includes Design Payload (12,571 lb)
(3) HOGE at sea level standard
(4) HOGE at 2,000 ft, 95°F
(5) 99 Nautical Miles
(6) 94 Nautical Miles
(7) 95 Nautical Miles
(8) 98 Nautical Miles
(9) 97 Nautical Miles

10,850 pounds of payload 100 nautical miles and return to base
when performing the detachable howitzer mission. Takeoff for
this mission is with the 12,571-pound design payload, and 1,721
pounds of fuel are burned during the 100-nautical-mile flight.
During this mission, the aircraft is required to hover 15
minutes on station and return to base with 10 percent fuel
reserve. At the mission midpoint, the removable howitzer
(3,751 pounds), two cans of ammunition (1,600 pounds), and
five gunners (1,000 pounds) are offloaded from the aircraft.
At an ambient condition of 2,000 feet, 95°F, for the same mis-
sion, the payload capability decreases to 9,950 pounds.

During the air-to-ground firing mission, the aircraft can take
off vertically and deliver a payload of 9,750 pounds at 2,000
feet, 95°F over a radius of 100 nautical miles. This mission
is based on firing 2,063 pounds of ammo at the midpoint.

The ground-to-ground firing mission calls for the CH-47C
aerial artillery aircraft to fire two cans of ammo (36 rounds)
from the permanent-mount howitzer after landing at the mission
midpoint. At 2,000 feet, 95°F, the CH-47C can perform this
mission over a radius of 100 nautical miles, based upon a
hover OGE takeoff criteria, with a payload of 10,450 pounds.

PERFORMANCE BASIS

Hover Power Required/Fuel Consumption

CH-47C hover power required is based upon testing of the
CH-47C conducted by Vertol and the U. S. Army and documented
in Reference 11, Flight Test Report. This data was adjusted
for increased download to obtain the hover performance of the
aerial artillery aircraft. The hover download contributed by
the permanent howitzer and the removable howitzer is indicated
in the following table.

HOVER DOWNLOAD (PERCENT TOTAL THRUST)	
Permanent Howitzer	2.90
Removable Howitzer	2.35
Total Increase	5.25

The larger percent download of the permanent-mounted howitzer
results due to the drag of the howitzer support platform which
is considered a part of the download of this howitzer.

93

Substantiation of the hover download estimate for the aerial
artillery configuration, based on model test data, is presented
in Appendix VIII.

Hover power required (OGE) and fuel flow over a range of weights
for the CH-47C and its aerial artillery derivative are pre-
sented in Figures 46 and 47. Data is presented at an ambient
condition of sea level standard and 2,000 feet, 95°F, respec-
tively.

Level Flight Power Required/Specific Range

Level flight performance for the CH-47C is presented upon test
data acquired by Vertol and the U. S. Army and documented in
the Reference 11 CH-47C Test Report. This data was modified to
reflect the increased drag of the aerial artillery configura-
tion. In cruise, the equivalent drag area of the aerial
artillery configuration is approximately 2.5 times that of the
standard CH-47C configuration. The removable howitzer contri-
butes about two-thirds of the total increase in drag area due
primarily to the dual (forward and aft) main howitzer support
and dual-winch support beams. The removable howitzer is a
complete unit, incorporating undercarriage wheels and traver-
sing beam, which further increases the drag. The total drag
increase due to the howitzer installation is shown below.

EQUIVALENT DRAG AREA (fe) (ft^2)	
Permanent Howitzer	24.3
Removable Howitzer	51.9
Total Increase	76.2

Substantiation of the estimated equivalent drag area for the
aerial artillery configuration is presented in Appendix VIII.

Level flight power required curves for both the standard
CH-47C and the aerial artillery version are presented in
Figures 48 through 51. Indicated on the curves are limitations
to speed due to available power, transmission torque limits,
and the structural flight envelope. Specific range (nautical
miles per pound of fuel burned) as a function of airspeed is
presented in Figures 52 and 53. Specific range and associated
cruise speeds over a range of gross weights for optimum range
and maximum continuous cruise speed flight conditions are pre-
sented in Figures 54 and 55. Data is shown at sea level

94

standard and 2,000 feet, 95°F for both the standard aircraft and the aerial artillery version.

Installed Power Available/Fuel Flow

The data presented in this document reflects the performance characteristics of the T55-L-11 engine contained in the Reference 12 Lycoming Model Specification. All mission calculations assume a 5-percent increase in engine manufacturers' stated fuel consumptions.

Figure 46. CH-47C Helicopter Hover Power and
Fuel Flow Versus Gross Weight

Figure 47.   CH-47C Helicopter Hover Power and
Fuel Flow Versus Gross Weight

97

SEA · LEVEL / STD. ATMOS.
TWO T55 · L · 11 ENGINES

Figure 48.   CH-47C Helicopter Standard Configuration
Level Flight Power Required

98

Figure 49. CH-47C Helicopter Aerial Artillery Configuration
Level Flight Power Required

Figure 50. CH-47C Helicopter Standard Configuration Level Flight Power Required

100

Figure 51. CH-47C Helicopter Aerial Artillery Configuration
Level Flight Power Required

Figure 52. CH-47C Helicopter Specific Range Versus Airspeed

102

Figure 53. CH-47C Helicopter Specific Range Versus Airspeed

103

SEA LEVEL/STD ATMOS. TWO T55-L-11 ENGINES
NOTE: 235 RPM (BELOW 40000 LB) & 245 RPM (ABOVE 40000 LB)

TRUE AIRSPEED - KNOTS

(XMSN. LIMIT)

160

STANDARD
CONFIGURATION

140

(XMSN. LIMIT)

AERIAL
ARTILLERY
CONFIG

120

100   —— STRUCTURAL ENVELOPE
   —·— NORMAL POWER
   ——— 99% BEST RANGE

80
20 24 28 32 36 40 44 48

ALTERNATE DESIGN G.W.

SPECIFIC RANGE - N.MI./LB.

.07

.06   STANDARD
   CONFIGURATION

.05

.04

ARTILLERY
AERIAL
CONFIG

.03

.02
20 24 28 32 36 40 44 48

GROSS WEIGHT - 1000 LB

ALTERNATE DESIGN G.W.

Figure 54. CH-47C Helicopter Specific Range and Cruise
     Speed Versus Gross Weight

2,000 FT/ 95°F   TWO T55-L-11 ENGINES

NOTE: 235 RPM (BELOW 40,000 LB) AND 245 RPM (ABOVE 40,000 LB)

Figure 55.   CH-47C Helicopter Specific Range and
             Cruise Speed Versus Gross Weight

105

FIRE CONTROL

Conventional artillery fire control equipment is provided in the aerial artillery weapon kit for ground-to-ground firing, and a simple depressible reticle sight is provided for air-to-ground firing. Considerably more sophisticated inertial platform-based target locators, stabilized-magnified sighting systems, etc. could readily be added to increase accuracy, reduce response time, and interface with automated battlefield equipment; but these items have not been considered. In this study, only the most simple, lowest-cost system that could give adequate performance was considered.

GROUND-TO-GROUND FIRING MODE

Firing of the howitzers in either of the two ground-to-ground modes is no different from firing any other artillery piece. Obviously, the detached howitzer introduces no firing complications. The attached howitzer (right side) is mounted on a larger firing base, the helicopter; but again, no new firing problems are introduced. It is necessary that an adequate fire direction center functional capability and authority be part of the aerial artillery firing mission. Provisions are made for a nine-man gun crew to include the men and equipment required for fire direction.

AIR-TO-GROUND FIRING MODE

Air-to-ground firing missions for the aerial artillery helicopter are likely to be either against hostile, well-emplaced enemy positions or to rapidly deny use of areas to the enemy. In either case, the maximum range capability of the 105mm howitzer in direct fire would be utilized to keep the helicopter away from the hot area. A nominal range of 4,000 meters with ability to accommodate ranges of 3,000 to 5,000 meters is provided. The system shown in the design is believed to be able to provide at least 15-mil accuracy and should be adequate to walk the rounds onto the target with the rapid automatic firing capability.

The fire control system provided in the design consists of the following:

- Fixed depressible reticle sight

- Laser rangefinder with mechanical connection to sight

- Artillery binoculars for target detection and identification by crew.

This system represents the least cost approach with the limitations being the ability to acquire targets and aim the weapons.

The sight provided consists of a combining glass mounted in
front of the copilot/gunner which has a light and optics for
projecting a crosshair on this combining glass. The copilot
looks through the combining glass at the target and sees the
reticle superimposed over the target. Since the reticle is
focused at infinity, it eliminates the eye-focusing problem
which normally exists when observing both close and distant
objects simultaneously. Also, movement of the pilot's head
does not cause a change in the sight line angle to the target.
It is assumed that the target has been located and identified
by some means other than the fire control sight. This allows
the use of the simple sight with no magnification for the solu-
tion to the fire control problem. With appropriate contrast
and illumination, the unaided human eye can detect objects
which subtend one minute of arc. At 4,000 meters,

$$R\theta = \text{object size}$$

$$(4000) [\frac{1}{(5.73)(60)}] \approx 1.163 \text{ meters}$$

Thus, at 4,000 meters, a target can be seen well enough to
align the optical sight crosshairs but not well enough to
identify the target. The artillery section chief aboard can
use his binoculars to locate and identify the targets.

For range determination, a simple, lightweight and relatively
inexpensive laser rangefinder is provided. These devices exist
as off-the-shelf hardware in production quantities. Since this
device has a very narrow beam, it must be changed in elevation
every time the sight angle to the target is changed. In order
to assure that the elevation boresight between the optical
sight and the laser rangefinder is maintained, the laser is
coupled mechanically in elevation to the optical sight.

Each time the weapon kit is installed on the hardpoints, the
system will have to be boresighted for air-to-ground firing.
Since the forward retractable beam can be used to adjust the
azimuth of the removable howitzer, both weapons can be adjusted
in elevation and azimuth for boresighting. Boresighting there-
fore requires that a crewman take a target to the nominal range
in front of the helicopter; and by use of hand signals, he
positions the target at the center of the crosshairs on the
sight. Range to the target can be checked with the laser range-
finder which must be adjusted to be aimed at the target. Next,
the howitzers would be aimed at the target using the elbow
telescope sights and adjusting the elevation with the standard
elevation handwheels. Azimuth of the right-side weapon will be
adjusted using the azimuth handwheel, and the left-side weapon
will be adjusted by positioning the forward retractable beam.
A boresight target and a retractable boresight tube are pro-
vided so that the left-side howitzer can be reboresighted

inflight after the howitzer is remounted to the helicopter by the hoists. The reboresight target will be a scale which is read during boresighting so that the position of the howitzer can be repeated when the howitzer is remounted. The retractable boresight tube is provided so that the elbow telescope sight on the howitzer can be used from inside the cabin of the helicopter.

Hitting targets in air-to-ground firing requires that the copilot/gunner, the pilot, and the artillery section chief preplan the mission to determine how the target is to be attacked. This is necessary so that the elevation of the two howitzers can be set using the handwheel controls. The problem, illustrated in Figure 56, results from the change in fuselage attitude with airspeed and the large difference in height between the helicopter and the target that can occur. As shown in Figure 57, a correction in gun elevation of about 100 mils must be made if the firing is done at 120 knots rather than at hover. This change in attitude must be added to the elevations from the firing tables (Reference 13) which are a function of delta height and range. It is anticipated that most firing would be accomplished from hover with the helicopter in the nap of the earth so that the delta height is no more than 50 meters. As shown by the Figure 58 data, the howitzers would be set at about 100 mils' elevation for firing in this condition.

Figure 56. Geometry Involved in the Air-to-Ground Firing

109

Figure 57. Helicopter Attitude Changes with Flight Speed in Level Flight

110

Figure 58.   Elevation and Delta Height Relationship
for Zone 5, M1 Rounds

111

CONCLUSIONS

1. Aerial artillery, using the XM204 howitzer and the CH-47C helicopter, is feasible. This concept will provide fire-power and a flexible capability that should warrant further development by the Army.

2. Impulse generators do not appear to be necessary for the CH-47C aerial artillery. Elastic responses of the heli-copter to inflight firing without impulse generators show peak accelerations of about 0.17 g. Flight motion simula-tion of the response of the helicopter to the recoil load which would result from inflight firing without the impulse generator shows that a 3/4-inch, 0.5-second directional control input will negate the response. This control input could be automatic or by the pilot.

3. Dynamic tuning of the mounting structures for the howitzers has an important influence on the vibration of the heli-copter and the weapons. Tuning to accept some motion of the howitzers appears to be the approach to give the best compromise between helicopter vibration, howitzer attachment vibratory stresses, and howitzer aiming accuracy.

4. Rotor blade stresses due to inflight firing of zone 5 from the forward-directed weapons are small enough to have a negligible influence on the service life of the rotor system.

5. Due to the continuous operation at high gross weight inher-ent in the aerial artillery missions, some reduction in the service life of the forward rotor components is required with the present design. This penalty would be alleviated if the CG were shifted back to the aft limit.

6. To provide for the malfunction of an erroneous round selection, muzzle blast doublers for the fuselage and par-ticularly for the transparent areas should be designed not to fail when the largest zone round aboard is fired.

7. Detail design of the aerial artillery installation may show that reinforcement of the fuselage frames under the muzzle blast doubler may be required.

8. Increased aerodynamic hover download and drag due to the weapon installation reduce the hover lift capability about 2,200 pounds and reduce the range about 20 percent compared to a standard CH-47C with internal cargo.

9. It was not required in this study that the normal combat equipment be included. The armor, tool kit, emergency

equipment, and suppressive fire weapons provided in the combat equipment are likely to be needed and should be included in subsequent efforts.

10. A rotor brake is required as part of the weapons kit so that quick response in ground-to-ground attached firing can be provided.

RECOMMENDATIONS

1. The aerial artillery weapon installation and hardpoints
    kits described in this report should be detail-designed,
    fabricated and tested. Production of at least enough of
    these units to acquire operational experience is
    recommended.

2. Direct air-to-ground firing of the aerial artillery appears
    to be a sufficiently important firing mode that it should
    be considered separately. An attractive inflight firing
    feasibility test could be accomplished using the M102 how-
    itzer and trainable gun mount from the AC-130 (Air Force)
    program with a sight and fire control avionics available
    from the MBT-70 program.

3. Helicopter model testing of muzzle blast effects on rotor
    blade loads could prevent expensive surprises in the
    development of large-caliber weapon installations on heli-
    copters and should be performed for all such developments.

4. Development of muzzle blast diffusers and/or other muzzle
    blast alleviation devices for use in helicopters should be
    continued.

REFERENCES

1. Peck, William B; Nutley, William S.; Yntema, Robert T.; Schwam, Stuart A.; Harley, Robert S., STUDY OF THE "BREATHING" EFFORT ON THE H-21 HELICOPTER, Vertol Division, Boeing Airplane Company, Report R-243, Feltman Research and Engineering Laboratories, Picatinny Arsenal, Dover, New Jersey, March 1961

2. Coppock, Max L. and Schertz, Charles J. STUDY OF THE EFFECTS OF FIRING A 75 MM HOWITZER FROM THE H2IA HELICOPTER, U. S. Army Weapons Command Technical Report 65-1889, Rock Island Arsenal, Rock Island, Illinois, August 1965

3. Coppock, Max L., STUDY OF THE EFFECTS OF FIRING A 105 MM HOWITZER FROM THE H21 HELICOPTER, U. S. Army Weapons Command Technical Report 64-3450, Rock Island Arsenal, Rock Island, Illinois, December 1964

4. Smith, William B., AERIAL ARTILLERY WEAPON (EXTERNALLY MOUNTED CONCEPT) (U), U. S. Army Weapons Command, Rock Island Arsenal, Rock Island, Illinois, November 1970. (Confidential)

5. ENGINEERING DESIGN HANDBOOK, GUN SERIES MUZZLE DEVICES, Franklin Institute, Philadelphia, Pennsylvania/Duke University, Durham, North Carolina; AMCP Pamphlet 706-251, U. S. Army Materiel Command, Washington, D. C., May 1968

6. Salsbury, Mark J., POLAR BLAST FIELD OF 105 MM HOWITZERS, MEASURED AND PREDICTED, Artillery Systems Laboratory Technical Report RE TR 71-11, U. S. Army Weapons Command, Rock Island Arsenal, Rock Island, Illinois, January 1971

7. Kinney, Gilbert Ford, EXPLOSIVE SHOCKS IN AIR, New York, Macmillan, 1962

8. Dobbs, N.; Cohen, E.; Weissman, S., BLAST PRESSURE AND IMPULSE LOADS FOR USE IN THE DESIGN AND ANALYSIS OF EXPLOSIVE STORAGE AND MANUFACTURING FACILITIES, Annals of the New York Academy of Sciences, Vol. 152, Art. 1, October 28, 1968, p. 323.

9. Sewell, Robert G. S. and Kinney, Gilbert Ford, RESPONSE OF STRUCTURES TO BLAST: A NEW CRITERION, NWC TP 4422, Naval Weapons Center, China Lake, California, June 1968

10. DETAIL SPECIFICATION FOR THE MODEL CH-47C HELICOPTER, Boeing-Vertol Report 114-PJ-7103, The Boeing Company, Philadelphia, Pennsylvania, May 1970

11. ANALYSIS OF CH-47C PERFORMANCE FLIGHT TEST, Boeing-Vertol Report 114-FT-712, The Boeing Company, Philadelphia, Pennsylvania, January 20, 1969

12. MODEL SPECIFICATION T55-L-11 SHAFT TURBINE ENGINE LYCOMING MODEL LTC4B-11 Specification 124.27A, Lycoming Division, AVCO Corporation, Bridgeport, Connecticut, May 24, 1968

13. FIRING TABLES, 105 MM HOWITZER, M103, FT 105-AS-2, Headquarters, Department of the Army, November 1967

14. PRELIMINARY DRAFT, TECHNICAL MANUAL, HOWITZER, LIGHT, TOWED; 105 MM SOFT RECOIL, XM204, Artillery Systems Laboratory, Research and Engineering Directorate, U. S. Army Weapons Command, Rock Island Arsenal, Rock Island, Illinois, March 1970

15. STRUCTURAL DESIGN CRITERIA FOR THE CH-47B and CH-47C HELICOPTERS, Boeing-Vertol Report 114-SS-603, The Boeing Company, Philadelphia, Pennsylvania

16. INVESTIGATION OF IMPACT OF RVN FLIGHT SURVEY DATA ON FATIGUE CRITICAL COMPONENTS, Boeing-Vertol Report 114-SS-025, The Boeing Company, Philadelphia, Pennsylvania

17. AERONAUTICAL AND STRUCTURAL DESIGN REQUIREMENTS, Naval Air Systems Command Specification AR-56, Department of the Navy, Washington, D. C.

18. FOREWARD LANDING GEAR ANALYSIS FOR THE CH-47C HELICOPTER, Boeing-Vertol Report 114-S-05.1, The Boeing Company, Philadelphia, Pennsylvania

19. CH-47C DYNAMIC SYSTEM FATIGUE ANALYSIS FINAL REPORT, Boeing-Vertol Report 114-SS-723, The Boeing Company, Philadelphia, Pennsylvania

20. STRUCTURAL DESIGN MANUAL, Boeing-Vertol DM 8611, The Boeing Company, Philadelphia, Pennsylvania

21. Roark, Raymond J., FORMULAS FOR STRESS AND STRAIN, New York, McGraw-Hill Book Company, 1965

22. CH-47B and CH-47C METAL ROTARY WING ULTIMATE STRENGTH ANALYSIS (CONFIGURATIONS IA AND II), Boeing-Vertol Report 114-SS-607.2.1, The Boeing Company, Philadelphia, Pennsylvania, March 1967

23. Westine, Peter S., MODELING THE BLAST FIELD AROUND NAVAL GUNS AND CONCEPTUAL DESIGN OF A MODEL GUN BLAST FACILITY, Southwest Research Institute; Final Technical Report 02-2643-01, U. S. Naval Weapons Laboratory, Dahlgren, Virginia, September 1970

24. Westine, Peter S., and Hoese, Fred, BLAST GAUGE FOR MEASURING SHOCKS WITH SHORT WAVE LENGTHS, Southwest Research Institute; Interim Report Contract N00178-69-C-0318, U. S. Naval Weapons Laboratory, Dahlgren, Virginia, May 1970

25. Long, George, 105 MM BLAST TESTS AND ANALYSIS, (U) NWL Report (Unnumbered), U. S. Naval Weapons Laboratory, Dahlgren, Virginia, February 1972, (Confidential)

HELICOPTER AND WEAPON PARAMETERS

Reference 10 is the detail specification for the model CH-47C
helicopter. The following data, extracted from Reference 10
has been used as the basic helicopter parameters for this study.

SCOPE

Helicopter Designation

This specification covers the requirements for the design and
construction of the following transport helicopter:

U. S. Army Designation	CH-47C
The Boeing Company, Vertol Division	Model 114
Number and Places for Crew	Three (3)
Number and Kind of Engines	Two (2) T55-L-11 (Lycoming)

Figure 59 is a three view drawing of the CH-47C showing external
measurements.

Mission

The primary tactical mission of the Model CH-47C helicopter is
to provide air transportation for cargo, troops and weapons
within the combat area. In addition, this helicopter will be
suitable for special support function. This aircraft shall be
suitable for operations during day, night, visual and instru-
ment conditions. The helicopter shall be designed to perform
the following specific missions.

    I.   Mission I - Design Mission

        Hover OGE* (6,000 Ft. 95°F)
        100 Nautical Mile Combat Radius
        Payload 12,000 pounds outbound
                6,000 pounds inbound

        *OGE = Out of Ground Effect

CH-47C THREE-VIEW

(2,7m.) 9' 0"

(3,8m.) 12' 5"

60' (18,3m.)

ROTATION

ROTATION

(3,2m.) 10' – 6"

(30.2m.) 99'

(2,7m.) 38' – 10"

(2,7m.) 8' – 9.9"

(1,1m.) 3' – 8.4"

(5,7m.) 18' – 7.8"

(3,8m.)

(2,1m.) 10' – 11"

7' – 2.6"

(4m.) 13' – 3"

(6,8m.) 22' – 6"

(15,5m.) 51' – 0"

Figure 59.

119

II.   Mission II - Design Gross Weight Mission

       Design Gross Wt. 33,000 Pounds
       100 Nautical Mile Combat Radius
       Payload 7,350 pounds outbound
               3,675 pounds inbound
       Sea Level/Standard Atmosphere

III.   Mission III - Alternate Gross Weight Mission

       Alternate Design Gross Weight - 46,000 Pounds
       100 Nautical Mile Combat Radius
       Sea Level Standard/Atmosphere

IV.   Mission IV - External Cargo Mission

       Gross Weight - 46,000 Pounds
       External Cargo Capability - 20,000 pounds
       20 Nautical Mile Radius
       Flat Plate Area - 26 sq.ft.

V.   Mission V - Ferry Mission

       Alternate Design Gross Weight - 46,000 Pounds
       Ferry Mission Internal Fuel and
       Aux. Tankage

Design, Design Data and Tests

The testing, analysis, and design required in this specification will be satisfied by tests, analysis, and design conducted under Contract AF33(600)39492, AF33(657)9036, AF33(657)-13157, AF33(600)42055, AF33(657)7004, AF33(657)9486, AF33(657)-12258, AF33(657)13529, AF33(657)14888, DA 23-204-AMC-04087(Y), DAAJ01-67-0001(M), DA 23-204-AMC-04366(Y), DAAJ01-68C-0577(M), DAAJ01-68C-1784(M), DAAJ01-68C-1566(M).

Gross Weight

    Design Mission Gross Weight (6000 ft., 95°F) 39,200 lb.
    Design Gross Weight   33,000 lb.
    Alternate Gross Weight   46,000 lb.

II.   Mission II - Design Gross Weight Mission

Design Gross Wt. 33,000 Pounds
100 Nautical Mile Combat Radius
Payload 7,350 pounds outbound
        3,675 pounds inbound
Sea Level/Standard Atmosphere

III. Mission III - Alternate Gross Weight Mission

Alternate Design Gross Weight - 46,000 Pounds
100 Nautical Mile Combat Radius
Sea Level Standard/Atmosphere

IV.   Mission IV - External Cargo Mission

Gross Weight - 46,000 Pounds
External Cargo Capability - 20,000 pounds
20 Nautical Mile Radius
Flat Plate Area - 26 sq.ft.

V.   Mission V - Ferry Mission

Alternate Design Gross Weight - 46,000 Pounds
Ferry Mission Internal Fuel and
Aux. Tankage

Design, Design Data and Tests

The testing, analysis, and design required in this specifica-
tion will be satisfied by tests, analysis, and design con-
ducted under Contract AF33(600)39492, AF33(657)9036, AF33(657)-
13157, AF33(600)42055, AF33(657)7004, AF33(657)9486, AF33(657)-
12258, AF33(657)13529, AF33(657)14888, DA 23-204-AMC-04087(Y),
DAAJ01-67-0001(M), DA 23-204-AMC-04366(Y), DAAJ01-68C-0577(M),
DAAJ01-68C-1784(M), DAAJ01-68C-1566(M).

Gross Weight

Design Mission Gross Weight (6000 ft., 95°F) 39,200 lb.
Design Gross Weight   33,000 lb.
Alternate Gross Weight   46,000 lb.

Center of Gravity Locations

Center of gravity locations at design gross weight are as follows: NOTE: See envelope diagram below for flight CG extremes versus gross weight.

Design Gross Weight

C G location forward of datum line between rotors: 3.1 in. fwd. (Condition: Center of Gravity of cargo located at middle of cargo floor).

Fuselage
Station 331

Forward   Aft

CG LOCATION

Areas

The principal areas are estimated to be as. follows:
(Not to be used for inspection purposes.)

Rotor Blade Area (6 at 63.1 sq.ft.)	379 sq.ft.
Swept Disc Area (per MIL-STD-832)	approx. 5000 sq.ft.
(£ Rotation To Tip)	
Geometric Solidity Ratio	.067
Geometric Disc Area	5,655 sq.ft.

(2 rotors at 2,827 sq. ft.)

Dimensions and General Data

The following information is not to be used for inspection
purposes:

Wheel Size

Wheels (Forward Gear)	24 x 7.7 VII
Wheels (Aft)	24 x 7.7 VII

Tire Size

Wheels (Forward Gear) (Ten Ply Rating)	8.50 - 10 III
Wheels (Aft Gear) (Ten Ply Rating)	8.50 - 10 III

Tread of Wheels

Forward Gear	10 ft. 6 in.
Aft Gear	11 ft. 2 in.

Wheel Base	22 ft. 5.9 in.

Vertical Travel of Axle from Fully Extended to
Fully Compressed Position

Forward Gear	11 in.
Aft Gear	11.5 in.

Angle Between Lines Joining Center of Gravity with Points
of Ground Contact of Outboard Forward Wheels

    Tires - Static Deflection of 1W
            (front elevation) degrees   77° 26 ft.

Rotor Spacing

    Distance between centerline of rotors   39 ft.2 in.

Height

    *Over Rotor Blades at Rest (Dephased)   18 ft.7.1 in.

    Sail area (cross section area of
    aircraft at butt line zero)   487 sq. ft.

    Sail Area Centroid   Sta. 367.5
                            W.L. 28.6

*For carrier based helicopters, the overall height can be
17 feet for hangar deck stowage when a kneeling kit is pro-
vided.

Rotor Blade Clearance**

(Ground to tip, forward rotor, static)   7 ft. 6.7 in.
(Ground to tip, rotors turning)   11 ft. 0.9 in.
(L.E. of aft pylon to forward rotor
    blade tip, rotor blades static)   16.7 in.
(L.E. of aft pylon to forward rotor
    blade tip, rotor turning)   40 in.
Elevation of aft rotor over forward
rotor (at hub)   4.0 in.

**Controls in neutral is defined by the following character-
istics: (1) The thrust level (collective pitch control) is
in the full down position: (2) The control stick (longi-
tudinal control) is in the center travel position as indicated
by the zero reading on the stick position indicator (stick
travels forward and aft); (3) The control stick (lateral con-
trol) is in the center travel position (equal-side by side,
left and right pedals travel forward and aft); the DCP trim
wheel (stick positioner) is in the zero trim position.

Rotor Data

Rotor RPM (normal and military power)	230 - 250
Rotor RPM (maximum autorotation)	261
Power Loading at Alternate Design Gross Weight (46,000/6090)	7.55 lb/HP
Tip Speed - Normal (245 rotor RPM)	769 fps
Thrust Coefficient (245 RPM, S.L. Std., 33,000 lb)	.00415
Blade Droop Stop Angle (ECP 563)	Fwd 4 3/4°
	Aft 1 1/2° (ECP 563)
Blade Twist (center line of rotor to tip)	9° 14 ft.

Angle of Line Through Center of Gravity and Ground Contact
Point of Forward Wheel Tire to Vertical Line

Reference line level, static deflection of 1W (side elevation) degrees.	45°

Maximum Slope Helicopter Can be Parked Upon Without
Overturning

Nose, uphill and most aft center of gravity, degrees	62° 30 ft.

Critical Turnover Angle

Normal C.G. with aft wheel swiveled inboard	51° 12 ft.
Weight Empty C.G. with aft wheel swiveled inboard	60° 19 ft.

Rotor Diameter

Span, Rotor Blade Extended	60 ft.

Number of Blades, Each Rotor	3
Geometric Disc Loading (Based on 46,000#)	8.13 lb/ft.^{2}
Airfoil Section Designation and Thickness Boeing-Vertol Drawing T114R1556	B-V 23010-1.58
Aerodynamic Chord Length, Root and Tip	25.25 in.

Width

Rotor Blades Folded	12 ft. 5 in.
Rotor Blades Turning	60 ft.

Length

Maximum
  Rotor Blades Turning (parallel to
  static ground line)   99 ft.

Maximum
  Rotor Blades Folded   51 ft.

Estimated Rotor Blade and Corresponding Blade Control
Movements

Collective Pitch

Blade Motion	1° to 18°
Collective Pitch Lever Travel	9.15 in.

Directional Control (Yawing)

Differential Lateral Cyclic   11.43° right
Blade Pitch   11.43° left

Directional Pedal   3.60 in. forward
                                     3.60 in. aft

Longitudinal Control (Pitching)

Differential Collective Blade Pitch 4° plus
                                     4° minus

Stick Control Movement   6.5 in. forward
                                     6.5 in. aft

Lateral Control (Rolling)

Lateral Cyclic Blade Pitch   8.0° left
                                     8.0° right

| Stick Control Movement | 4.18 in. right |
| | 4.18 in. left |

| Maximum Simultaneous Directional | 16.5° fwd. rotor |
| Plus Lateral Control | 16.5° aft rotor |

Trim Controls

Stick Trim

| Differential Collective Blade Pitch | 1° plus |
| | 1° minus |

Speed Trim

Automatic as a function of forward speed as required.
(Reference 114-TN-601, Revision A & ECPs 571, 575, 598, and 611)

WEAPON PARAMETERS

Reference 14 contains detailed data on the XM204, 105mm Howitzer. The following data has been extracted from Reference 14 and was used as the basic weapon parameter for this study.

XM204, 105mm Howitzer Parameters

Description

   a. General - The XM205 105mm Howitzer is the first towed artillery weapon which uses the Soft (Fire-Out-Of-Battery) Recoil Cycle. This weapon differs in appearance from conventional artillery weapons in that it has a single trail extending forward under the tube and no trails extending to the rear, Figure 60. The weapon is traversed and elevated by handwheels located on the side of the carriage. A 6,400 mils traverse capability is provided as the carriage pivots around the center of a circular base by means of a roller device located at the end of the trail. The elevating system is of extending ball screw type, with concentric mechanical springs for equilibration, and provides an elevation range of from -89 to +1333 mils. This weapon is capable of being air lifted in

126

Figure 60. XM204 Howitzer, Light Towed, 105mm, Soft Recoil

127

RECOIL MECHANISM, 105MM HOWITZ

ITEM - 638441
SCREW - MS51905-17 (2)
WASHER - MS35333-42 (2)

Figure 60.   XM204 Howitzer, Light Towed, 105mm, Soft Recoil

ER. XM46 - 69F129

CANNON, 105 MM HOWITZER, XM205 - WTV- F20561

CARRIAGE, 105 MM HOWITZER, XM44 - 69F127

MECHANICAL PROPERTIES						DEPT OF THE ARMY U.S. ARMY WEAPONS COMMAND ROCK ISLAND, ILLINOIS, 61201		
			TOLERANCES ANGLES ± 3 PLACE DECIMALS ± 2 PLACE DECIMALS ±			XM204 HOWITZER LIGHT TOWED, 105 MM SOFT RECOIL		
			DATE 6 JAN 1972					
NEXT ASSY	USED ON					19204	69F126	
APPLICATION								REA

addition to being towed at speeds up to 35 mph over hard-surface roads.

This weapon utilizes the soft-recoil cycle to achieve its reduced size and weight while still maintaining good firing stability. Staking is not required for most soil conditions.

The XM204 Howitzer (69F126) is composed of an XM44 Carriage, an XM46 Recoil Mechanism, an XM205 Cannon and the required fire control equipment. These major components are described in detail in the paragraphs that follow.

Figure 60 is a side view drawing showing a general overview of the XM204 Howitzer Light Towed, 105mm Soft Recoil.

b. XM44 Carriage (69F127) - The XM44 Carriage mounts the cannon and recoil mechanism and provides the means of transporting and emplacing the weapon. The carriage is composed of a welded box section undercarriage, a traversing beam assembly, a cradle and buffer assembly, an elevating mechanism, a suspension system and a firing base. These components are described in the paragraphs that follow:

(1) Carriage (69F665): The undercarriage is basically an aluminum box frame construction. Triangular shaped boxed sides provide the required carriage stiffness. This welded structure is composed of three major sections. The breech end contains the trunnions, the firing base connection, the handwheel locations, and a compartment for tools and accessories. The center section contains all the suspension connections and the muzzle end contains the traversing and elevating component connections. The muzzle section also provides the connecting point for the cradle travel lock.

(2) Traversing Beam Assembly (69F161): The forward part of the traversing mechanism is called the walking beam. This assembly is a boxed H-shaped beam with a fixed pintle which allows it to rotate 20° total displacement perpendicular to the ground. The walking beam consists of an H-frame, a pair of rubber treaded aluminum rollers, splined shafts, U-joints and drive chains. The 15 in. diameter rollers are driven by splined shafts and U-joints with the chains from a central drive shaft through the pintle into the carriage traverse drive.

Tabulated Data

Weights

Complete Weapon	3,615 lb.
30 in. Barrel Extension	136 lb.
Carriage XM44	1,973 lb.
Recoil Mechanism XM46	505 lb.
Cannon XM205	1,137 lb.

Dimensions (Travel Condition)

Length	14 ft. 10 in.
Width	6 ft. 6 in.
Height	5 ft. 10 in.
Ground Clearance	12 in.
Tread	5 ft. 10 in.
Center of Gravity	8 ft. 4 in. behind center of lunette

Lunette Load	225 lb. at 29 in. high

Tires

Size	7:00 x 16, 6 ply

Pressure:

Transport	45 psi
Tactical	20 psi

Angle of Departure	26 degrees
Elevation Range	-89 mils to +1333 mils
Traverse Range	Full 6400 mils
Prime Mover	3/4 ton 4 x 4 truck

Maximum Towing Speed

    Cross Country   10 mph
    Improved Roads   35 mph

Brakes   Hand Parking

Type of Firing Mechanism   Continuous Pull

Rate of Fire

    Maximum   10 rds per min
                                        for 3 minutes

    Sustained   3 rds per min

Handwheel Loads   10 lb. (approx)

Mils of Movement per Turn of Handwheel

    Elevation   10 (approx)

    Traverse   10 (approx)

TABLE XI. ENGINE CHARACTERISTICS AND WEIGHT AND PERFORMANCE CRITERIA

		CH-47C
Engine Characteristics		
Maximum Rating	(shaft HP)	3,750
Military Rating	(shaft HP)	3,400
Normal Rating	(shaft HP)	3,000
Weights		
Design Gross Weight	(lb)	33,000
	(kg)	14,969
Alternate Gross Weight	(lb)	46,000
(1)	(kg)	20,856
Empty Weight	(lb)	20,378
	(kg)	9,243
Payload Capability	(alternate GW)	
- 10 nautical miles	(lb)	24,100
18.5 kilometers	(kg)	10,931
- 100 nautical miles	(lb)	19,800
185 kilometers	(kg)	8,981
- Full Fuel	(lb/NM)	17,300/149
	(kg/km)	7,847/276
Performance (33,000 Pounds Gross Weight, Standard Atmosphere)		
Hover Ceiling - Out of Ground	(ft)	14,700
Effect	(meters)	4,481
Maximum Power		
Forward Rate of Climb	(ft/min)	2,880
(Sea Level/Normal Rated Power)	(meters/sec)	14.63
Service Ceiling - Two		(2)
Engines	(ft)	15,000
(Normal Rated Power)	(meters)	4,572
Speed Capability	(kt)	165
(Sea Level/Normal Rated Power)	(km/hr)	306

(1) Excludes troop seats, supports, and engine inlet screens

(2) Envelope established by current flight test program

APPENDIX II

DESIGN CRITERIA AND LOADS

This appendix presents the design criteria and applied loads due to howitzer recoil, blast pressure, crash and maneuver loads which were used for design. Functional design criteria are also presented.

STRUCTURAL DESIGN CRITERIA

The structural design criteria established herein are in compliance with AR-56 military requirements and special CH-47 design limitations. These criteria will be used for sizing redesigned airframe structure for the weapons kit and to evaluate the present aircraft structural integrity and feasibility for a howitzer-mounted CH-47C.

PHYSICAL PROPERTIES OF MATERIALS

The physical properties of materials used in the design will be in accordance with MIL-HDBK-5.

FACTORS OF SAFETY

Yield factor of safety = 1.0; alternate factor of safety = 1.5.

FLIGHT AND LANDING RESTRICTIONS

Item	Minimum Flight Gross Weight	Alternate Gross Weight
Gross Weight, lb	35,000 (33,000 test data)	46,000
Flight Maneuver Load Factors at CG, g (Limit)	3.0	2.3
	-.5	-.5
Sinking Speed for Landing, fps (Limit)	8.2	designed and demonstrated

Slope landings to the right or left must not exceed 15 degrees.

EXTERNAL HOWITZER HOIST

Maneuver load factor = 3.0 g's (vertically). Sway or coning angle = 15 degrees in any quadrant.

133

CRASH LOADS CRITERIA

Eight g's down (vertically)

Eight g's forward (longitudinally)   Acting separately

Eight g's side (laterally)

CARGO COMPARTMENT FLOOR

1. Internal cargo and ordinance shall not exceed a uniform
    floor loading of 300 psf.

2. Concentrated loads in the cargo area shall not exceed
    2,500 pounds for the treadway, 1,000 pounds for the floor.

DRIVE SYSTEM

The torque split will not exceed 60 percent on either rotor.

FATIGUE DESIGN CONDITIONS

Dynamic Components

A representative aircraft mission profile is required to re-
evaluate component lives. These lives should not be degraded
from the standard CH-47C component fatigue lives as a result
of the incorporation of the weapons.

Howitzer Attaching Hardware

The attaching structure will be designed for an unlimited life.

APPLIED LOADS

The weapon installation generates loads due to firing the
weapons and the accelerations caused by maneuvering the heli-
copter and by crashing. These applied loads multiplied by the
appropriate factors result in limit and ultimate loads. Firing
the weapons produces muzzle blast loads and recoil loads.
Blast loads have been calculated based on the pressure isobars
with consideration for blast pressure reflections. These
blast loads are presented in this report in the section where
the loads data are required. Recoil loads for the XM204
howitzer were obtained from RIA and are summarized in Table XII.
A distribution of these recoil loads may be useful in subse-
quent studies where fatigue due to firing is addressed. The
distribution in Table XIII is suggested for this purpose.

DESIGN LIMIT LOADS

Design limit loads are the maximum loads anticipated to be

134

TABLE XII. DESIGN RECOIL LIMIT LOADS CRITERIA

	Condition	Design Load Magnitude lb/direction	Frequency of Occurrence
Normal Operations Inflight	Zone 5, no impulse generator	7,000 aft	5,000 firings from each weapon
Normal Operations on Ground	Attached firing, all zones and elevations except zone 8 at 75°	7,000 distributed in elevation, azimuth and charge as shown in Table XIII 13,000	5,000 firings
Malfunctions Inflight	Zone 8 with velocity for zone 5 Sensor misfire Zone 5 from latch (cookoff)	36,500 aft 19,500 forward 16,000 aft	1 per weapon 1 per weapon
Malfunctions Ground	Zone 8 with velocity Sensor set for zone 5 misfire Zone 5 from latch	36,500 recoil 19,500 counter-recoil 16,000 recoil	The mounting shall be designed for one of each failure with the weapon at any azimuth and elevation within its available travel

TABLE XIII. DISTRIBUTION OF GROUND FIRING CONDITIONS TO BE USED FOR RIGHT-SIDE HOWITZER

ELEVATION (DEGREES)	PERCENT OF ALL FIRING AT AZIMUTH ANGLES (DEGREES)									TOTAL FOR ALL AZIMUTHS
	0	45	60	75	90	105	120	135	180	
10	0	0	0	1	1	1	0	0	0	3
20	0	0	1	1	1	1	1	0	0	5
30	0	0	1	1	1	1	1	0	0	5
45	2	5	5	10	30	10	5	5	2	74
60	0	0	1	2	4	2	1	0	0	10
70	0	0	0	0	3	0	0	0	0	3
TOTALS FOR ALL ELEVATIONS	2	5	8	15	40	15	8	5	2	

Charge zones for ground firing will be assumed to be distributed as:

ZONE	PERCENT OF ALL ROUNDS FIRED
8	60
7	20
6	10
5	5
4 or less	5

applied on the helicopter during its lifetime of operation. The helicopter structure shall be capable of supporting these limit loads without suffering detrimental permanent deformation. For the weapon installation, the design limit loads are based on 3g maneuver loads and the recoil applied loads as shown in Table XIV. The various components of these loads as applied to the weapon support structure are shown in Table XV.

ULTIMATE DESIGN LOADS

Ultimate design loads are the limit design loads multiplied by a 1.5 factor of safety. Ultimate loads for the fuselage attachments are shown in Table XVI with comparable ultimate design loads for the forward main landing gear beam. This comparison shows that the howitzer installation causes loads which are about twice the landing gear loads.

FUNCTIONAL DESIGN CRITERIA

To ensure functional compatibility of the XM204 weapons and CH-47C aircraft, design criteria for each of these major components were separately formulated and then integrated to produce the system criteria for the study configuration.

The following itemizes those installation design considerations important to the safe, efficient operation of the XM204 weapon:

1. Provide a level, secure foundation for the weapon firing base and walking beam assembly.

2. Prevent exposure to damaging vibration or loads which would adversely affect the fatigue service life of the weapon.

3. Protect the weapon against deterioration due to constant exposure to climatic conditions.

4. Provide for ease of weapon servicing maintenance and repair.

5. Provide space for crew stations for manual operation of the weapon.

6. Provide for ease of handloading (nearest obstruction behind breech shall be no closer than 40 inches).

7. Provide means for boresighting the weapon.

The following are the external loading considerations which have been developed to ensure the safe operation of the aircraft:

137

			Design Recoil Load From Table I, lb		Design Load Factor g		
Flight Conditions	No.	Howitzer Charge Conditions	P_L	P_R	n_z	n_x	n_y
Inflight Normal		Acting together Zone 5	+7000	+7000	3.0	1.0	1.0
		Acting separately Zone 5	+7000	0	3.0	1.0	1.0
		Acting separately Zone 5	0	+7000	3.0	1.0	1.0
Inflight Malfunctions		Zone 5, Cookoff	+16000	0	3.0	1.0	1.0
		Zone 5, Cookoff	0	+16000	3.0	1.0	1.0
		Misfire	-19500	0	3.0	1.0	1.0
		Misfire	0	-19500	3.0	1.0	1.0
		Zone 8, Velocity Sensor Set at Zone 5	36500	0	3.0	1.0	1.0
		Zone 8 Velocity Sensor Set at Zone 5	0	36500	3.0	1.0	1.0
Ground Operations Normal	10	All Firing Zones & Elev. Except Zone 8 at 75°	0	+7000	1.0	1.0	1.0
	11	Firing Zone 8 at 75°	0	+13000	1.0	1.0	1.0
Ground Operation Malfunction	12	Zone 8 with Velocity Sensor at Zone 5	0	+36500	1.0	1.0	1.0
	13	Misfire	0	-19500	1.0	1.0	1.0
	14	Zone 5, Cookoff	0	+16000	1.0	1.0	1.0
Crash 1	15	No Gun Firing	0	0	8.0	8.0	8.0

TABLE XIV.   DESIGN LIMIT LOADS

Notes: 1   Load factors are for ult. condition acting separately in each direction.
         2   Double failures are not considered as a design condition

H_{ZL} = Port Howitzer Weight = 3571 Lbs.
H_{ZR} = Starboard Howitzer Weight = 3200 Lbs.

TABLE XV. CRITICAL DESIGN LIMIT AND ULTIMATE LOADS

CONDITION NO FROM TABLE XIV	GUN FIRING AZIMUTH & ALTITUDE POSITION - DEG	LIMIT DESIGN LOADS - LBS							ULTIMATE DESIGN LOADS - LBS				
		GUN RECOIL LOAD		GUN RECOIL LOADS IN X Y Z AXIS			HOWITZER WT		GUN RECOIL LOADS IN X, Y, Z AXIS			HOWITZER WT	
		P_L	P_R	P_Y	P_X	P_Z	M_{ZR}	M_{ZL}	P_Y	P_X	P_Z	M_{ZR}	M_{ZL}
9	0.0	0	36,500	0	36,500	0	3,675	-3,571	0	54,900	0	16,600	16,000
12 a	0.0	0	36,500	0	36,500	0	4,475	-3,571	0	54,900	0	-6,700	5,350
12 b	0.75°	0	36,500	0	9,450	35,200	4,475	-3,571	0	14,200	52,900	-6,700	5,350
12 c	90°	0	36,500	36,500	0	0	4,475	3,571	54,900	0	0	6,700	5,350
12 d	90°,75°	0	36,500	9,450	0	35,200	-4,475	3,571	14,200	0	52,900	6,700	5,350

NOTES

1. STARBOARD GUN FIRING WILL SIZE BEAM SUPPORT STRUCTURE
2. WT INCLUDES 3 200 LB HOWITZER · 475 LB PLATFORM
3. WT INCLUDES 3 200 LB HOWITZER · 475 LB PLATFORM · C L 800 LB MEN

CONDITIONS
9, 12 a, 12 b


CONDITIONS
12 c, 12 d

139

TABLE XVI.

ULTIMATE DESIGN LOAD SUMMARY – LBS

	FWD MAIN LANDING GEAR BEAM RH AND LH SIDES STA 260 TO 240	HOWITZER SUPPORT BEAM STA 320 TO 300 AFT BEAM		STA 210 TO 230 FWD BEAM
		RH SIDE	LH SIDE	LH SIDE
VERT	34,500	52,900	17,100	11,400
DRAG	19,900	54,900	33,000	22,000
SIDE	16,700	54,900	17,100	11,400

NOTES: 1. THE ULTIMATE LOADS SHOWN ABOVE DO NOT NECESSARILY ACT TOGETHER, EACH LOAD REPRESENTS THE MAXIMUM IN ITS RESPECTIVE DIRECTION.

2. FWD MAIN LANDING GEAR ULTIMATE LOADS WERE EXTRACTED FROM REF. NO. 18

140

1. Total loading (including externally-mounted equipment) shall not exceed the alternate gross weight of the aircraft.

2. Externally-mounted objects shall be adequately secure to prevent them coming off in flight and damaging the rotor system.

3. Static and dynamic (recoil) loads from externally-mounted equipment must be reacted without detrimental effect on the airframe structure.

4. Externally-mounted loads must not change airframe vibration natural frequency to such an extent as to result in premature fatigue failure of components.

5. Emergency jettison provisions shall be included for external loads suspended from the aircraft on cables.

6. External loads must not contribute excessive rotor downwash frontal area which would result in excessive hover download.

7. Drag increase due to the weapons must not seriously disrupt aircraft performance or controllability.

APPENDIX III

REQUIREMENTS FOR THE STRUCTURAL TEST PROGRAM

In this appendix, a first cut has been taken to define the structural test program required to ensure that the weapons installation is adequate. This outline should be expanded as more details become known.

STATIC TEST OF WEAPON INSTALLATION TO LIMIT LOADS

Test the howitzer attaching hardware as mounted on a CH-47C fuselage at limit load under design operating conditions. The test static limit load is 36,500 pounds on the right-hand side acting at any azimuth position and altitude. Strain gauge the howitzer attaching hardware and fuselage at critical locations. Success is defined by no yielding of the aircraft structure at limit load. Spring rates of the mounting structure should be measured during loadings to check the vibration dynamics analyses.

WEAPON FIRING GROUND TESTING

Limit load test the forward fuselage skin, doubler, stringers, and frames during a zone 8 charge blast with the weapon's muzzle in the in-flight mode parallel to the fuselage longitudinal axis. The test should be performed with rotors operating at 100-percent rpm. Six weapon firings is a minimum requirement.

Strain gauge the rotor blades, controls, forward fuselage skin, frames and doubler. Gauge response time should be capable of recording the peak overstress lasting approximately .1 to .8 milliseconds. Success is defined by no yielding of the aircraft structure for a zone 8 charge.

Monitor peak fuselage acceleration airframe locations selected by the Dynamics group. A major concern is the vertical, longitudinal and lateral accelerations in the forward cabin area. Various doubler isolation designs may be experimented with to optimize the vibration environment for airframe fatigue and crew comfort.

Acoustical measurements in the forward and aft fuselage should be measured to determine the noise levels during firing to see if further acoustic treatment is necessary.

COMPONENT VIBRATION TESTING

All components of the weapons installation must be tested to ensure that helicopter vibration will not cause fatigue

142

failures. Vibration shake tests will be conducted on all
components including the howitzers with accelerations and
frequencies to be Boeing-Vertol specifications. Components
that could cause the firing of the weapons to hit the heli-
copter need particular attention.

FLIGHT TESTING INCLUDING WEAPON FIRING

Conduct a flight test program to determine dynamic component
loads, airframe loads, and airframe vibrations during level
flight including firing of a zone 5 charge with each howitzer.
Determine lateral cg limits based on structural or control
limits, whichever is less, with the left-side howitzer detached
and unloaded. Also, record steady and vibratory stress and
vibration data for rotor blades, controls and rotor shaft.

APPENDIX IV

STRESS ANALYSIS

In this appendix, the detail stress calculations used to size the structure of the weapons kit and the hardpoints provisions are presented. Results of a reevaluation of the dynamic component fatigue lives which consider the continuous high gross weight operation of the aerial artillery mission are also presented. Detail calculation of rotor blade stresses that show that muzzle blast loads can be accommodated without modification is presented.

DYNAMIC COMPONENT FATIGUE EVALUATION

Incorporation of the weapons kit on the CH-47C helicopter will have a consequential effect on the assumed aircraft mission profile and dynamic system component vibratory loads and life. A simplified fatigue evaluation relating aircraft usage (mission profile), structural envelope, and fatigue loads is presented.

The current CH-47C mission profile used in establishing component lives, as reported in Reference 15, is shown in Table XVII. The AAWS CH-47C mission profile, Table XVIII, was constructed by coordinating appropriate field experience (Reference 16), military requirements (Reference 17), and configuration design requirements. The major differences between the current CH-47C profile and AAWS CH-47C profile are:

- Time spent at normal and alternate gross weights

- Time spent in the forward CG position

- Time spent from 0-6000 (H_D) density altitude

- Time spent in a lateral CG position

The first two items may have an adverse effect on forward dynamic component fatigue lives. The third item should enhance forward and aft component fatigue lives. The effects of lateral CG position on dynamic component fatigue loading is uncertain with the exception of vibratory rotor shaft bending moments which will increase above the 0.0 lateral CG position vibratory shaft bending moments.

The maximum forward airspeed V_H (maximum airspeed attainable using the lower of military rated power or the structural limit Vne) for the basic CH-47C and the modified AAWS CH-47C is shown in Figure 61. As noted in the figure, the AAWS-configured CH-47C maximum airspeed (V_H) at 35,000 pounds gross weight is

144

TABLE XVII. BASIC CH-47C FATIGUE LOADING SCHEDULE

Gross Weight (lb)	Percent Time	RPM Split	CG Split	Aft Split	Cargo Split	Flight Condition	Occurrence
27,000	50	100% at 235-245 rpm	100% at normal CG	50% <6,000' 40% 6-10,000' 10% >10,000'	None	**Level Flight** Hover Transition 60% Vne 90% Vne 100% VH 110% VH **Maneuvers** Landing Flare Turn Pullup Lateral Rev Long Rev Dir Rev	10% 15% 25% 20% 20% 10% 4/hr 10/hr 4/hr 4/hr 4/hr 4/hr
33,000	25	Same as 27,000 lb GW	50% fwd CG; 50% aft CG	Same as 27,000 lb GW	None	Same as 27,000 lb GW	Same as 27,000 lb GW
46,000	25	100% at nominal 245 rpm	See cargo split	50% <6,000' 50% >6,000" (internal cargo only)	75% w/external cargo at aft CG, TAS ≤6,000', VH = 100 kt 25% w/internal cargo 50% at fwd CG 50% at aft CG	Same as 27,000 lb GW	Same as 27,000 lb GW

TABLE XVIII.   CH-47C AAWS FATIGUE LOADING SCHEDULE

Gross Weight (lb)	Percent Time	RPM Split	CG Split	Aft Split	Cargo Split	Flight Condition	Occurrence
33,000 Right Howitzer Only	10	100% at 235-245 rpm	100% at neutral or foward longitud-inal CG, 18"R lateral CG	90% <6,000', 10% <6,000'	None	**Level Flight** Hover Transition 60% VH 90% VH 100% VH 110% VH **Maneuvers** Landing Flare Turn Pullup Lateral Rev Longitudinal Rev Directional Rev	10% 15% 25% 20% 20% 10% 4/hr 10/hr 4/hr 4/hr 4/hr 4/hr
35,000 Left & Right Howitzers, Minimum Flight Weight	40	Same as 33,000 lb GW above	100% at forward CG	90% <6,000', 10% <6,000'	None	Same as 33,000 lb GW above	Same as 33,000 lb GW above
46,000 Alternate GW	50	100% at normal 245 rpm	100% at forward CG	90% <6,000', 10% <6,000'	None	Same as 33,000 lb GW above	Same as 33,000 lb GW above

146

BASIC CH-47C

GW = 35,000 LB
N_r = 235 RPM

GW = 46,000 LB
N_r = 245 RPM

AAWS CH-47C

—— V_{NE}

GW = 35,000 LB   — ·— XMSN LIMIT   GW = 46,000 LB
N_r = 235 RPM   - - - - MIL POWER N_r = 245 RPM

DENSITY ALT ... FT

T..S - KNOTS

Figure 61. CH-47C Structural and Power Flight Limitations
            For STD

147

approximately 33 knots slower than the basic CH-47C. As a result, fatigue damage at 35,000 pounds gross weight in the AAWS configuration will be negligible. Maximum airspeed (V_H) at 46,000 pounds gross weight is essentially the same for the basic CH-47C configuration and the AAWS configuration.

Longitudinal CG limits are within the flight manual limits (Figure 36); lateral CG structural limits have not been established at this time.

CONCLUSION

The following assumptions are made concerning fatigue damage for the AAWS configuration:

1. Forward dynamic system component fatigue damage at 46,000 pounds gross weight - level flight will double in the AAWS configuration from that published in Reference 19.

2. Forward dynamic system component vibratory loads during gun firing are assumed nearly equivalent to loads prior to firing.

3. No fatigue damage at 35,000 pounds and below to either the forward or aft dynamic component.

4. The entire aircraft life is spent in the AAWS configuration.

5. Possible fatigue damage incurred during operations at the extreme lateral CG position is negligible due to low occurrence.

Table XIX lists the CH-47C dynamic component lives that will be reduced when operating in the AAWS configura*.: All other component lives will remain as listed in Refe· .. ..

CH-47C AIRFRAME ULTIMATE STRENGTH

Any redesign or addition to the helicopter structure that alters the original design loads requires an ultimate and fatigue analysis to substantiate the structural integrity of the integrated systems. Reanalysis of the present CH-47C airframe to accommodate two externally-mounted XM204 howitzers is beyond the scope of this study; therefore, only general strengthening requirements are discussed.

The present CH-47C lower fuselage structures are constructed of .020-inch-thick skin, stiffened by honeycomb stringers. Skin and stringer stiffening between stations 160 to 360 will be required to distribute howitzer ultimate design side and drag loads into the fuselage. Frame stiffening between stations 160 and 360 is required to react ultimate design vertical

		Current Life (hr)	AAWS Life Approx. (hr)
TABLE XIX.	REDUCED FORWARD ROTOR COMPONENT LIVES DUE TO CONTINUOUS HIGH GROSS WEIGHT OPERATIONS OF AERIAL ARTILLERY MISSIONS		
P/N	Component		
114R1570-1	Forward Rotor Blade Nose Cap Station 100	6,220	3,300
114R1518-1, -2, -3	Forward Rotor Blade Trailing Edge Station 144	12,500	5,800

loads from howitzer recoil, crash conditions, and hoist requirements.

Airframe bending moments and shear diagrams for each critical design condition will be calculated to determine the fuselage stiffness requirements to accommodate the externally-mounted howitzers.

CH-47C AAWS HOWITZER SUPPORT BEAM ANALYSIS

The purpose of this section is to size the howitzer support beam installation as shown in Figure 10. Airframe beef-ups required to incorporate this system will be discussed in another section.

The design criteria as established by the customer and presented in the Boeing-Vertol Progress Report of May 1972 is presented in Tables XII and XIII.

The right-side gun mounting is more critical than the left gun. The selected material and beam cross-section which conforms to the design conditions is shown below.

Summary

Material

4340 HT steel

$F_{tu} = 150,000$ psi

Beam Section

Starboard Side Aft Beam

$t = .062"$ 10"   20"

Port Side Aft Beam

10" $t = .062"$ 20"   Retractable Beam

Port Side Fwd Beam

6"   12"   Retractable Beam

150

HOWITZER INSTALLATION

Aft lateral beam support sizing (right side); condition #9, Table XIV.

View looking forward:

View A-A

$\overline{P}_X$ Recoil Reaction Load) = 54900 Lbs.

Beam Material: 4340 HT steel from (SDM) Reference 20.

F_{tu} = 150 ksi	S_e = ±20,000 psi nonfretted R = -1
F_{ty} = 132 ksi	S_e = ±10,000 psi fretted R = -1 } K_t = 1
F_{cu} = 145 ksi	F_{bu} = 222.5 ksi
F_{su} = 95 ksi	F_{by} = 165 ksi
E = 29 x 10^6 psi	
G = 11 x 10^6 psi	

151

Condition #9, Table XIV

$M_{xA} = 0$

$M_{yA} = +46.5 \times 16600 - 38 \times 54900 = 0$

$M_{yA} = +770,000 - 2,080,000$

$M_{yA} = -1,310,000$ in.-lb

$M_{Az} = -2,745,000$ in.-lb

$P_{zA} = +16,600$ lb

$P_{xA} = -54,900$ lb

$P_{yA} = 0$

Condition #12.c, Table XIV

$P_{xA} = 0$

$P_{zA} = +6,700$ lb

$P_{yA} = +54,900$ lb

$M_{yA} = 0$

$M_{xA} = +2,715,000$ in.-lb

$M_{zA} = 0$

$+M_{xA} - 6700 \times 95 - 38 \times 54,900 = 0$

$M_{xA} = 635,000 + 2,080,000$

$M_{xA} = 2,715,000$ in.-lb

Condition #12.d, Table XIV

$P_{xA} = 0$

$P_{yA} = -14,200$ lb

$P_{zA} = -46,200$ lb

$M_{xA} = -2,850,000$ in.-lb

$M_{yA} = 0$

$M_{zA} = 0$

P_{zA} $+52,900 - 6700 = 0$

$P_{zA} = -46,200$ lb

P_{yA} $+14,200 = 0$

$P_{yA} = -14,200$ lb

M_{xA} $-50 \times 6700 \times 50 \times 52,900$

$+38 \times 14,200 = 0$

$M_{xA} = -2,850,000$ in.-lb

<u>Right-Hand Lateral Support Beam Sizing</u>

Condition	REACTION LOADS						THICK NESS t (IN)	M.S.
	P_{XA} (LB)	P_{YA} (LB)	P_{ZA} (LB)	M_{XA} x1000 IN-LB.	M_{YA} x1000 In-LB.	M_{ZA} x1000 IN-LB.		
#9	-54900	0	+16600	0	-1310	-2745	.062	+.40
#12.c	0	+54900	+6700	+2715	0	0	.062	+.16
#12.d	0	-14200	-46200	-2850	0	0	.062	+.12

BEAM REACTIONS FOR CRITICAL DESIGN CASES

<u>Right-Hand Side Looking Forward</u>

SECTION PROPERTIES OF RIGHT SIDE LATERAL SUPPORT BEAM

Assume t = .062

Area = 20 x 10 - 19.81 x 9.88 = 200 - 195.5

A = 4.5 in.^{2}

154

$$I_x = \frac{1}{12} \times 3 \times .062 \times 9.88^3 \times 2 \times 20 \times .062 \times 4.97^2$$

$$I_x = 14.95 + 61.26 = 76.21 \text{ in.}^4$$

$$I_z = 1 \times 2 \times .062 \times 19.88^3 + 2 \times 10 \times .062 \times 9.97^2$$

$$I_z = 81.19 + 123.26 = 204.45 \text{ in.}^4$$

STRESS ANALYSIS OF BEAM STRUCTURE

Condition #9, Table XIV

$$\tau_{av} = \frac{P_zA}{3 \times h \times t} = \frac{16,600}{3 \times 10 \times .062} = 8,800 \text{ psi}$$

$$\tau_{av} = \frac{P_xA}{2 \times h \times t} = \frac{54,900}{2 \times 20 \times .062} = 22,200 \text{ psi}$$

$$\tau = \frac{M_yA}{A\ t} = \frac{1,310,000}{2 \times 20 \times 10 \times .062} = 53,000 \text{ psi}$$

$$f_b = \frac{M_zA\ C}{I_z} = \frac{2,745,000}{204.45} \times 10 = 134,000 \text{ psi}$$

$$f_{max} = \frac{f_b}{2} \pm \tau_{max}$$

$$f_{max} = \frac{134,000}{2} \pm 91,000$$

$$f_{max} = 67,000 \pm 91,000$$

$$f_{max} = 158,000 \text{ psi}$$

$$F_{bu} = 22.5 \text{ ksi}$$

$$MS = \frac{222.5 - 1}{158} = +.40$$

$$\tau_{max} = \sqrt{\left(\frac{f_b}{2}\right)^2 + (\tau_{av})^2}$$

$$\tau_{max} = \sqrt{\left(\frac{13.4 \times 10^4}{2}\right)^2 + (6.18 \times 10^4)^2}$$

155

$$\tau_{max} = \sqrt{(45 + 38.3) \times 10^6}$$

$$\tau_{max} = 91,000 \text{ psi}$$

$$F_{su} = 95,000 \text{ psi}$$

$$MS = \frac{95}{91} - 1$$

$$MS = +.04$$

STRESS ANALYSIS OF BEAM STRUCTURE

Condition #12.C, Table XIV

$$f_{axial} = \frac{P_{yA} + P_{zA}}{A} = \frac{54,900 + 6,700}{4.5 \text{ in.}} = \frac{61,600}{4.5}$$

$$f_{axial} = +13,700 \text{ psi}$$

$$f_b = \frac{M_{xA}C}{I_X} = \frac{2,715,000 \times 5}{76.21} = 178,000 \text{ psi}$$

$$f_{max} = 178,000 + 13,700 = 191,700 \text{ psi}$$

$$F_{bu} = 222.5 \text{ ksi}$$

$$MS = \frac{222.5 - 1}{191.7} = +.16$$

Condition #12.d, Table XIV

$$f_{axial} = \frac{P_{yA} + P_{zA}}{A} \quad \frac{14,200 + 46,200}{4.5} = \frac{60,400}{4.5}$$

$$f_{axial} = 13,400 \text{ psi}$$

$$f_B = \frac{M_{xA}C}{I_X} = \frac{2,850,000 \times 5}{76.21} = 186,000 \text{ psi}$$

$$f_{max} = 186,000 + 13,400 = 199,400 \text{ psi}$$

$$MS = \frac{222.5 - 1}{199.4} = +.12$$

156

Forward and Aft Retractable Beam Strength, Left Side

Material

4340 HT Steel

F_{tu} = 150 ksi

F_{ty} = 132 ksi

F_{tu} = 145 ksi

F_{su} = 95 ksi

E = 29 x 10⁵ psi

Beam Dimensions and Properties

Aft Beam - WF Shape

B   = 8.962 in.

A   = 20.86 in.

t_f = .79 in. flange

t_w = .499 in. web

Area = 24.10 in.²

I_{zz} = 1752.4 in.⁴

Z_{zz} = 168 in.³

ρ_{zz} = 8.35 in.

I_{xx} = 89.6 in.⁴

Z_{xx} = 20 in.³

ρ_{xx} = 1.93 in.

Forward Beam - American Standard

B   = 5.477 in.

A   = 12.00 in.

t_f = .659 in.

t_w = .687 in.

Area $= 14.57$ in.^{2}

$I_{ZZ} = 301.6$ in.^{4}

$Z_{ZZ} = 50.3$ in.^{3}

$\rho_{ZZ} = 4.55$ in.

$I_{XX} = 16.0$ in.^{4}

$Z_{XX} = 5.8$ in.^{3}

$\rho_{XX} = 1.05$ in.

Ultimate Design Condition #8, Table XIV

Aft Beam Analysis

$\bar{P}_X = 1.5 \times 36,500 \times .6 = 33,000$ lb

Ultimate Allowable Bending Stress (F_{bu})

$$K = \frac{2Q_m}{I/c} = \frac{2Q_m}{Z_{ZZ}}$$

$Q_m = \bar{x}$ area

$$\bar{x} = \frac{\sum xa}{A} = \frac{.499 \times 9.63 \times 4.8 + .795 \times 8.9 \times 10}{12.05}$$

$$\bar{x} = \frac{22.7 + 60.8}{12.05} = 7.75 \text{ in.}$$

$$K = \frac{2 \times 7.75 \times 24.10}{2 \times 168} = 1.11$$

$F_{bu} = 166$ ksi   From SDM Figure 4.2.1-8 (Reference 20)

$F_{by} = 138$ ksi

$$f_{bx} = \frac{M}{I/c} = \frac{\bar{P}_X d}{Z_{ZZ}} = \frac{33,000 \times 50}{168} = 9,800 \text{ psi}$$

$$MS = \frac{F_{bu} - 1}{f_b} = \frac{166,000 - 1}{9,800} = +16.0$$

$MS = +16.0$

Aft Beam Analysis (Cont.)

Ult. Design Condition #15, Table XIV

$\overline{P}_z = .5 \times 8 \times 3570 = 14300$ Lbs.

$f_{bz} = \dfrac{M}{Z_{xx}} = \dfrac{14300 \times 50}{20} = 36000$ Psi

$M.S. = \dfrac{F_{bu}}{f_{bz}} -1 = \dfrac{166000}{36000} -1$

$M.S. = \quad \quad c$

Fwd Beam Analysis

Ult. Design Condition #8, Table XIV

$\overline{P}_x = 1.5 \times 36500 \times .4 = 22000$ Lbs.

$f_{bx} = \dfrac{M}{Z_{zz}} = \dfrac{22000 \times 50}{50} = 22000$ Psi

$M.S. = \dfrac{166}{22} -1 =$

$M.S. = +6.55$

Ult. Design Condition #15, Table XIV

$\overline{P}_z = 8 \times 3570 \times .5 = 14300$ Lbs.

$f_{bz} = \dfrac{M}{Z_{xx}} = \dfrac{14300 \times 50}{5.8} = 124000$ Psi

$M.S. = \dfrac{F_{bu}}{f_{bz}} -1 = \dfrac{166}{124} -1$

$M.S. = + .34$

LONGITUDINAL SUPPORT BEAM ANALYSIS

Critical design flight condition is #9 of Table XIV.

Figure   Longitudinal Support Beam

Force Diagram   Sign Convention

$P_{LU} = 1.5 \times 7000 = 10,500$ lb

$P_{RU} = 1.5 \times 36,500 = 55,000$ lb

$\varepsilon M_{RL} = 0$

$50 \times 10500 + 106 \times R_R - 156 \times 55,000 = 0$

$$R_R = \frac{860 \times 10^4 - 52.5 \times 10^4}{106}$$

$R_R = 76,000$ lb

$R_L = 10,500$ lb

160

Fifty percent of the maximum and (R_R) goes forward in tension and 50 percent goes aft in compression. The compression section will be critical in crippling.

Material Properties

7075-T6 Aluminum Alloy (CLAD)

F_{tu} = 76 ksi

F_{ty} = 64 ksi

F_{su} = 43 ksi

E = 10.3 x 10^6 psi

Use Channel Section

Assume

F_{cs} = .5 F_{cy}

F_{cs} = .5 x 76,000 lb

P_{cs} = F_{cs} A

$$A = \frac{.5 \times 76,000}{.5 \times 64,000}$$

A = 1.19 in.

From Chap C7.4 in Bruhn Figure C7.7

$$\left(\frac{F_{cy}}{E_c}\right)^{1/2} = \left(\frac{64,000}{10.3 \times 10^6}\right)^{1/2} = .0788 \qquad g = 5 \text{ for a channel}$$

$$\frac{A}{gt^2}\left(\frac{F_{cy}}{E_c}\right)^{1/2} = .0788 \qquad \frac{A}{gt^2} = \frac{.0788 \times 1.19}{5 \times t^2} = 1.15 \text{ (solve for t)}$$

$$t = \sqrt{\frac{.0788 \times 1.19}{5 \times 1.15}}$$

t = .128

161

From SDM selected channel size based on

$A = 1.19$ in.^{2} and $t = .128$ in.

Channel AND 10137 - 2013

$A = 2.0$ in.

$A = 2.5$ in.

$t = .188$ in.

Area $= 1.25$ in.^{2}

$y = .939$ in.

$I_{xx} = .772$ in.^{4}

$I_{yy} = .8394$ in.^{4}

LEFT SIDE HOWITZER TANDEM HOIST LOADS

The two hoists will be sized, based on Appendix II, Design Criteria.

Load factor = 3 g's vertical

Maximum coning angle = 15" in any direction about the vert.

$P_{zu} = 16800$ Lbs.

162

P_{z1} = forward hoist cable reaction load, lb

P_{z2} = aft hoist cable reaction load, lb

Howitzer weight = 3,750 lb

P_{zu} (ultimate design load) = 1.5 x 3 x 3,750 lb

P_{zu} = 16,800 lb

Hoist Cable Ultimate Reaction Loads

Sign Convention - Positive Shown

$\varepsilon F_z + 0$

$P_{z1} + P_{z2} = 16,800$ lb

$\varepsilon M_{cg} = 0$

$49\ P_{z2} - 105\ P_{z1} = 0$

$P_{z2} = \frac{105}{49}\ P_{z1}$

$P_{z2} = 2.15\ P_{z1}$

$\frac{1}{2.15}\ P_{z2} + P_{z2} = 16,800$

$P_{z2} = \frac{16,800}{1.465}$

$P_{z2} = 11,500$ lb

$P_{z1} = 5,300$ lb

163

$\varepsilon F_Z = 0$

$R_{DZ} = 11,500 \text{ lb}$

$\varepsilon M_{OX} = 0$

$- 30 \times 11500 - 21 \times 11500 - 40 R_{BZ} + 104 R_{BZ} = 0$

$64 R_{BZ} = \dfrac{51 \times 11500}{64}$

$R_{BZ} = 9,200 \text{ lb}$

Check

$\varepsilon M_{ZX} = 0$

$- 51 \times 11500 - 70 \times 9200 + 134 \times 9200 = 0$

$- 51 \times 11500 + 64 \times 9200 = 0$

$0 = 0 \qquad \therefore \text{ OK}$

Section A-A Required Section (Previous Page)

Hoist Structure Material

7075-T6 Al. Alloy (CLAD)

Properties

F_{tu} = 73 Ksi

F_{ty} = 63 Ksi

F_{su} = 44 Ksi

E = 10.5 x 10^6 Psi

F_{bu} = 115 Ksi $\left.\begin{array}{l}\\\\\end{array}\right\}$ for K = 1.5

F_{by} = 84 Ksi

Plastic Bending at Section A-A About the X Axis

$$F_{bu} = \frac{M}{I/C} = \frac{\gamma P_z 2}{Z_R} = \frac{30 \times 11500}{Z_R} = 115000 \text{ psi}$$

$$Z_R = \frac{30 \times 11500}{115000}$$

Z_R = 3.0 in.^{3} Required

Assumed Section

h = 6"
B = 6"
t = .064"

$$I_X = \frac{BH^3 - bh^3}{12}$$

where

h = 5.872 in.

b = 5.872 in.

H = 6 in.

B = 6 in.

$$I_X = \frac{6 \times 6^3 - 5.872 \times 5.872^3}{12} = 9.0 \text{ in.}^4$$

$$Z_X = \frac{I_X}{c} = \frac{9.0}{3.0} = 3.0 \text{ in.}^3$$

Area

A = 36 - 5872^2

A = 1.5 in.^2

$$MS = \frac{Z_R}{Z_X} - 1$$

MS = 0.0

Vertical Support Member, Section B-B

<u>Column Instability</u>

Allowable Stress $F_C = \frac{\pi^2 E}{(L'/\rho)^2}$

Column End Fixity Coefficient

C = 4

Assume Section same as Section A-A

L' = L = 90 in.

$$\rho = \sqrt{\frac{I}{A}} = \sqrt{\frac{9.0}{1.5}}$$

ρ = 2.45 in.

$$L'/\rho = \frac{90}{2.45} = 37$$

From SDM Figure 4.1.2.1-6 (Reference 15)

$$F_C = 52.5 \text{ ksi}$$

$$f_C = \frac{R_{DZ}}{A} = \frac{11500}{1.5} = 7,670 \text{ psi}$$

$$MS = \frac{F_C - 1}{f_C} = \frac{52500 - 1}{7670}$$

$$MS = +5.85$$

## FUSELAGE SKIN DOUBLER SIZE DUE TO GUN BLAST PRESSURE WAVE

The purpose of this analysis is to determine the forward fuselage skin doubler sizes required due to a gun blast at zone 8 charge.

The zone 8 charge is based on an inflight malfunction as shown in Table XII. The aft fuselage will be protected during ground firing by limiting the azimuth travel. Present CH-47C forward fuselage skin thicknesses are shown on the following page.

Material

2024-T3 Aluminum Alloy (CLAD)

t	- thickness (doubler)	= determine
ρ	- density	= 5.23 slugs/ft^3
C	- speed of sound, f/s	= 16,470
V_C	- critical velocity, f/s	= 240
E	- elastic modulus, psi	= 11 x 10^6 (1.58 x 10^8 psf)
F_{TU}	- static ultimate strength, psi	= 59,000
F_{TY}	- static yield strength, psi	= 39,000
σ_{yc}	- dynamic yield strength, at V_C, psi	= 143,600
σ_{yc}	$= \rho C V_C = \frac{5.23 \times 16470 \times 240}{144}$	= 143,600 psi

167

Fuselage
Station

Upper Skin(i)
(View Looking Down) (114S1503)

Long'N 41R   B.L. 37.0
B.L. 10.5
.040
.050
B.L. 18.0

B.L. 18.0
.040
Long'N.
.040
B.L. 46.2

Left Hand Side Skin(i)
(View Looking Inb'd) (114S1501)

Long'N 6L
WL 47.0
STR.11
W.L. 23.2
STR.16
W.L. -5.3
STR.21
W.L. -30.0
STR.59L

.040
Escape
Hatch
Cutout
.040
.025
.025
.025
W.L.
-170

Bottom Skin(i)
(View Looking Up) (114S1504)

STR. 59L
B.L. 45.9
B.L. 33.6
B.L. 2.0
B.L. 33.6
STR.59R
B.L. 45.3

.025
.025
B.L. 28.0
.025
.025
.05
.025
Cutout
Cutout
B.L. 17.0
B.L. 8.0
B.L. 2.0

Right Hand Side Skin(i)
(View Looking Outb'd) (114S1502)

Long'N 41R
W.L. 53.7
STR.37
W.L. 38.0
W.L. 34.9
STR.24
W.L. 30.0
STR.59R
W.L. -33.0

.071
.035
Cabin
Door
Cutout
.040
.025
.063
.025
.025
W.L.
17.0

Forward Fuselage Skin Gages

168

Free-space peak overpressure (p) from a zone 8 howitzer charge
is:

$\qquad$ p = 12.0 psi

Peak reflected overpressure (p_r) at a surface of interference
with the free-space peak overpressure is:

$$p_r = 2p\left(\frac{7p_0 + 4p}{7p_0 + p}\right)$$

where

$\qquad$ p_0 = ambient pressure = 14.7 psi

$$p_r = 2 \times 12 \left(\frac{7 \times 14.7 + 4 \times 12}{7 \times 14.7 + 12}\right)$$

$\qquad$ p_r = 31.5 psi

Design pressure (P_D) is equal to peak reflected overpressure
(p_r) and the ultimate design pressure $P_u = 1.5 \times p_r$.

$\qquad$ $P_u = 1.5 \times p_r = 1.5 \times 31.5$

$\qquad$ $P_u = 47.25$ psi

The critical impulse, which is the maximum allowable impulse,
is defined in Reference 9 as:

$$I_c = \frac{t\sigma_y}{c}$$

where

$\qquad$ t = panel thickness

$\qquad$ σ_y = dynamic yield strength

$\qquad$ c = velocity of sound in material

The critical time (t_c) is the duration the yield pressure must
act to obtain sufficient impulse to yield the structure. The
critical structure on the CH-47C is a panel normal to the
howitzer pressure blast.

a = 5 in.

b = 20 in.

The panel frequency from the Boeing-Vertol SDM (Reference 20) for simply supported ends is:

$$f = \frac{.985 \times 9.6 \times 10^4 \, \delta}{25}$$

$$f = 3775 \, \delta \text{ cps}$$

From Reference 9, the critical time t_c is:

$$t_c = \frac{1}{4 \times f} = \frac{1}{4 \times 3775 \, \delta}$$

Equating the impulse required to yield the panel and the critical impulse gives:

$$I_c = I_y = \frac{\delta y}{c} = P_y t_c$$

Now P_y is the reflected peak yield overpressure of the panel. Yielding of the panel is considered a failure. 1.5 time the maximum anticipated reflected peak overpressure (p_r) must be $\leq P_y$ to maintain a positive margin of safety.

$$P_y = P_u = 1.5 \times p_r = 1.5 \times 31.5 = 47.25 \text{ psi}$$

$$\delta = \frac{P_y \, t_c \, C}{\delta y} = \frac{P_y \, C}{4 \times 3775 \, \delta \, \delta y}$$

$$\delta^2 = \frac{P_y \, C}{4 \times 3775 \, \delta y} = \frac{47.25 \times 16470 \times 12}{4 \times 3775 \times 143,600}$$

$$\delta^2 = .0043$$

$$\delta = .065 \text{ in.}$$

A doubler thickness of .065 in. is required to withstand a zone 8 howitzer blast.

GROUND FIRING AZIMUTH ANGLE REQUIRED TO PREVENT BLAST DAMAGE TO AFT FUSELAGE

AAWS-CH-47C

Skin - 2024-T3 Al. Alloy (CLAD)

t = Skin Thickness = .025 In.

Max. Overpressure aft fuselage can support

$$I_c = \frac{t \, \sigma_{yc}}{c} \qquad\qquad I_A = 1.5 \, P_D \times t_c$$

$$P_D = \frac{t \, \sigma_{yc}}{1.5 \, c \, t_c} = \frac{.025 \times 143600}{1.5 \times 16470 \times .003 \times 12}$$

$\underline{P_D = 4.04 \text{ Psi}}$ (Max. Allowable free-space overpressure for present skin)

Required gun azimuth position to prevent an overpress. of the aft starb'd fuselage skin is: = 150°

171

ESCAPE HATCH WINDOW PLEXIGLAS DOUBLER ANALYSIS

Drawing No. 114S-2721

Material Properties from Lockheed Stress Memo No. 124.

Plexiglas II Solid

$E \quad = 4.5 \times 10^5$ psi

$F_{tu} = 10.3$ ksi

$F_{cu} = 17.0$ ksi

$F_{bu} = 16$ ksi

$F_{su} = 9.0$ ksi

$r \quad = .35$ (Poisson's ratio)

$. \quad = .0\text{?} \; lb/in.$

The ultimate allowable design stress   ension is

$F_{uA} = 2/3 \times 10300 - 6,900$ psi

Pilot escape hatch door strength as determined from tests at Boeing-Vertol, Drawing No. 114S-1713. Pane was loaded without failure to 1.2 psi,

$t = .187$ in.

From Roark, Pg. 246 (Reference 21)

$$\text{Coef.} = k = \frac{p \; b^4}{Et \; 4} = \frac{1.2 \times 19^4}{4.5 \times 10^5 \times .187^4}$$

$k = 284$

$$\frac{S_u b^2}{Et^2} = 72.5$$

$$S_a = 72.5 \; \frac{Et^2}{b^2} = \frac{72.5 \times 4.5 \times 10^5 \times .187^2}{19^2}$$

$S_a = 3,160$ psi (test substantiated under static loading)

172

Dynamic Stress Analysis of Circular Fuselage Escape Hatch Doubler

Applied peak reflected overpressure based on a zone 8 charge,

$w_1 = 20.9$ psi

$w_{ave} = 17.0$ psi

$w_2 = 15.3$ psi

21.0 in dia

P_L = 17 psi (limit)

P_u = 1.5 x 17 = 25.5 psi (ultimate)

$F_{u(all)}$ = 6,900 psi

Assume a dynamic coefficient of 2.0 for plastics.

Required doubler thickness without a stiffener using design allowable of $F_{u(all)}$ = 6,900 psi

Stress formula from Roark, Pg. 216, case no. 6 (Reference 21),

$$S_{r(max)} = \frac{3W}{4 \cdot t} \qquad W = P_u \cdot r$$

$S_r = F_{u(all)}$ = 6,900 psi ($F_{u(all)}$ dynamic = 2 x 6900)

P_u = 25.5 psi

r = 10.5 in.

$$t = \sqrt{\frac{3 \times P_u \times r}{4 \times F_{u(all)} \text{ dyn.}}} = \sqrt{\frac{3 \times 25.5 \times 10.5}{4 \times 2 \times 6900}}$$

t = .39 in.

Required doubler thickness without a stiffener using test allowable of S_a = 3,160 psi.

$$t = \sqrt{\frac{3 \times 25.5 \times 10.5}{4 \times 2 \times 3160}}$$

t = .58 in.

Pilot Escape Door Doubler Analysis

Applied peak reflected overpressure at panel is

$$P_L = 5.8 \times 2 = 11.6 \text{ psi}$$

Ultimate

$$P_u = 1.5 \times 11.6 = 17.4 \text{ psi}$$

Allowable stress $F_{u(all)} = 6,900$ psi

Allowable dynamic stress $= 2 \times 6,900$ psi

Required doubler thickness

$$t = \sqrt{\frac{2 \ F_{u(all)} \ b}{72.5E}} = \sqrt{\frac{2 \times 6900 \times 19^2}{72.5 \times 4.5 \times 10^6}}$$

$$t = .39 \text{ in.}$$

ROTOR BLADE SPAR STRESSES DUE TO MUZZLE BLAST

The ultimate maneuver stresses were calculated at six critical stations to include the increase in stress caused by muzzle blast. A 1.5 ultimate factor is included in this stress. The maximum stress was 13,500 psi attained at $x/R = 0.187$. This stress level yields a margin of safety (MS) of

$$MS = \frac{\sigma_{cu}}{\sigma} - 1 = \frac{150,000}{135,000} - 1$$

$$MS = +0.11$$

The additional moment per inch at the spar-to-box attachment due to a uniform pressure of 1.2 psi applied to the box is

$$\Delta M = 1/2 \ (\text{chord} - \text{spar})^2 \ \Delta P_{blast} \ (1.5)$$

$$= 1/2 \ (25.25 - 7.1)^2 \ (1.2)(1.5)$$

$$= 300 \ \text{in-lb/in.}$$

The allowable ultimate compression stress is $\sigma_{cu} = 38,200$ psi (Reference 22). At $x/R = .95$, the maximum maneuver flight air pressure loading is a maximum and causes a compression stress of $\sigma = 26,470$ psi. The stress due to the blast is

$$\sigma_{blast} = \frac{\Delta M}{d \times t \times 1}$$

where

d = distance between top and bottom skins

t = skin thickness

$$\sigma_{blast} = \frac{300}{(2.52)(.018)} = 6540 \ \text{psi}$$

The margin of safety is therefore reduced from MS = +.44 to:

$$MS = \frac{\sigma_{cu}}{\sigma} - 1$$

$$= \frac{38,200}{(26,470 + 6540)} - 1$$

$$MS = +0.16$$

A blast pressure which would cause a MS = 0 would be:

$$P_{blast} = \frac{2 \Delta M \, d \, t}{(chord - 7.1)^2} = \frac{2(38,200 - 26,470)(2.52)(.018)}{(25.25 - 7.1)^2 \, 1.5}$$

$$= 3.23/1.5$$

$$P_{blast} = 2.09 \text{ psi}$$

While this small pressure implies a small margin, the above calculation is based on firing during a maximum maneuver condition and is therefore extremely conservative.

The spar stress fatigue limits (M - 3σ) have been calculated by adding the stresses due to firing to the maximum level flight stresses at the critical blade stations. These calculations show that the increases in the stress levels at these critical blade stations due to the pressure blast do not create any fatigue problems at the stations indicated. Calculations of the effects of the muzzle blast on the fatigue strength of the blade aerodynamic fairing have also been performed for the critical blade section. The additional alternating moment per inch due to the blast pressure at x/R = .95 is

$$\Delta M = 100 \text{ in-lb/in.}$$

The maximum level flight alternating moment is 108 in-lb/in. (Reference 19), and the fatigue endurance limit is 243.6 in-lb/in. The fatigue limit is therefore not exceeded, and the margin of safety is:

$$MS = \frac{243.6}{208} - 1$$

$$MS = +0.17$$

APPENDIX V

DETAIL WEIGHT SUBSTANTIATION

		Weight lb
1. Crash Resistant Fuel System (Ref. ECP 626)		586
2. Beam Attachment Forgings (Aluminum)		25
Forward (4 req'd) 20 cu in. @ 0.1 lb/cu in.	8	
Aft (4 req'd) 30 cu in. @ 0.1 lb/cu in.	12	
Attaching Hardware	5	
3. Frame Reinforcements (5 req'd) (aluminum)	(12)(5)	60
1,820 sq in. x 0.06 in. thick @ 0.1 lb/cu in.	11	
Rivets, etc.	1	
4. Muzzle Blast Doublers (2 req'd)	(55)(2)	110
Add aluminum plates 5,201 sq in. x 0.065 in. thick @ 0.1 lb/cu in.	34	
Upper Sliding Side Window, Double Thickness of Glass 1.93 lb x 2	4	
Lower Fixed Side Window, Double Thickness of Glass 3.86 lb x 2	8	
Escape Hatch Window, Double Thickness of Glass 1.4 lb x 2	3	
Attaching Hardware Including Rubber Snubbers	6	
5. Forward Hoist		96
Lateral Beam (Aluminum) 1.5 sq in. x 150 in. long x 0.1 lb/cu in	22.5	
Vertical Support (Aluminum) 1.5 sq in. x 88 in. long x 0.1 lb/cu in.	13.2	
Diagonal Brace (Aluminum) 1.0 OD x 0.08 in. wall x 90 in. long x 0.1 lb/cu in.	2.2	
Gusset - Main Boom (Aluminum) (2 req'd) 170 sq in. x .125 in. thick x 0.10 lb/cu in. x 2	3	
Fitting - Bottom Vertical Est.	1	
Fitting - Diagonal Vertical Est.	1	
Attaching Hardware	5	
Hydraulic Winch, Breeze BL 4600	41	
Winch Control Panel, Valve, Pump, Electrical Connectors, etc.	7	
6. Aft Hoist - Same as Forward		96

			Weight lb

7. **Gun Support Platform** — 155
   - Lateral Beam (Aluminum) (6 req'd) — 12
     - 60 cu in. x 0.10 lb/cu in. x 6
   - Spokes (Aluminum) (5 req'd) — 22
     - 44 cu in. x 0.1 lb/cu in. x 5
   - Ring Gear (Steel) — 42
     - 14) cu in. x 0.3 lb/cu in.
   - Walking Platform Screen — 41
     - 8,221 sq in. x 0.005 lb/sq in.
   - Attaching Hardware — 13
   - Screw Jack Est. — 25

8. **Forward Lateral Gun Support** — 586
   - Lateral Main Beam (Steel) — 77
     - 257 cu in. x 0.3 lb/cu in.
   - Lateral Excension Beam (Steel) — 469
     - 1,562 cu in. x 0.3 lb/cu in.
   - Bearings, Stops, etc. — 15
   - Attaching Hardware — 25

9. **Aft Lateral Gun Support** — 1,328
   - Main Beam (Steel) — 265
     - 883 cu in. x 0.3 lb/cu in.
   - Aft Lateral Extension (Steel) — 1,023
     - 3,410 cu in. x 0.3 lb/cu in.
   - Bearings, Stops, etc. — 15
   - Attaching Hardware — 25

10. **Longitudinal Beams – Aluminum** — 48
    - Forward (2 req'd) — 19
      - 95 cu in. x 0.1 lb/cu in. x 2
    - Aft (2 req'd) — 19
      - 95 cu in. x 0.1 lb/cu in. x 2
    - Hardware — 10

11. Tie-Down Dogs and Clamps, Est. — 25

12. Electric Motors and Controls, Est. — 60

13. Gun Fire Controls, Est. — 50

14. Ammunition Loaders, Est. (each) — 200

15. Ammunition Racks and Cans (Steel) — 140
    - 28 in. diameter x 36 in. long @ equivalent
    - thickness = 0.13 in. (each)

16. Ferry Fuel Tank - from extended range studies: — 600
    - Tank, 600 gal capacity — 497
    - Plumbing — 28
    - Pallet, Tie-Downs, etc. — 75

		Weight lb

17. Rotor Brake - from CH-47C Australian Proposal: 51
    Brake   29
    Motor Pump   20
    Remove Solenoid and Valve   -2
    Miscellaneous   4

18. Ammunition (each)   37
    Projectile   33
    Charge (zone 5)   1.4
    Case   2.6

19. Howitzer - Left Side   3,751
    Ref.: Preliminary draft, technical manual,   3,615
    operations and organizational maintenance
    manual, howitzer light, towed, 105 soft
    recoil, XM204, dated March 1970

    Add 30 in. to barrel, Est.   136

20. Howitzer - Right Side   3,200
    Howitzer Left Side (above)   3,751
    Remove: Transverse mechanism   -273
           spindle, brakes and wheels   -140
           Sections of baseplate and   -138
             carriage, Est.

TEST FIRING OF MODEL HOWITZER
TO PRODUCE MUZZLE BLAST FIELDS

The feasibility of modeling the XM204 howitzer for the genera-
tion of a scaled muzzle blast field was investigated. This
effort was to provide for subsequent testing of Boeing's fully-
instrumented 1/11-scale model of the Chinook CH-47C helicopter
in a model blast environment. Determination of the effects of
muzzle blast on rotor and airframe loads by firing a model
weapon in the proximity of the model helicopter would be a
valuable step in the progression toward full-scale airborne
testing of the helicopter-mounted howitzer. Results summarized
in Figure 62 show that modeling is feasible and can produce
correlation with full scale within 0.5 psi.

SCALING TECHNIQUES

Fabrication of the 1/11-scale model of the XM204 105mm howitzer
was accomplished by use of Hopkinson scaling techniques. These
replica model laws, discussed in Reference 23, are presented in
Table XX. In brief, all linear dimensions scale as the geomet-
ric length ratio (11:1). Mass, weight, and energy scales as
the cube of the geometric length ratio (1331:1), and blast
pressure (measured at scaled distances) and projectile velocity
of the model have a one-to-one relationship with that of the
full-scale weapon.

Table XXI lists the pertinent parameters of XM204 howitzer and
the corresponding parameters of the model weapon as determined
by application of the replica modeling laws. The scaling laws
would dictate the scaling of the propellant on a weight basis
with the model rounds loaded with 1/1331 times the weight of
propellant in its full-scale equivalent if the model propellant
had the same specific energy content as the full-scale
propellant. Data obtained from the manufacturer (Hercules) of
the model propellant (Unique) showed that its heat of explosion,
a measure of energy content, was 1,145 calories per gram as
contrasted with 700 calories per gram for the M-1 propellant
used in the 105mm rounds. Propellant scaling therefore had to
take energy into account; and the values of model propellant,
shown in Table XXI, used a scale factor equal to $700/1145$ x
$1/1131 = 4.59$ x 10^{-4}. The model propellant weight equivalent
to the 2.82-pound zone 7 charge is therefore:

$$2.82 \times 4.59 \times 10^{-4} \times 7000 = 9 \text{ grains}$$

Model Weapon

Application of the 1/11-scale factor to the 105mm howitzer

LEGEND

—— ● EXPECTED

—— △ TEST DATA (INTERPCLATED)

Figure 62. Comparison of Predicted and Model Overpressure
Measurements for 2.82 Pounds (Zone 7) of Equivalent
Full-Scale Charge

TABLE XX. REPLICA MODEL (HOPKINSON) SCALING LAWS

Parameter	Scale Factor
Barrel Length	λ
Bore	λ
Measurement Distances	λ
Projectile Mass	λ^3
Propellant Weight	λ^3
Blast Pressure (Measured at Scaled Distances)	1.0
Projectile Velocity	1.0

λ = Geometric Length Ratio

TABLE XXI. MODEL VERSUS FULL-SCALE WEAPON PARAMETERS

Parameter	XM204	Model
Barrel Length	150 in.	13.60 in.
Bore	105mm	.375 in.
Projectile Weight	33 lb	173 grains
Propellant Weight	(scaled on an energy basis)	
Charge Zone		
7	2.82 lb	9.03 grains
6	1.91 lb	6.15 grains
5	1.38 lb	4.42 grains
4	1.01 lb	3.23 grains

182

resulted in a model weapon bore of .375 caliber which is a
standard available barrel. A 1917 model Eddystone barrel was
obtained and cut to 11.75 inches in length. The barrel was
then married to a Remington-Essington action and the trigger
mechanism modified for lanyard pull operation with appropriate
safety devices added. Figure 63a shows the model weapon
on the test mount.

Ammunition

Modeling of the ammunition necessitated foreshortening and
counterboring the nose of the projectile to attain the required
scaled weight of 173 grains. As the program goal was to build
a replica model "blast-maker," degradation of projectile
velocity caused by this unorthodox nose shaping was of no con-
cern. Similarly, projectile length was not scaled. Figure 63b
is a photograph of the model round.

MEASUREMENT TECHNIQUES

Testing included acquisition of blast data and evaluation of
various types of transducers. The test setup for measurement
of blast overpressures was essentially the same for all trans-
ducer types used. As two-channel recording was available,
only two transducers could be used at any time. Transducer
location was measured in calibers (actual distances divided by
the diameter of the weapon's bore). In this manner, compara-
tive measurements at a given number of calibers could be made
for model and full-scale weapons.

In all measurements, transducers were located in a plane per-
pendicular to, and 14.4 calibers forward of, the muzzle and at
distances of from 10 to 50 calibers from boresight of the
weapon. The selection of 14.4 calibers forward was made to
locate the measurements along a radius from the center of the
blast.

A sand-filled five-gallon can with a cardboard lid was used as
a bullet catcher and was located approximately 10 feet in front
of the weapon.

A microphone was positioned nearer to the muzzle than either
transducer at a location experimentally determined for each
test setup to provide triggering for an oscilloscope. A Polar-
oid oscilloscope camera was employed for data recording.

Microphone transducers were fed directly into the oscilloscope
input, as were the Pitran pressure transducers. The SWRI pan-
cake transducers required the use of charge amplifiers prior to
signal application to the oscilliscope. Kulite pressure trans-
ducers required use of a wide band amplifier which also provided
a buffering function.

a

b

Figure 63.   (a)   Scale Model Weapon on Ballistic Test Mount
             (b)   Model Ammunition Showing Projectile Modifications

184

Muzzle velocity tests were performed in the Boeing test range
(Figure 64) by firing through screens 25 and 35 feet from the
muzzle. A clock started as the projectile passed a photocell in
the first screen and was stopped by a similar one in the second
screen. Velocity was determined by dividing the fixed distance
by the measured time. Figure 65 is a plot of velocity test data.

TESTING

First Test Series

The initial test series was conducted on April 24, 1972, with
an objective of obtaining model blast pressure data at loca-
tions of 20, 30, 40, and 50 calibers off boresight which would
correlate well with XM204 data and thus validate the model
weapon. Figures 66 to 69 show typical oscilloscope traces.

Of the 11 rounds of assorted charge weight fired, one was a
blank to check the test setup, two produced no data due to
faulty instrumentation, one produced abnormally high pressures
and was discounted, and the remaining five rounds produced
meaningful data and good correlation.

Figure 70 shows comparison of predicted and model overpressures
measured at 50 calibers using the microphone transducer. Test
data fell within .3 psi of predictions. Data taken at 40
calibers using microphone transducers are shown plotted on
Figure 71. Scope traces of the runs made at 11 and 14 grains
of propellant displayed blunted pressure peaks which were
apparently caused by the microphone dynamic response. Data
enhancement was effected by extrapolation of the recorded
pressure amplitude trace to provide well defined maxima for
those two data points. Relocation of these data points pro-
duced a better-shaped curve with very good correlation.

Although this initial test series produced encouraging results,
its limited number of firings and some then unexplainable
results cast doubts on the weapon's repeatability and caused
the test conclusions to be suspect. Measurements could not be
made at x/c (distance in calibers off boresight) of 20 and 30
as the predicted pressure levels exceeded the microphone trans-
ducer limitation, and the Pitran pressure transducers which
had this capability had produced the abnormally high overpres-
sures. In addition, the lower charge zone projectiles lodged
in the barrel, casting doubts on the validity of the scaling.

Initial Boeing analysis with subsequent confirmation by South-
west Research Institute determined the cause of the abnormal
Pitran transducer data to be due to the method of mounting and
the orientation of the mounting plate within the blast field.
The flat plate mount had been inadvertently positioned so as
to disturb the blast field and produce a reflected pressure

185

Figure 64. Setup For Muzzle Velocity Measurement in
Boeing-Vertol Test Range

Figure 65. Comparison of Full-Scale and Model Muzzle Velocity
Measurement

187

Figure 66. Scope Trace of 14 Grain Firing Test
Upper - Microphone Transducer at 50 Calibers
(scale: 0.36 psi/cm; 200 μ sec/cm)
Lower - Microphone Transducer at 40 Calibers
(scale: 0.46 psi/cm; 200 μ sec/cm)

Figure 67. Scope Trace of 10.1 Grain Firing Test
Upper - SWRI "Pancake" Transducer No. 14-9 at 30
Calibers (scale: 1.03 psi/cm; 200 μ sec/cm)
Lower - SWRI "Pancake" Transducer No. 25-2 at 20
Calibers (scale: 1.18 psi/cm; 200 μ sec/cm)

188

Figure 68. Scope Trace of 17 Grain Firing Test
Upper - Kulite Transducer at 40 Calibers (scale:
1.91 psi/cm; 200μ sec/cm)
Lower - SWRI "Pancake" Transducer No. 25-2 at 40 calibers
(scale: 1.18 psi/cm; 200μ sec/cm)

Figure 69. Scope Trace of 7.25 Grain Firing Test
Upper - SWRI "Pancake" Transducer No. 14-9 at 30
Calibers (scale: 1.03 psi/cm; 200μ sec/cm)
Lower - SWRI "Pancake" Transducer No. 25-2 at 20
Calibers (scale: 1.18 psi/cm; 200μ sec/cm)

Figure 70. Comparison of Predicted and Model Overpressure Measurements at 50 Calibers Off Boresight

190

Figure ... Comparison of Predicted and Model Overpressure
Measurements at 40 Calibers Off Boresight

191

wave. It was later determined that the measured reflected overpressures actually correlated well with calculations based upon the free-space (nonreflective) overpressures produced and the angle of incidence of the wave striking the mount.

With the criticality of transducer aerodynamics and orientation thus established, it was necessary to obtain transducers capable of measuring free-space overpressures without causing wave disturbance. It was ι ˙ned that Southwest Research Institute had designed and built a limited number of blast gauges for the Naval Weapons Laboratory at Dahlgren, Virginia (Reference 24), which were ideally suited for measurement of the fast rise time pressure pulses produced by small-caliber weapons. Furthermore, its pancake-shaped head, feathered periphery, and sharp edge afforded excellent aerodynamics and caused minimum wave disturbance. The Naval Weapons Laboratory (Dahlgren) readily agreed to provide four of these pancake units, but they cautioned that their experience with the gauges had not been satisfactory due to a problem with noise. Dahlgren advised that Kulite transducers had produced excellent results for them and suggested this type of gauge be used. Two of the Kulite gauges were purchased and installed in mounts patterned after the SWRI gauges. It was planned to compare performance of the Kulite and SWRI gauges in the second series of test firings.

Repeatability would be verified in the second test series by multiple firings for given charge weights at specific transducer locations, as contrasted with the single firing for each condition performed in the initial tests.

The problem of projectiles lodging in the barrel was analyzed, and its suspected cause was the failure to scale the engraving surface of the projectile. The length of the engraving surface of the model projectile was considerably greater than that dictated by application of the scale factor to the full-scale projectile. The resulting increase in engraving, it was theorized, resulted in the model projectile lodging in the barrel for low charge zones. It was planned that the second test series would employ some projectiles with reduced engraving for low zone firings. Figure 72 shows comparison of the standard and reduced engraving of the model projectile.

Second Test Series

The second series of test firings was performed on June 29. Fifty rounds were fired in the effort to validate the weapon as a true blast maker capable of producing overpressures at 1/11 scale that of the XM204. Of the 50 rounds fired, four were blanks to assist in test setup, five rounds produced no data due to loss of the electronic trigger signal for the oscilloscope, and one round (without reduced engraving)

192

(a) STANDARD ENGRAVING

(b) REDUCED ENGRAVING AREA

Figure 72.   Geometry of Model Projectile

lodged in the barrel. The remaining 38 rounds, with the exception of several odd data points, produced repeatable data which showed good correlation with predicted levels of over-pressure.

The first number of runs was designed to compare the SWRI pancake transducers with the Kulite transducers. One of each type was located at x/c = 40. Figure 73a is a photograph of the test setup.

Transducers were oriented with their knife edge in the horizontal plane to enable the incident pressure wave to roll across them with minimal disturbance. This arrangement, suggested by William Burgess of Dahlgren, is superior to positioning in the vertical plane since aiming of the knife edge at the center of the blast is less critical. A microphone transducer used to provide a trigger for the oscilloscope can also be seen in the photograph.

During the course of data reduction and analysis of this second test series, it became increasingly apparent that the SWRI gauges were out of calibration. Attempts to calibrate them with regular calibration equipment, as well as attempts to build a simple calibrator, proved fruitless due to the rapid rise times necessary for the calibrating shock pulse. Once again, Dahlgren cooperated by providing the special calibrator which SWRI had built for these pancake transducers. Figure 74 is a photograph of the calibration test setup used. Shown are transducers, calibrator, charge amplifiers, oscilloscope and ancillary equipment. After successful calibration of the transducers, data taken with two SWRI transducers correlated with each other and reduction and analysis were continued.

Figure 71 is a plot of the overpressures measured at 40 calibers by SWRI pancake gauge 25-2 for 11 rounds fired at 7.25, 10.1, 14.8, and 17 grains of propellant weight. Repeatability proved to be quite good, and results correlate well with the predicted curve.

The results of the Kulite transducer measurements proved to be somewhat disappointing due to the presence of hash or ringing in the resulting scope traces (see Figure 68). As it could not be determined where in these traces to read the true over-pressure levels, both the maxima and minima of all Kulite measurements were plotted and can be seen as a shaded band in Figure 75. The lower boundary of the band appears to correlate well with the predicted levels, but use of these minima would be purely arbitrary and without scientific foundation. Similar tests run with the second of the Kulites produced similar results. The ringing is believed to be caused by mechanical resonances in the transducer mount. Subsequent calibration of

194

(a) Free Space Overpressure Measurement

(b) Effects on Model Skin Panel

Figure 73. Test Setup for Measurement of Muzzle Blast

195

Figure 74.   Test Setup for Transducer Calibration

196

Figure 75. Comparison of Predicted and Model Overpressure Measurements at 40 Calibers Off Boresight Using Projectiles With Reduced Engraving

197

the Kulites in a fixture which restrains the mount produced a clean oscilloscope trace without hash. While the pressure-sensitive crystals in the SWRI transducers were solidly potted in their mounts, Boeing had refrained from this approach, fearing that the epoxy-curing heat might damage the Kulite pressure crystals.

Testing was performed with SWRI transducers 14-9 and 25-2, located at x/c's of 30 and 20 calibers, respectively. Figure 76 is a plot of overpressures measured at 30 calibers for various propellant weights. Good repeatability is in evidence; and correlation, which proved almost as good as at 40 calibers, was within .4 of a psi at zone 7 and even closer agreement at zone 6. When projectiles with reduced engraving were fired and measured at this same location, not only did the low charge zones successfully exit the barrel, but correlation was much improved. Figure 77 shows the results of these measurements.

Measurements taken with transducer 25-2 located at 20 calibers are shown plotted in Figure 78. Again, repeatability was excellent. Correlation with predictions was still good; however, when projectiles with reduced engraving were used (Figure 79), overpressures fell below predictions rather than above as in previous runs. Correlation was still within .5 psi.

Tests run at 10 calibers using SWRI pancake transducer 14-9 are shown in Figure 80. Results appear to run true to form, that is, progressively worsened correlation as measurement distances are decreased while repeatability is still good.

A summary curve, Figure 62, was then plotted showing comparison of predicted and interpolated test data for transducer locations of 10, 20, 30, and 40 calibers off boresight for 2.82 (zone 7) pounds of equivalent full-scale charge. Similarly, summary curves, Figures 81 and 82, were plotted for 3.23 and 3.8 pounds of equivalent full-scale charge, respectively. In all cases, the correlation between predicted and measured proved to be quite good.

PULSE DURATION

No data is presently available for time duration of the muzzle blast produced by the XM204 to enable comparison with measurements made during model testing. However, measurements made at Dahlgren (Reference 25) with a standard 105mm howitzer indicate that an average duration of 1.88 milliseconds was measured at approximately 20 calibers off boresight and in the plane of the muzzle. In addition, an average duration of 2.39 milliseconds was measured at approximately 40 calibers off boresight.

198

Figure 76. Comparison of Predicted and Model Overpressure Measurements at 30 Calibers Off Boresight

199

Figure 77. Comparison of Predicted and Model Overpressure Measurements at 30 Calibers Off Boresight Using Projectiles With Reduced Engraving

Figure 78. Comparison of Predicted and Model Overpressure Measurements at 20 Calibers Off Boresight

201

Figure 79. Comparison of Predicted and Model Overpressure
Measurements at 20 Calibers Off Boresight Using
Projectiles With Reduced Engraving

202

Figure 80. Comparison of Predicted and Model Overpressure
Measurements at 10 Calibers Off Boresight

Figure 81. Comparison of Predicted and Model Overpressure Measurements for 3.23 Pounds Equivalent Full-Scale Charge

Figure 82. Comparison of Predicted and Model Overpressure Measurement for 3.8 Pounds of Equivalent Full-Scale Charge

Time duration was, in many cases, difficult to estimate from the scope traces of the model tests. However, an average of the 24 measurements made at 20 calibers yielded a time duration of 165 microseconds which, when scaled up by the factor of 11, equaled 1.82 milliseconds (only .06 milliseconds less than the full-scale Dahlgren data). The distribution appeared Gaussian, and the range varied from -.94 milliseconds to +.82 milliseconds from the arithmetic mean.

A plot of 15 measurements made at 40 calibers (the results of the ambiguous Kulite readings were not used) yielded a distribution curve which was somewhat skewed at the upper end. The average value of blast duration was 197 microseconds which scaled up to 2.17 milliseconds (as compared to 2.39 milliseconds for full-scale data). The distribution ranged from -.97 milliseconds to +.69 milliseconds of the arithmetic mean.

CALCULATIONS OF PREDICTED OVERPRESSURES

As an example of the method of predicting overpressures, calculations are presented for finding the predicted overpressure at $x/c = 40$ and $z/c = 14.4$ for a zone 7 charge fired from an XM204 howitzer with a 30-inch extended barrel. Calculations are based on Reference 6 with muzzle velocities obtained verbally from Rock Island Arsenal.

$$\text{Overpressure } (\Delta P) = \frac{KE_T}{C^2 L}$$

where

$\quad C = 4.16$ in. (bore diameter)

$\quad L = 12.5$ ft (barrel length)

$\quad E_T = $ thermal energy (ft-lb)

$\quad K = $ dimensionless isobar constant

Using Figure 4 of Reference 6, K is found to be 2.75×10^{-4}.

$$\Delta P = \frac{2.75 \times 10^{-4} \ (E_T)}{(4.16)^2 \ (12.5)}$$

$$\Delta P = 1.27 \times 10^{-7} \ (E_T)$$

where

$$E_T = E_A - \frac{E_P}{.85}$$

and

E_A = total energy available in propellant

$\quad = 1.4 \times 10^3 \, (H_C)(W_C)$

where

$H_C = 700$ cal/gram (for 105mm propellant)

$W_C = 2.82$ lb (zone 7 charge)

$E_A = 1.4 \times 10^3 \, (700)(2.82)$

$E_A = 2.76 \times 10^6$ ft-lb

E_P (kinetic energy of projectile) $= \frac{M_P \, (V_O)^2}{2}$

where

M_P = projectile mass (slugs)

$V_O = 1700$ ft/sec (zone 7 muzzle velocity)

$E_P = \frac{1.025(1.7 \times 10^3)^2}{2} \qquad E_P = 1.48 \times 10^6$ ft-lb

so that

$$E_T = E_A - \frac{E_P}{.85}$$

$E_T = 2.76 \times 10^6 - \frac{1.48 \times 10^6}{.85}$

$E_T = 1.02 \times 10^6$ ft-lb

and

$\Delta P = (1.27 \times 10^{-6})(1.02 \times 10^6)$

$\Delta P = 1.3$ psi

CONCLUSIONS

Modeling of the XM204 howitzer to produce scaled muzzle blast

207

fields is feasible at 1/11 scale. Some further experimentation with propellant weight and projectile engraving would be in order as these parameters represent the greatest source of error. To a lesser degree, instrumentation and test setup is felt to be another error source. In model scale, the size and relatively blunt shape of the transducers raise concern. An isobar plot of XM204 overpressures shows that large pressure gradients exist at the close-in ranges, so a slight error would cause a fair percentage change in overpressure measurement. The knife edge of the transducer, while keen enough to slice into the pressure wave without perturbation at full-scale dimensions, is rather blunt at model dimensions.

It is felt that the SWRI gauges are satisfactory for model blast testing. The noise reported by Dahlgren was not experienced, and this is attributed to the use of shorter leads of Microdot cabling. Cable runs between transducers and charge amplifiers were limited to 10 feet. More suitable mounting provisions and retesting would be required before the Kulite transducers could be considered usable.

APPENDIX VII

TESTING OF MODEL STRUCTURAL PANEL WITH MODEL HOWITZER
TO EXPLORE DYNAMIC EFFECTS OF MUZZLE BLAST

An instrumented model of a structural panel was fabricated
and tested for response to muzzle blast to explore how well
peak panel dynamic stresses due to blast can be predicted.
The muzzle blast field was caused by a model howitzer. The
model was an 1/11-scale structural representation of the most
critical panel of the CH-47C for muzzle blast effects. The
location of the scaled test panel relative to the muzzle of
the model weapon is shown in Figure 83. It was found that if
the panel is considered simply supported rather than clamped,
and if the stress concentration at the edge of the panel is
properly accounted for, the experimental findings can be ade-
quately predicted.

The model panel was made of a readily-available aluminum sheet-
stock which was close to the desired model panel thickness.
Number 3003 aluminum alloy with H27 temper and a yield strength
(Fty) and ultimate strength (Ftu) of 27,000 psi and 29,000 psi,
respectively, was selected. Chemical milling was employed to
reduce the .005-inch thickness of the sheetstock to the scaled
value of .0036 inch. A .45-inch x 1.75-inch window (represen-
ting full-scale panel dimensions of 5 inches x 19.25 inches)
was cut in a relatively thick aluminum plate to simulate the
structure supporting the aircraft skin. The model skin was
then cemented in place across the window and a strain gauge
cemented to the skin. This assembly can be seen in Figures 84a
and 84b. A Pitran pressure transducer was mounted on the
supporting plate near the model skin to record reflected pres-
sures.

To assure that the chemical milling did not reduce the strength
of the model skin material, samples of milled and unmilled
material were tested with a Siemens Microhardness Tester and
found to have equal hardness. The assembly was then mounted on
a wooden beam and positioned to simulate the aircraft with the
panel approximately five calibers forward of the muzzle and
12 calibers parallel to the line of fire of the model weapon.
Figure 73 shows this test setup.

The test was designed to demonstrate the firing of a zone 5
modeled charge (simulating the air-to-ground mode) without
damaging the model panel. The model rounds used 7.25 grains
of propellant. As mentioned in the model weapon discussions,
it was found that the energy content of the model propellant
was such that this model charge actually modeled a full-scale
charge of 2.26 pounds which falls between zones 6 and 7.

Figure 83. Scale Model Skin Panel and Supporting Structure

(a)   Top View Showing Strain Gauge and Pitran Pressure
      Transducer Mounted

(b)   Bottom View Showing Window in Panel Support Plate

Figure 84.   Scale Model Skin Panel

Employing the formulae in the Salsbury report for general blast field solution, Reference 6, and using the full-scale muzzle velocity determined by use of the curve shown in Figure 65, a free-space blast overpressure of 5.5 psi was predicted for the geometry of this test setup. At this level of overpressure, the blast wave, which st·ikes the panel at a nearly-normal angle of incidence, experiences a reflection factor of 2.3, resulting in a reflected overpressure of 12.7 psi.

Using similar analysis to that shown for calculating protective panel doubler thickness, but using the lower yield strength of the model panel material, the dynamic yield strength of the model material is found by the formula:

$$\frac{\sigma y_2}{\sigma y_1} = \frac{Fty_2}{Fty_1}$$

$$\sigma y_2 = 143,600 \times \frac{27,000}{39,000}$$

$$\sigma y_2 = 99,300 \text{ psi}$$

where

σy_1 = dynamic yield strength of full-scale panel material

σy_2 = dynamic yield strength of model panel material

Fty_1 = static yield strength of full-scale panel material

Fty_2 = static yield strength of model panel material

The critical impulse for yield becomes:

$$I_c = \frac{t \sigma y}{C}$$

$$I_c = \frac{.0003 \times 9.93 \times 10^4}{16,470}$$

$$I_c = 1.81 \text{ psi-milliseconds}$$

where

t = panel thickness (ft)

C = velocity of sound in aluminum (fps)

212

If the panel is considered to be clamped, its natural frequency is equal to:

$$fo = .985 \ K \ \frac{\delta}{b^2}$$

$$fo = \frac{.985 \times 21.76 \times 10^4 \times .0036}{(.45)^2}$$

$$= 3800 \ cps$$

where

δ = panel thickness (in.)

b = width (in.)

$.985$ = factor for aluminum

K = 21.76×10^4 for clamped panels

Its period

$$T = \frac{1}{3800} = 263 \times 10^{-6} \ \text{seconds}$$

The critical time

$$t_c = \frac{263 \times 10^{-6}}{4} = 66 \times 10^{-6} \ \text{seconds}$$

The maximum overpressure

$$\Delta p = I_c / t_c$$

$$\Delta p = \frac{1.81 \ psi - ms}{.066 \ ms}$$

$$\Delta p = 27.4 \ psi$$

It was therefore predicted that the model panel could withstand the reflected pressure of 12.7 psi with a safe margin. However, firing of the weapon actually resulted in panel yield. A close inspection of Figure 73 will show a faint outline of the hidden window in the support plate, resulting from panel yield. Some failure of the cement was also detected.

It was then theorized that the error lie in considering the panel to be clamped. If it were simply supported, the natural frequency would be:

213

$$fo = .985 \ K \ \frac{t}{b^2}$$

where

$$K = 9.6 \times 10^4 \text{ for simply supported panels}$$

$$fo = \frac{.985 \times 9.6 \times 10^4 \times .0036}{(.45)^2}$$

$$fo = 1675 \text{ cps}$$

Its period

$$T = \frac{1}{1675} = .597 \text{ milliseconds}$$

The critical time

$$t_c = \frac{.597}{4} = .149 \text{ milliseconds}$$

And the allowable ∆p overpressure = $\frac{1.81}{.149}$ = 12.1 psi

Therefore, were this truly a simply supported panel, test
results of yield would correlate with predictions. In actuality,
the panel most likely falls somewhere between the simply sup-
ported and clamped configurations. However, it is believed
that the added mass of the strain gauge reduced the natural
frequency of the panel (and its resulting critical time, t_c)
just enough that when added to the reduction attributed to the
method of support, resulted in a reduction of allowable over-
pressure to below that produced by the weapon.

The measurement of pressure by the Pitran gauge proved disap-
pointing as its readings of 3.2 psi were far below the predicted
level of reflected pressure. The scope trace was indistinct
and difficult to interpret, and it can only be assumed that
either the gauge was faulty or the calibration of the system
was in error.

Strain gauge measurements obtained appear to be believable with
an indicated strain (in the area of the gauge) of .00243 in./in.
This is not the strain required for yield which is calculated
as:

$$\varepsilon = \frac{\sigma y}{E}$$

214

$$= \frac{99,300}{10.5 \times 10^6}$$

$\epsilon = .00945$ in./in.

The difference in these two values apparently results from the positioning of the gauge away from the edge of the panel. It is reasonable to assume that the actual strain at the edges of the panel, where the greatest stress concentration occurs, is easily four times that measured in the area of the gauge. It is therefore understandable that yield occurred under these conditions.

It is concluded that model testing is a valuable tool in predicting full-scale responses to muzzle blast. Care must be taken, however, in design of the instrumentation and in the determination of the edge conditions of the panel.

APPENDIX VIII

PERFORMANCE SUBSTANTIATION

HOVER DOWNLOAD ESTIMATE

An estimate of the incremental increase in hover download of the Aerial Artillery configuration over the standard CH-47C is presented below.

Download, in terms of total rotor thrust, is expressed as follows:

$$\frac{DL}{T} = \frac{C_{D_V} A_V \left(\frac{\rho}{2}\right) v^2}{2 A \rho v^2_{IND}} = \frac{C_{D_V} A_V}{4 A} \left(\frac{v}{v_{IND}}\right)^2 = \frac{C_{D_V} A_V}{8 \pi R^2} \left(\frac{v}{v_{IND}}\right)^2$$

where: DL = hover download, lbs

   T = total rotor thrust, lbs

   C_{D_V} = vertical drag coefficient of fuselage section

   A_V = exposed vertical drag area, sq. ft.

   ρ = mass density of air, slug/ft^3

   A = total rotor disc area ($2 \pi R^2$), ft^2

   R = rotor radius, ft.

   v = actual downwash velocity, ft/sec

   v_{IND} = induced velocity from momentum theory

   $(\sqrt{T/2A\rho})$, ft/sec

The download between two locations A and B along the fuselage is:

$$\frac{DL}{T}\bigg)_A^B = \frac{\overline{C_{D_V}}}{8 \pi R^2} \left(A_V\right)_A^B \int_A^B \left(\frac{v}{v_{IND}}\right)^2$$

216

A   B

R

A_V $\overline{W}$

A   B
(20% R)   (60% R)

R

⌀   ⌀
FORWARD   AFT
ROTOR   ROTOR

The exposed vertical drag area (A_V) between locations A and B in terms of average width $(\overline{w})$ and length $(\ell 1)$ in percent of rotor radius (%R) is noted below.

$$(A_V)_A^B = (\ell 1)\ (\overline{w}) = \left(\frac{60\%R}{100} - \frac{20\%R}{100}\right)_A^B (\overline{w}) = \frac{40\%R}{100}(\overline{w})$$

The final expression for hover download between locations A and B along the fuselage is

$$\left(\frac{DL}{T}\right)_A^B = \frac{\overline{C}_{D_V}}{8\pi R^2}\ \left(\frac{40\%R}{100}\right)\ (\overline{w})\ \Big|_A^B\ \cdot\frac{v}{v_{IND}}$$

$$= \frac{\overline{C}_{D_V(\overline{v})}}{800\pi R}\left\{\left[\overline{\left(\frac{v}{v_{IND}}\right)}\ (\%R)\right]_B - \left[\overline{\left(\frac{v}{v_{IND}}\right)}\ (\%R)\right]_A\right\}$$

Figure 85 presents the downwash velocity profile developed from model rotor test data expressed in terms of integrated non-dimensional downwash velocity $[\overline{(v/v_{IND})}\ (\%R)]$ as a

217

Figure 85.   Downwash Velocity Distribution Used
for Hover Download Calculation

function of percent radius from the forward rotor centerline. The test data was obtained with a tandem rotor model having the same rotor overlap as the CH-47C helicopter.

Applying this methodology to the CH-47C aerial artillery configuration the following incremental hover download estimate is made for the dual gun installation.

$$\left(\frac{DL}{T}\right)^{B}_{A} = \frac{\overline{C}_{D_V(\overline{w})}}{(75,400)}\left\{K_B - K_A\right\}$$

$$\text{WHERE, } K = \left[\sum \frac{V}{V_{IND}} \cdot (\%R)\right]$$

Permanent Howitzer

Ref. Area	Exposed Area			$\overline{C}_{D_V}$	%R	K	$\left(K_B - K_A\right)$	$\left(\frac{DL}{T}\right)$ (%)
	A_V (sq. in.)	(in.)	$\overline{w}$ (ft.)					
A1	5230	96	4.54	.43 [1] [2]	49 77	150 370	220	.57
A2	7842	114	5.72	1.00 [1]	45 77	120 370	250	1.90
A3	1254	47	2.22	1.20 [3]	77 89	370 455	85	.30
A4	1216	94	1.08	.80 [1]	18 45	0 120	120	.14
Total : $\left(\frac{DL}{T}\right)$ for permanent howitzer								2.90

219

NOTES:

(1) Reference: "Technology Instruction Manual", W.B. Peck and C.B. Fay, Boeing-Vertol Division

(2) $\Delta C_{D_V} = .43$ added to ref. area, A_1 to account for extended platform, A_2, influence on vertical drag of adjacent fuselage

(3) Reference: "Fluid Dynamic Drag", Sighard F. Hoerner, 1965

Removable Howitzer

Ref. Area	A_V (sq. in.)	$\Delta \ell$ (in.)	$\bar{w}$ (ft.)	C_{D_V}	%R	K	$\left\{K_B - K_A\right\}$	$\left(\dfrac{DL}{T}\right)$ (%)
A_1	1170	65	1.5	.80	14.0 32.5	0 45	45	.07
A_2	8496	204	3.5	1.20	32.5 89.0	45 455	410	2.28
Total $\Delta \left(\dfrac{DL}{T}\right)$ for Removable Howitzer								2.35

The net increase in hover download of the aerial artillery configuration over the standard configuration CH-47C is summarized below:

Hover Download (Percent of Total Rotor Thrust)	
2.90	Permanent Howitzer Installation
2.35	Removable Howitzer Installation
5.25	Net Increase Over CH-47C

EQUIVALENT DRAG AREA ESTIMATE

An estimate of the increase in equivalent drag area (f_e) of the aerial artillery aircraft over the standard CH-47C helicopter is presented below.

Permanent Howitzer

Component	Quantity	A_F Projected Frontal Area (ft²)	C_D Based On Projected Frontal Area	Interference Factor	f_e Equivalent Flat Plate Drag Area (Ft²)
Gun proper, Platform and Loader	1	14.58	.8[1]	1.25	14.6
Main Support Beam	1	8.12	1.2[2]	----	9.7
Total f_e for Permanent Howitzer					24.3

Removable Howitzer

Component	Quantity	A_F Projected Frontal Area (ft^2)	C_D Based On Projected Frontal Area	f_e Equivalent Flat Plate Drag Area (ft^2)
Gun proper	1	20.10	.8[1]	16.1
Retracted Gun Wheel & Axle	1	1.90	.4[2]	.8
Main Support Beams (Fwd & Aft)	2	8.43	1.2[2]	20.2
Winch Support Beams (Fwd & Aft)	2	6.16	1.2[2]	14.8
Total Δf_e for Removable Howitzer				51.9

NOTES:
(1) Reference: NACA Memo No. 1-31-59L, "Parasite Drag Measure-
     ments of Helicopter Rotor Hubs", G.E. Churchill & R.D.
     Harrington, Feb 1959

(2) Reference "Fluid Dynamic Drag", Sighard F. Hoerner, 1965

The aerial artillery configuration has a net increase in equiva-
lent flat plate drag area (Δf_e) of 76.2 square feet over the
standard configuration CH-47C as summarized below:

Equivalent Drag Area (f_e) (FT^2)	
24.3	Permanent Howitzer Installation
51.9	Removable Howitzer Installation
76.2	Net Increase Over CH-47C